SCHEDULE OF QUANTITIES

PAVEMENT MARKING TAPE, TYPE III, 4"

LOCATION	FOOT
Adjacent to Work Area & Temporary Concrete Barrier Taper	2114
TOTAL	2114

EPOXY MARKING LINE, 4"

LOCATION		FOOT
Jobsite Deck Surface		1290
	TOTAL	1290

THERMAL SPRAYING (METALLIZING) PPC BEAM ENDS

LOCATION		SQFT
Beams next to Abutments		414
	TOTAL	414

<u>BRIDGE DECK</u> HYDRO-SCARIFICATION (1/2")

LOCATION	SQYD
Jobsite - SN.102-0041 Deck	261
TOTAL	261

WORKZONE PAVEMENT MARKING REMOVAL

LOCATION	SQFT
Adjacent to Work Area & Temporary Concrete Barrier Taper	705
TOTAL	705

PAVEMENT MARKING REMOVAL

LOCATION		FOOT
Jobsite Deck Surface		1290
	TOTAL	1290

BLAST CLEANING PPC BEAM ENDS

LOCATION	FOOT
Beams next to Abutme	nts 40
	TOTAL 40

EROSION CONTROL CURB

LOCATION	FOOT
Alongside Existing Bridge Railing	925
TOTAL	925

TEMPORARY CONCRETE BARRIER

LOCATION		FOOT
Jobsite - SN.102-0041		322
	TOTAL	322

WIDTH RESTRICTION SIGNING

	L	OCATION		LSUM
Jobsite	-	SN.102-0041		1
			TOTAL	1

BRIDGE DECK LATEX CONCRETE OVERLAY

LOCATION	SQYD
Jobsite - SN.102-0041 Deck	261
TOTAL	261

IMPACT ATTENUATORS, TEMP NRD TL 3

LOCATION	EACH
Traffic Control Standard 701321	2
TOTAL	2

RELOCATE TEMPORARY CONCRETE BARRIER

LOCATION		FOOT
Jobsite - SN.102-0041		298
	TOTAL	298

PREFORMED JOINT STRIP SEAL

LOCATION	FOOT
North Deck Joint	36
TOTAL	36

HMA SURF. REM. BUTT JOINT

LOCATION	SQYD
25' Back From Both Deck Joints	178
TOTAL	178

IMPACT ATTENUATORS, RELOCATE NRD, TL 3

LOCATION	EACH
Traffic Control Standard 701321	2
TOTAL	2

SN. 102-0041 IL.117 ovr MILL CRK. S. of US24

FILE NAME =

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SHEET NO. OF SHEETS STA.