

F F F ESP ESP NP

LOCATION OF WORK: FAP 749 (IL 133) MOULTRIE COUNTY STA 0+14.00 TO STA 1+87.40  
 FAP 749 (IL 133) DOUGLAS COUNTY STA. 1+87.40 TO STA. 61+45.00  
 FAP 749 (IL 133) S.N. 021-8055 STA 2+48.30  
 FAP 749 (IL 133) MOULTRIE COUNTY STA 0+14.00 TO STA 1+87.40  
 FAP 749 (IL 133) DOUGLAS COUNTY STA. 1+87.40 TO STA. 61+45.00  
 FAP 749 (IL 133) DOUGLAS COUNTY FLASHING BEACON

FUNDING BREAKOUT: 80% FEDERAL 20% STATE  
 80% FEDERAL 20% STATE  
 80% FEDERAL 20% STATE  
 80% ARRA 20% STATE  
 80% ARRA 20% STATE  
 50% ARTHUR 50% STATE

CONSTRUCTION TYPE CODE: 1000 1000 Y007 SFTY-2A SFTY-2A Y031-1F

CODE NO	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	40.0	0.0	40.0	0.0	0.0	0.0	0.0
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	129.0	49.0	80.0	0.0	0.0	0.0	0.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	368.0	32.0	336.0	0.0	0.0	0.0	0.0
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	14,432.0	454.0	13978.0	0.0	0.0	0.0	0.0
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	182.0	71.0	111.0	0.0	0.0	0.0	0.0
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	40.0	0.0	40.0	0.0	0.0	0.0	0.0
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	129.0	49.0	80.0	0.0	0.0	0.0	0.0
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	77.0	2.0	75.0	0.0	0.0	0.0	0.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	77.0	2.0	75.0	0.0	0.0	0.0	0.0
80500100	SERVICE INSTALLATION, TYPE A	EACH	1.0	0.0	0.0	0.0	0.0	0.0	1.0
81100500	CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA., GALVANIZED STEEL	FOOT	20.0	0.0	0.0	0.0	0.0	0.0	20.0
83057210	LIGHT POLE, WOOD, 40 FOOT, CLASS 3	EACH	2.0	0.0	0.0	0.0	0.0	0.0	2.0
85800100	FLASHER CONTROLLER	EACH	1.0	0.0	0.0	0.0	0.0	0.0	1.0
87200400	SPAN WIRE	FOOT	129.0	0.0	0.0	0.0	0.0	0.0	129.0
87200500	TETHER WIRE	FOOT	129.0	0.0	0.0	0.0	0.0	0.0	129.0
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	50.0	0.0	0.0	0.0	0.0	0.0	50.0
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	25.0	0.0	0.0	0.0	0.0	0.0	25.0
87302225	ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 3C	FOOT	125.0	0.0	0.0	0.0	0.0	0.0	125.0
88040420	SIGNAL HEAD, POLYCARBONATE, LED, 4-FACE, 1-SECTION, SPAN WIRE MOUNTED	EACH	2.0	0.0	0.0	0.0	0.0	0.0	2.0
89502400	REMOVE EXISTING FLASHING BEACON INSTALLATION COMPLETE	EACH	1.0	0.0	0.0	0.0	0.0	0.0	1.0
X0321297	REMOVE EXISTING SIGN POST	EACH	1.0	0.0	1.0	0.0	0.0	0.0	0.0
X0324058	OUTLET SPECIAL	EACH	2.0	1.0	1.0	0.0	0.0	0.0	0.0
X0545000	BOX CULVERT REMOVAL	FOOT	18.0	0.0	18.0	0.0	0.0	0.0	0.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	4.0	0.0	0.0	4.0	0.0	0.0	0.0
X7240600	REMOVE AND RE-ERECT EXISTING SIGN	EACH	4.0	2.0	2.0	0.0	0.0	0.0	0.0
Z0002900	BASE COURSE (OPTION)	SQ YD	135.0	55.0	80.0	0.0	0.0	0.0	0.0
Z0023500	FILLING EXISTING CULVERTS	CU YD	40.0	0.0	40.0	0.0	0.0	0.0	0.0
Z0023900	FILLING EXISTING WELLS	EACH	1.0	1.0	0.0	0.0	0.0	0.0	0.0

\* SPECIALTY ITEMS

\*DOUGLAS & MOULTRIE

FILE NAME = c:\pwork\pwidot\BOWERML\dms85936\70234	USER NAME = bowerml	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.P. RTE. 749	SECTION 120RS-3	COUNTY *	TOTAL SHEETS 55	SHEET NO. 6
PLOT SCALE = 40.0000' / IN.	DRAWN -	CHECKED -	REVISED -						SCALE: N/A	SHEET NO. OF SHEETS	STA. TO STA.	CONTRACT NO. 70234	
PLOT DATE = 12/3/2009	DATE -	REVISED -	REVISED -		ILLINOIS FED. AID PROJECT								