

STATION		INCIDENTAL AREA (SQ YD)	AVERAGE THICKNESS (INCH)	40800050 INCIDENTAL HOT-MIX ASPHALT SURFACING (TON)	40800010 BIT MAT'L PRIME COAT (GALLONS)	40800030 AGGREGATE PRIME COAT (TON)	44000196 HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL (SQ YD)	40600982 HOT-MIX ASPHALT SURFACE REMOVAL, BUTT JOINT (SQ YD)	44000200 DRIVEWAY PAVEMENT REMOVAL (SQ YD)	42300400 PCC DRIVEWAY PAVEMENT 8" (SQ YD)	
LT.	1+87.40	647.71	1.50	54.41	32.39	0.65	647.71				
RT.	1+87.40	308.43	1.50	25.91	15.42	0.31		308.43			
LT.	6+39.83	40.3	1.50	3.39	2.02	0.04		40.30			
RT.	6+36.30	32.1	1.50	2.70	1.61	0.03		32.10			
LT.	8+20.24	7.5	1.50	0.63	0.38	0.01		7.50			
LT.	8+44.09	17.6	1.50	1.48	0.88	0.02		17.60			
RT.	8+86.52	44.3	1.50	3.72	2.22	0.04		44.30			
LT.	9+21.08	9.8	1.50	0.82	0.49	0.01		9.80			
RT.	10+27.94	69.9	1.50	5.87	3.50	0.07		69.90			
LT.	10+39.20	40.9	1.50	3.44	2.05	0.04		40.90			
LT.	11+42.23	53.7	1.50	4.51	2.69	0.05		53.70			
RT.	11+95.99	54.1	1.50	4.54	2.71	0.05		54.10			
LT.	12+47.73	77.5	1.50	6.51	3.88	0.08		77.50			
LT.	13+26.96	53.0	1.50	4.45	2.65	0.05		53.00			
RT.	13+26.96	79.9	1.50	6.71	4.00	0.08		79.90			
LT.	15+14.13	30.8	1.50	2.59	1.54	0.03		30.80			
RT.	15+15.46	66.0	1.50	5.54	3.30	0.07		66.00			
LT.	16+12.61	18.4	1.50	1.55	0.92	0.02		18.40			
LT.	17+34.20	45.7	1.50	3.84	2.29	0.05		45.70			
RT.	17+46.54	70.2	1.50	5.90	3.51	0.07		70.20			
LT.	18+42.50	63.0	1.50	5.29	3.15	0.06		63.00			
RT.	19+36.43	45.5	1.50	3.82	2.28	0.05		45.50			
LT.	19+58.22	23.7	1.50	1.99	1.19	0.02		23.70			
LT.	20+05.97	25.4	1.50	2.13	1.27	0.03		25.40			
LT.	21+67.76	67.5	1.50	5.67	3.38	0.07		67.50			
RT.	23+29.39	113.6	1.50	9.54	5.68	0.11		113.60			
RT.	24+80.73	168.1	1.50	14.12	8.41	0.17		168.10			
RT.	26+43.80	76.4	1.50	6.42	3.82	0.08		76.40			
LT.	27+05.87	69.8	1.50	5.86	3.49	0.07		69.80			
RT.	27+84.45	120.6	1.50	10.13	6.03	0.12		120.60			
RT.	28+67.16	81.8	1.50	6.87	4.09	0.08		81.80			
LT.	29+26.84	27.7	1.50	2.33	1.39	0.03		27.70			
RT.	29+40.82	78.7	1.50	6.61	3.94	0.08		78.70			
LT.	30+59.85	19.8	1.50	1.66	0.99	0.02		19.80			
RT.	30+76.91	30.6	1.50	2.57	1.53	0.03		30.60			
LT.	31+25.98	24.8	1.50	2.08	1.24	0.02		24.80			
LT.	31+54.61	36.5	1.50	3.07	1.83	0.04		36.50			
LT.	32+08.33	64.4	1.50	5.41	3.22	0.06		64.40			
LT.	32+45.45	43.4	1.50	3.65	2.17	0.04		43.40			
RT.	33+63.72	125.7	1.50	10.56	6.29	0.13			125.70	125.70	
LT.	34+00.00	152.0	1.50	12.77	7.60	0.15			152.00	152.00	
RT.	35+14.16	83.5	1.50	7.01	4.18	0.08		83.50			
LT.	36+18.38	121.0	1.50	10.16	6.05	0.12			121.00	121.00	
LT.	40+60.98	134.0	1.50	11.26	6.70	0.13			134.00	134.00	
LT.	41+65.00	96.7	1.50	8.12	4.84	0.10		96.70			
LT.	42+48.00	86.5	1.50	7.27	4.33	0.09		86.50			
RT.	42+60.42	132.7	1.50	11.15	6.64	0.13		132.70			
RT.	50+30.86	205.8	1.50	17.29	10.29	0.21		205.80			
LT.	57+82.44	134.5	1.50	11.30	6.73	0.13		134.50			
RT.	60+08.12	100.9	1.50	8.48	5.05	0.10		100.90			
LT.	60+09.33	53.4	1.50	4.49	2.67	0.05		53.40			
				TOTAL =	367.57	218.79	4.38	647.71	3195.43	532.70	532.70
				USE =	368.0	219.0	5.0	648.0	3196.0	533.0	533.0
					(TON)	(GALLONS)	(TON)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)

*DOUGLAS & MOULTRIE

FILE NAME =	USER NAME = bowerml	DESIGNED - MLB	REVISED -
ct:\pw\work\PIWIDOT\BOWERML\dms85036\70234 Schedules.dgn		DRAWN - MLB	REVISED -
		CHECKED -	REVISED -
		DATE - 11/05/20	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: N/A SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
749	12ORS-3	*	55	13
CONTRACT NO. 70234				
ILLINOIS FED. AID PROJECT				