

SUMMARY OF QUANTITIES

LOCATION OF WORK FAU 7052 / FAP 729 (US 150)
SECTION : (36X, 36X-1, 34Z-3)RS-1)
VERMILION COUNTY

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	FAU 7052	FAP 729	FAU 7052	FAP 729
				STA 396+77 TO STA. 408+65.06 URBAN 100% STATE 1000	STA. 410+89.34 TO STA. 188+46 URBAN 100% STATE 1000	STA 396+77 TO STA. 408+65.06 URBAN 100% STATE Y002-1C	STA. 410+89.34 TO STA. 188+46 URBAN 100% STATE Y002-1C
40600100	BITUMINOUS MATERIALS PRIME COAT	GALLON	13,176.0	388.0	12,788.0	0.0	0.0
40600300	AGGREGATE PRIME COAT	TON	265.0	8.0	257.0	0.0	0.0
40600635	LEVEL BINDER (MACHINE METHOD), N70	TON	4,323.0	0.0	4,323.0	0.0	0.0
40600990	TEMPORARY RAMP	SQ YD	1,243.0	102.0	1,141.0	0.0	0.0
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	753.0	0.0	753.0	0.0	0.0
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	10,965.0	300.0	10,665.0	0.0	0.0
40800010	BITUMINOUS MATERIALS PRIME COAT	GALLON	464.0	0.0	464.0	0.0	0.0
40800030	AGGREGATE PRIME COAT	TON	10.0	0.0	10.0	0.0	0.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	520.0	0.0	520.0	0.0	0.0
44000154	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/4"	SQ YD	28,736.0	4,103.0	24,633.0	0.0	0.0
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	101,894.0	0.0	101,894.0	0.0	0.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1,208.0	0.0	1,208.0	0.0	0.0
44000170	HOT-MIX ASPHALT SURFACE REMOVAL, 5 1/4"	SQ YD	3,582.0	0.0	3,582.0	0.0	0.0
44201811	CLASS D PATCHES, TYPE I, 14 INCH	SQ YD	64.0	20.0	44.0	0.0	0.0
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	96.0	20.0	76.0	0.0	0.0
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	224.0	20.0	204.0	0.0	0.0
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	2,793.0	20.0	2,773.0	0.0	0.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,887.0	59.0	1,828.0	0.0	0.0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	104.0	45.0	59.0	0.0	0.0
56109210	WATER VALVES TO BE ADJUSTED	EACH	4.0	0.0	4.0	0.0	0.0
60255500	MANHOLES TO BE ADJUSTED	EACH	12.0	0.0	12.0	0.0	0.0
60260100	INLETS TO BE ADJUSTED	EACH	50.0	0.0	50.0	0.0	0.0

*FAU 7052 / FAP 729

FILE NAME =	USER NAME = bucklesj	DESIGNED - RLA	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.* RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pw_work\PWIDOT\BUCKLESJ\0132727\0570315-shr-500.dgn	PLOT SCALE = 40.0000' / IN.	DRAWN - RLA	REVISED -					(36X,36X-1,34Z-3)RS-1	VERMILION	58	5	
	PLOT DATE = 12/7/2009	CHECKED - JMS	REVISED -		SCALE:	SHEET NO. 1 OF 3 SHEETS	STA.	TO STA.	CONTRACT NO. 70315			
		DATE - 7/1/2009	REVISED -		ILLINOIS FED. AID PROJECT							