

EARTHWORK AND FURNISHED EXCAVATION

LOCATION	EARTH EXCAVATION (CU YD)	EARTH EXCAV. ADJUSTED FOR SHRINKAGE* (CU YD)	EMBANKMENT (FILL) (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
STA TO STA	CU YD	CU YD	CU YD	CU YD
LT 277+25 TO LT 281+83	34.0	25.5	51.0	-25.5
RT 277+50 TO RT 280+75	0.0	0.0	6.0	-6.0
ACTUAL TOTAL	34.0	25.5	51.0	-31.5
USE TOTAL	34.0	-	-	32.0

*BASED ON SHRINKAGE FACTOR OF 25% EARTH EXCAVATION: 34 CU YD
 20400800 FURNISHED EXCAVATION: 32 CU YD

LANDSCAPING & EROSION CONTROL

LOCATION	25000210	25100630	28000250	25000400	25000500	25000800	28000305
	SEEDING CLASS 2A	EROSION CONTROL BLANKET	TEMP. EROSION CONTROL SEEDING	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	TEMPORARY DITCH CHECKS
STATION TO STATION O/S	ACRE	SQ YD	POUND	POUND	POUND	POUND	FOOT
277+30.0 TO 281+83.4 LT & RT	0.250	570.0	25.0	22.5	22.5	22.5	24.0
ACTUAL TOTAL	0.25	570.00	25.00	22.50	22.50	22.50	24.0
USE TOTAL	0.25	570.0	25.0	23.0	23.0	23.0	24.0

HMA REMOVAL, HMA LEVEL BINDER, HMA SURFACE, AND SHOULDER ITEMS

STA	STA	44000158	44000155	40600990	40603310	40600625	40600100	40600300	48203100	48102100
		HMA SURF REM 2.25"	HMA SURF REM 1.5"	TEMPORARY RAMP	HMA SURF. CSE. 1.5"	HMA LVL BIND 0.75"	BIT. MAT'L PRIME COAT	AGG MAT'L PRIME COAT	HMA SHOULDERS	AGG WEDGE SHOULDERS TYPE B
		SQ YD	SQ YD	SQ YD	TON	TON	GALLON	TON	TON	TON
244+00.00	280+72.00	9792.0		20.0	822.5	411.26	1468.80	29.38		107.10
280+72.00	281+96.40	373.2			31.3	15.67	55.98	1.12		3.83
281+96.40	287+59.81	1690.2			142.0	70.99	253.53	5.07		16.43
287+96.40	288+83.00	259.8			21.8	10.91	38.97	0.78		2.53
288+83.00	300+68.50	3181.3			265.6	132.78	474.20	9.48		34.58
300+68.50	302+15.00		431.4		36.2		43.14	0.86		4.27
302+15.00	303+61.67		651.9		54.8		65.19	1.30		0.00
303+61.67	315+70.00		5280.2		443.5		528.02	10.56		0.00
315+70.00	328+63.80		3737.6		314.0		373.76	7.48		0.00
328+63.80	381+00.00	16872.2			1417.3	708.63	2530.83	50.62		152.72
381+00.00	382+16.00	373.8			31.4	15.70	56.07	1.12		3.38
382+16.00	388+26.11	1965.9			165.1	82.57	294.89	5.90		17.79
388+26.11	390+00.00	415.7			34.9	17.46	62.35	1.25		3.76
390+00.00	401+82.60	3153.6			264.9	132.45	473.04	9.46		34.49
401+82.60	403+73.40	508.8			42.7	21.37	76.32	1.53		5.57
403+73.40	424+00.00	3437.3			288.7	144.37	515.60	10.31		37.80
424+00.00	443+25.00	5133.3			431.2	215.60	770.00	15.40		56.15
443+25.00	460+00.00	4466.7			375.2	187.60	670.00	13.40		48.85
460+00.00	471+50.00	3086.7			257.6	128.80	480.00	9.20		33.54
471+50.00	492+00.00	5466.7			459.2	229.60	820.00	16.40		59.79
492+00.00	522+00.58	8001.5			672.1	336.06	1200.23	24.00		87.52
522+00.58	552+00.00	7686.6			645.7	322.84	1152.98	23.06		84.07
552+00.00	560+07.00	2152.0			180.8	90.38	322.80	6.46		23.54
560+07.00	560+17.40	27.7	12.7		2.3	1.16	6.07	0.12	1.60	0.30
560+17.40	561+70.00	406.9	356.1		34.2	17.09	114.45	2.29	29.91	4.45
561+70.00	567+18.50	1462.7	1279.8	20.0	122.9	61.43	411.38	8.23	107.51	16.00
ACTUAL TOTAL		79874.7	11749.7	40.0	7558.0	3354.7	13238.6	264.8	139.0	838.1
USE TOTAL		79,875.0	11,750.0	40.0*	7,558.0	3,355.0	13,239.0	265.0	139.0	839.0*

*SEE INCIDENTAL SCHEDULE FOR ADDITIONAL QUANTITY

FILE NAME =	USER NAME = ppersonbr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pw\work\PIWIDOT\PIERSONBR\d0115438\05	0523-shit-schedule.dgn	DRAWN -	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	2466	(9,10,11)RS-3	MCLEAN	47	12
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -						CONTRACT NO. 70523					
	PLOT DATE = 12/4/2009	DATE -	REVISED -						ILLINOIS FED. AID PROJECT					