CONTRACT NO. 70584

| F.A.S. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 1517 | 12BR | CHAMPAIGN | 30 | 4 |

# SUMMARY OF QUANTITIES

LOCATION OF WORK: CHAMPAIGN CO.
FAS 1517
US 150

FUNDING BREAKOUT: 80% FED. / 20% STATE

CONSTRUCTION TYPE CODE: Y007

| | CODE NO. | DESCRIPTION | UNIT | TOTAL QUANTITY |
|---|---|---|---|---|
| | 20200100 | EARTH EXCAVATION | CU YD | 80.0 |
| | 20400800 | FURNISHED EXCAVATION | CU YD | 205.0 |
| | 20700220 | POROUS GRANULAR EMBANKMENT | CU YD | 312.0 |
| | 21301052 | EXPLORATION TRENCH 52" DEPTH | FOOT | 100.0 |
| | 25000210 | SEEDING, CLASS 2A | ACRE | 0.3 |
| * | 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 45.0 |
| * | 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 45.0 |
| * | 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 45.0 |
| * | 25001850 | SEEDING, CLASS 7 (MODIFIED) | ACRE | 0.3 |
| * | 25100115 | MULCH, METHOD 2 | ACRE | 0.5 |
| * | 25100630 | EROSION CONTROL BLANKET | SQ YD | 285.0 |
| | 28000250 | TEMPORARY EROSION CONTROL SEEDING | POUND | 50.0 |
| | 28000305 | TEMPORARY DITCH CHECKS | FOOT | 72.0 |
| | 28000400 | PERIMETER EROSION BARRIER | FOOT | 715.0 |
| | 28100705 | STONE DUMPED RIPRAP, CLASS A3 | SQ YD | 42.0 |
| | 28200200 | FILTER FABRIC | SQ YD | 42.0 |
| | 44201796 | CLASS D PATCHES, TYPE IV, 12 INCH | SQ YD | 128.0 |
| | 48101500 | AGGREGATE SHOULDERS, TYPE B 6" | SQ YD | 192.0 |
| | 50100100 | REMOVAL OF EXISTING STRUCTURES | EACH | 1.0 |
| | 50200100 | STRUCTURE EXCAVATION | CU YD | 275.0 |
| | 50800105 | REINFORCEMENT BARS | POUND | 15,790.0 |
| | 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 1,600.0 |
| | 51500100 | NAME PLATES | EACH | 1.0 |
| | 54003000 | CONCRETE BOX CULVERTS | CU YD | 123.0 |
| | 54248510 | CONCRETE COLLAR | CU YD | 1.0 |
| | 61101011 | STORM SEWERS PROTECTED, CLASS A, 10" | FOOT | 8.0 |

* SPECIALTY ITEMS

PLOT DATE = 12/4/2009
FILE NAME = c:\pwwork\PWIDOT\COOHSESSF\dms87978\70584Cover-Sheet.dgn
PLOT SCALE = 42.3529 ' / IN.
USER NAME = scombart