

SCHEDULE OF QUANTITIES

| SB LANES | | START STATION | STOP STATION | LENGTH FEET | LEFT SHOULDER SQ.YDS. | RIGHT SHOULDER SQ.YDS. | ROUT CRACKS | | HMA SURFACE REMOVAL, VAR DEP SQYD | MICROSURFACING SINGLE PASS, TYPE II SQYD | BITUMINOUS PRIME COAT GALLON | FIBER ASPHALT POUND |
|--------------------|-------------------------|---------------|--------------|-------------|-----------------------|------------------------|------------------|---------------------|-----------------------------------|--|------------------------------|---------------------|
| | | | | | | | TRANSVERSE FOOT* | LONGITUDINAL FOOT** | | | | |
| | | | | | | | 45200205 | | | | | |
| | | 1280+42.70 | 1231+39.40 | 4,903.30 | 3,268.87 | 5,448.11 | 784.53 | 9,806.60 | 8,716.98 | 8,716.98 | 871.70 | 5,613.30 |
| | Eq. Sta. 802+56.61 BK | 1231+39.40 * | 1165+43.63 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| EQ.STA | 1165+43.63 AH | 802+56.61 * | 802+37.08 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | | 802+37.08 | 787+55.68 | 1,481.40 | 987.60 | 1,646.00 | 237.02 | 2,962.80 | 2,633.60 | 2,633.60 | 263.36 | 1,695.91 |
| US 51 BUS | | 787+55.68 | 781+22.38 | 633.30 | 422.20 | 703.67 | 101.33 | 1,266.60 | 1,125.87 | 1,125.87 | 112.59 | 725.00 |
| | | 781+22.38 | 760+40.68 | 2,081.70 | 1,387.80 | 2,313.00 | 333.07 | 4,163.40 | 3,700.80 | 3,700.80 | 370.08 | 2,383.13 |
| | SN 020-0050 | 761+52.85 | 762+47.15 | -94.30 | -62.87 | -104.78 | -15.09 | -188.60 | -167.64 | -167.64 | -16.76 | -107.95 |
| | | 755+14.48 | 704+94.38 | 5,020.10 | 3,346.73 | 5,577.89 | 803.22 | 10,040.20 | 8,924.62 | 8,924.62 | 892.46 | 5,747.01 |
| IL 10 | | 699+92.88 | 681+75.38 | 1,817.50 | 1,211.67 | 2,019.44 | 290.80 | 3,635.00 | 3,231.11 | 3,231.11 | 323.11 | 2,080.67 |
| | SN 020-0052 | 689+14.40 | 691+05.60 | -191.20 | -127.47 | -212.44 | -30.59 | -382.40 | -339.91 | -339.91 | -33.99 | -218.89 |
| | | 675+41.38 | 661+71.58 | 1,369.80 | 913.20 | 1,522.00 | 219.17 | 2,739.60 | 2,435.20 | 2,435.20 | 243.52 | 1,568.15 |
| | | 661+71.58 | 656+72.38 | 499.20 | 332.80 | 554.67 | 79.87 | 998.40 | 887.47 | 887.47 | 88.75 | 571.48 |
| | | 656+72.38 | 651+88.38 | 484.00 | 322.67 | 537.78 | 77.44 | 968.00 | 860.44 | 860.44 | 86.04 | 554.08 |
| IL 54 | | 645+57.38 | 623+97.88 | 2,159.50 | 1,439.67 | 2,399.44 | 345.52 | 4,319.00 | 3,839.11 | 3,839.11 | 383.91 | 2,472.20 |
| | | 618+96.28 | 570+45.88 | 4,850.40 | 3,233.60 | 5,389.33 | 776.06 | 9,700.80 | 8,622.93 | 8,622.93 | 862.29 | 5,552.74 |
| CLINTON RD | | 585+77.50 | 588+20.50 | -243.00 | -162.00 | -270.00 | -38.88 | -486.00 | -432.00 | -432.00 | -43.20 | -278.19 |
| | SN 020-0055 | 563+87.88 | 544+42.74 | 1,945.14 | 1,296.76 | 2,161.27 | 311.22 | 3,890.28 | 3,458.03 | 3,458.03 | 345.80 | 2,226.80 |
| EQ.STA | Eq. Sta. 944+00.00 BK | 944+00.00 | 943+95.84 | 4.16 | 2.77 | 4.62 | 0.67 | 8.32 | 7.40 | 7.40 | 0.74 | 4.76 |
| | 544+42.74 AH | 932+87.34 | 931+51.44 | 135.90 | 90.60 | 151.00 | 21.74 | 271.80 | 241.60 | 241.60 | 24.16 | 155.58 |
| HERITAGE RD | | 926+76.84 | 916+76.14 | 1,000.70 | 667.13 | 1,111.89 | 160.11 | 2,001.40 | 1,779.02 | 1,779.02 | 177.90 | 1,145.60 |
| | | 912+28.54 | 901+47.54 | 1,081.00 | 720.67 | 1,201.11 | 172.96 | 2,162.00 | 1,921.78 | 1,921.78 | 192.18 | 1,237.53 |
| | | 898+03.34 | 894+89.64 | 313.70 | 209.13 | 348.56 | 50.19 | 627.40 | 557.69 | 557.69 | 55.77 | 359.12 |
| EQ.STA | Eq. Sta. 880+16.13 BK = | 894+89.64 | 880+15.45 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | | | | |
| | 880+15.45 AH | | | | | | | | | | | |

* Quantity reflects 1 crack greater than 3/4" every 100 feet.

** Quantity reflects 1 crack between pavement and shoulder on each side of US 51 for length of section

| | | | | | | | | | | | |
|--|---------------------|----------------|-----------|---|-------------------------------|--------------------|-----------|--------|--------------|-----------|----|
| FILE NAME = | USER NAME = leroyma | DESIGNED - MAL | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SCHEDULE OF QUANTITIES | F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. | |
| ct:\pwork\pwork\LEROYMA\d0149985\0570809-sht-500.dgn | | DRAWN - JJB | REVISED - | | | 322 | 2010PPP | DEWITT | 11 | 8 | |
| PLOT SCALE = 40.0000' / IN. | | CHECKED - | REVISED - | | | CONTRACT NO. 70809 | | | | | |
| PLOT DATE = 11/17/2009 | | DATE - 7-8-09 | REVISED - | | | SCALE: | SHEET NO. | OF | SHEETS | STA. | TO |