

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	80% FED. 20% STATE TOTAL	CASS CO.	SANGAMON CO.
			QUANTITY	I 000 QUANTITY	I 000 QUANTITY
20200100	EARTH EXCAVATION	CU YD	1,461		1,461
28000305	TEMPORARY DITCH CHECKS	FOOT	100		100
28000400	PERIMETER EROSION BARRIER	FOOT	3,875		3,875
31100700	SUB-BASE GRANULAR MATERIAL, TYPE A 8"	SQ YD	2,946		2,946
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQ YD	627		627
35600724	HOT-MIX ASPHALT BASE COURSE WIDENING, 12"	SQ YD	1785		1785
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	37.8	4.4	33.4
40600300	AGGREGATE (PRIME COAT)	TON	201.1	24.4	176.7
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	439		439
40600895	CONSTRUCTING TEST STRIP	EACH	1		1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	218	80	138
40600990	TEMPORARY RAMP	SQ YD	75	15	60
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	8377	976	7,401
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	77	33	44
44000100	PAVEMENT REMOVAL	SQ YD	31		31
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	25,144		25,144
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	72,064	11,502	60,562

FILE NAME =	USER NAME = coxte	DESIGNED - RTS	REVISED -
c:\pwork\PIWIDOT\COXTE\dms84394\ahh-SC0.dgn		DRAWN - RTS	REVISED -
PLOT SCALE = 100.0000' / IN.	CHECKED - RTS	REVISED -	REVISED -
PLOT DATE = Dec-18-2009 04:09:55PM	DATE - 12-16-09	REVISED -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 1 OF 4 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
67	105(RS-6), 106(RS-4)	SANG/CASS	88	3
CONTRACT NO. 72C49			ILLINOIS FED. AID PROJECT	

Rev.