

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CASS CO.	SANGAMON CO.
				100% FED QUANTITY	100% FED QUANTITY
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15	2	13
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2800	270	2,530
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	933	90	843
72400600	RELOCATE SIGN PANEL ASSEMBLY-TYPE B	EACH	3		3
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	51.5		51.5
78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	9,008		9,008
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	340		340
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	343		343
78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	<u>56,370</u>	<u>5,136</u>	<u>51,234</u>
78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SQ FT	78		78
78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	100		100
78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	460		460
78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	53		53
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	391	34	357
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	350	34	316
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1		1
81020500	CONDUIT PUSHED, 2" DIA., INTERMEDIATE METAL	FOOT	312		312

Rev.