

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CASS CO.	SANGAMON CO.
				100% FED QUANTITY	100% FED QUANTITY
81603000	UNIT DUCT, 600V, 2-1C NO. 8, 1/C NO. 8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	1,595		1,595
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1,200		1,200
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	11		11
82500310	LIGHTING CONTROLLER, POLE MOUNTED, 240VOLT, 60AMP	EACH	1		1
83003600	LIGHT POLE, ALUMINUM, 45 FT. M. H., 15 FT. DAVIT ARM	EACH	11		11
83600355	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8"X6'	EACH	11		11
83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	44		44
89502400	REMOVE EXISTING FLASHING BEACON INSTALLATION COMPLETE	EACH	1		1
X0325739	HOT-MIX ASPHALT SHOULDER REMOVAL AND REPLACEMENT (SPECIAL)	SQ YD	2,131	207	1,924
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	43		43
X6064201	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.06	FOOT	23		23
XX005938	SOLAR-POWERED FLASHING BEACON ASSEMBLY (COMPLETE)	EACH	3		3
73700100	REMOVE GROUND-MOUNTED SIGN SUPPPORT	EACH	3		3
84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	1		1
84200807	REMOVAL OF POLE FOUNDATION, METAL	EACH	1		1
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1		1
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1		1