

GUARDRAIL SCHEDULE									
STA	TO	STA	LT / RT	63000001	63100087	63200310	63100167	78200410	78201000
				STEEL PLATE BEAM GUARD RAIL, TY A, 6 FT POSTS	TRAFFIC BARRIER TERMINAL, TYPE 6A	GUARDRAIL REMOVAL	TRAFFIC BARRIER TERMINAL, TY 1 (SP) TAN	GUARDRAIL MARKERS TYPE A	TERMINAL MARKER - DIRECT APPLIED
				(FOOT)	(EACH)	(FOOT)	(EACH)	(EACH)	(EACH)
IL 185									
938+65.5		939+15.5	LT				1		1
939+15.5		939+53.0	LT	37.5				1	
939+53.0		939+97.0	LT		1			1	
939+20.0		939+97.0	LT			77.0			
937+55.0		938+05.0	RT				1		1
938+05.0		939+30.0	RT	125.0				2	
939+30.0		939+74.0	RT		1			1	
938+93.0		939+73.0	RT			80.0			
940+27.0		940+71.0	LT		1			1	
940+71.0		941+71.0	LT	100.0				2	
941+71.0		942+21.0	LT				1		1
940+27.0		941+07.0	LT			80.0			
940+04.0		940+48.0	RT		1			1	
940+48.0		940+85.5	RT	37.5				1	
940+85.5		941+35.5	RT				1		1
940+03.0		940+80.0	RT			77.0			
TOTALS				300.0	4	314	4	10	4

STRIPING SCHEDULE							
STA.	TO	STA.	LOCATION	70300220	78001110	78100100	78300100
				TEMPORARY PAVEMENT MARKING - LINE 4"	PAINT PAVEMENT MARKING - LINE 4"	RAISED REFLECTIVE PAVEMENT MARKER	PAVEMENT MARKING REMOVAL
				(FOOT)	(FOOT)	(EACH)	(SQ FT)
STAGE I							
936+22		938+65	CENTER				20
941+01		943+14	CENTER				18
STAGE I SUB TOTAL							38
STAGE II							
939+40		940+60	CENTER				
937+78		942+01	LT EDGE				141
STAGE II SUB TOTAL							141
FINAL							
936+22		943+14	RT EDGE	692	692		
936+22		943+14	CENTER	173	173		
936+22		943+14	LT EDGE	692	692		
939+40		940+60	CENTER			2	
FINAL SUB TOTAL				1,557	1,557	2	179
TOTALS				1,557	1,557	2	179

SEEDING SCHEDULE					
STATION TO STATION	LT / RT	AREA	25001000	28000250	
			SEEDING, CLASS 2 (SPECIAL)	TEMPORARY EROSION CONTROL SEEDING	
			(SQ FT)	(ACRE)	(POUND)
938+24		939+82	3,320	0.08	8
936+41		939+67	5,006	0.12	12
940+53		942+31	3,391	0.08	8
940+05		942+49	3,890	0.09	9
TOTALS				0.37	37
USE				0.4	40

RIGHT OF WAY MARKER SCHEDULE					
STA	OFFSET	LT / RT	66600105	20025500	
			FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	FURNISHING AND INSTALLING PROPERTY MARKERS	
			(EACH)	(EACH)	
IL 185					
935+00.0	40'	RT	1		
937+26.97	5.75'	RT			1
939+00.0	60'	RT	1		
940+00.0	60'	RT	1		
944+00.0	40'	RT	1		
TOTAL			4		1