

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT		100% STATE 1000
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	158	158
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	6742	6742
40600300	AGGREGATE (PRIME COAT)	TON	135	135
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	2831	2831
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	160	160
40600990	TEMPORARY RAMP	SO YD	27	27
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	5691	5691
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	210	210
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	1995	1995
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	6384	6384
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	58856	58856
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SO YD	897	897
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SO YD	37	37
44200174	PAVEMENT PATCHING, TYPE IV, 14 INCH	SO YD	100	100
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1534	1534
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	9	9
67100100	MOBILIZATION	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7368	7368
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	59960	59960
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	819	819
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	59960	59960
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	306	306

\* SPECIALTY ITEMS

FILE NAME = *FILEL*	USER NAME = *USER*	DESIGNED - DRAWN -	REVISED - REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.S. RTE. 1652	SECTION (12,13)RS-3	COUNTY Effingham	TOTAL SHEETS 15	SHEET NO. 3
	PLOT SCALE = *SCALE*	CHECKED - DATE -	REVISED - REVISED -		SCALE: NA	SHEET NO. 1	OF 1 SHEETS	STA.	TO STA.	CONTRACT NO. 74376		
	PLOT DATE = *DATE*				ILLINOIS FED. AID PROJECT							