

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	025-0083 SFTY-2A	-----
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	50	50	
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SQ YD	289	289	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	108	108	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1275	1275	
44004250	PAVED SHOULDER REMOVAL	SQ YD	289	289	
50102400	CONCRETE REMOVAL	CU YD	12.7	12.7	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	12.7	12.7	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1620	1620	
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	12	12	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1980	1980	
50800515	BAR SPLICERS	EACH	22	22	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	89	89	
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	12	12	
52100520	ANCHOR BOLTS, 1"	EACH	24	24	
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	1275	1275	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	8	8	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1480	1480	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3400	3400	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	470	470	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	525	525	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	525	525	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2160	2160	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	14	14	
* 78100300	REPLACEMENT REFLECTOR	EACH	6	6	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	560	560	

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	025-0083 SFTY-2A	-----
X0322050	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	EACH	6	6	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	25	25	
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	1	1	
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	87	87	
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	64	64	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	