

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1696	1696
40600300	AGGREGATE (PRIME COAT)	TON	34	34
40600855	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N105	TON	870	870
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1101	1101
40600990	TEMPORARY RAMP	SQ YD	260	260
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	1424	1424
44000086	HOT-MIX ASPHALT SURFACE REMOVAL COMPLETE	SQ YD	10302	10302
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	5668	5668
44200994	CLASS B PATCHES, TYPE II, 12 INCH	SQ YD	413	413
44200998	CLASS B PATCHES, TYPE III, 12 INCH	SQ YD	44	44
44213100	PAVEMENT FABRIC	SQ YD	44	44
44213200	SAW CUTS	FOOT	3075	3075
48101200	AGGREGATE SHOULDERS, TYPE B	TON	71	71
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1
63200310	GUARDRAIL REMOVAL	FOOT	25	25
67100100	MOBILIZATION	L SUM	1	1
70100455	TRAFFIC CONTROL AND PROTECTION, STANDARD 701206	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6805	6805
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	239.2	239.2

SUMMARY OF QUANTITIES (Cont'd)			100% STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	13242	13242
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	676	676
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	413	413
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	775	775
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	127	127
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6799	6799
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	239	239
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	13242	13242
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	676	676
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	413	413
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	775	775
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	127	127
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	85	85
* 78200300	PRISMATIC CURB REFLECTOR	EACH	123	123
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	8	8
* 88600100	DETECTOR LOOP, TYPE I	FOOT	687	687
X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	14	14
Z0017100	DOWEL BARS	EACH	1372	1372

* SPECIALTY ITEMS