

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE											
				ROADWAY				TRAFFIC SIGNALS			UTILITIES		BOX CULVERT	RETAINING WALLS	
				1000-2A				Y031-IF			Y060		X028-2A	Y007	
				ST. CLAIR COUNTY		MADISON COUNTY		MADISON COUNTY	MADISON COUNTY	ST. CLAIR COUNTY	ST. CLAIR COUNTY	MADISON COUNTY	ST. CLAIR COUNTY	MADISON COUNTY	
CODE NO	ITEM	UNIT		80% FED 20% STATE	80% FED 10% STATE 10% CITY	80% FED 20% STATE	80% FED 10% STATE 10% CITY	E. CHURCH ST. 80% FED 10% STATE 10% CITY	MID BLOCK CROSSING 80% FED 20% CITY	MORRISON AVE. 80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	
*63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	3			3									
*63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	3	3											
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	7	4		3									
63200310	GUARDRAIL REMOVAL	FOOT	1388	362.5		1025.5									
66400305	CHAIN LINK FENCE, 6'	FOOT	347			347									
66402700	CHAIN LINK GATES, 6' X 4' SINGLE	EACH	1			1									
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24	4		20									
67100100	MOBILIZATION	L SUM	1	0.15		0.85									
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.15		0.85									
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.15		0.85									
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.15		0.85									
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0.15		0.85									
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0.15		0.85									
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.15		0.85									
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	0.15		0.85									
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	0.15		0.85									
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.15		0.85									
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	0.15		0.85									
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	200	30		170									
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8000	924		7076									
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	890	187		703									
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	74562	17210		57352									
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	784	140		644									
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5181	1850		3331									
70400100	TEMPORARY CONCRETE BARRIER	FOOT	560	440		120									
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	240	240											
*72000100	SIGN PANEL - TYPE 1	SQ FT	402	49		303		50							
*72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	32	8		24									

\*Specialty Items

REV

Rev. 7-18-10

Rev.

FILE NAME =	USER NAME = keplarcl	DESIGNED -	REVISED -
c:\pwwork\pwwdot\keplarcl\dms79887\08	6830-sht-plan.dgn	DRAWN -	REVISED -
PLOT SCALE = 50.3041' / IN.	CHECKED -	REVISOR -	REVISED -
PLOT DATE = 11/19/2009	DATE -		REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>SUMMARY OF QUANTITIES</b>			
SCALE: _____	SHEET NO. _____ OF _____ SHEETS	STA. _____ TO STA. _____	

F.A.P. RTE. 600	SECTION 60-(30.31.128)-1	COUNTY MADISON/ST. CLAIR	TOTAL SHEETS 399	SHEET NO. 10
FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT			CONTRACT NO. 76830	