

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE														
				ROADWAY 1000-2A				TRAFFIC SIGNALS Y031-1F			UTILITIES Y000		BOX CULVERT X028-24	RETAINING WALLS Y007				
				ST. CLAIR COUNTY		MADISON COUNTY		MADISON COUNTY	MADISON COUNTY	ST. CLAIR COUNTY	ST. CLAIR COUNTY	MADISON COUNTY	ST. CLAIR COUNTY	MADISON COUNTY				
				80% FED 20% STATE	80% FED 10% STATE 10% CITY	80% FED 20% STATE	80% FED 10% STATE 10% CITY	E. CHURCH ST. 80% FED 10% STATE 10% CITY	MID BLOCK CROSSING 80% FED 20% CITY	MORRISON AVE. 80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE				
550A0710	STORM SEWERS, CLASS A, TYPE 3 24"	FOOT	240			240												
550A0780	STORM SEWERS, CLASS A, TYPE 3 40"	FOOT	139			139												
550A0840	STORM SEWERS, CLASS A, TYPE 3 84"	FOOT	141			141												
550A0850	STORM SEWERS, CLASS A, TYPE 3 90"	FOOT	336			336												
550A0870	STORM SEWERS, CLASS A, TYPE 3 102"	FOOT	129			129												
55100200	STORM SEWER REMOVAL 6"	FOOT	88			88												
55100300	STORM SEWER REMOVAL 8"	FOOT	59			59												
55100400	STORM SEWER REMOVAL 10"	FOOT	90			90												
55100500	STORM SEWER REMOVAL 12"	FOOT	795	384		411												
55100700	STORM SEWER REMOVAL 15"	FOOT	182			182												
55100900	STORM SEWER REMOVAL 18"	FOOT	125			125												
55101200	STORM SEWER REMOVAL 24"	FOOT	639			639												
55101400	STORM SEWER REMOVAL 30"	FOOT	83			83												
55101600	STORM SEWER REMOVAL 36"	FOOT	182			182												
55101800	STORM SEWER REMOVAL 42"	FOOT	43			43												
55101900	STORM SEWER REMOVAL 48"	FOOT	89			89												
55102100	STORM SEWER REMOVAL 60"	FOOT	101	101														
56100500	WATER MAIN 4"	FOOT	92								81	11						
56100600	WATER MAIN 6"	FOOT	1219								46	1173						
56100700	WATER MAIN 8"	FOOT	5299								375	4924						
56200300	WATER SERVICE LINE 1"	FOOT	2618									2618						
56200700	WATER SERVICE LINE 2"	FOOT	955									955						
56300100	ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS	FOOT	10									10						
56400500	FIRE HYDRANTS TO BE REMOVED	EACH	7								1	6						
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	119													22	97	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	435													75	360	

Rev.

FILE NAME =	USER NAME = keplerol	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ci:\pw_work\VPWIDOT\KEPLARCL\dms79807\08	6830-ah-plot.dgn	DRAWN -	REVISED -			600	60-(30,31,128)-1	MADISON/ST. CLAIR	399	8	
	PLOT SCALE = 50.3841' / IN.	CHECKED -	REVISED -			SCALE: _____ SHEET NO. ____ OF ____ SHEETS STA. _____ TO STA. _____		FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT			
	PLOT DATE = 11/19/2009	DATE -	REVISED -			CONTRACT NO. 76830					