

PIPE SCHEDULE (CONT'D)																		
UPSTREAM STRUCTURE	DOWNSTREAM STRUCTURE	STORM SEWERS, REINFORCED CONCRETE CULVERTS, STORM DRAINS AND SEWER PIPE, SS (LF)						STORM SEWERS REINFORCED CONCRETE ELLIPTICAL, RCEP (LF)			PRECAST CONCRETE BOX CULVERT, PCBC (LF)						SS TYPE	TRENCH BACKFILL (CY)
		12"	15"	18"	24"	36"	48"	23"x14"	30"x19"	38"x24"	2'x2'	3'x2'	4'x2'	4'x3'	5'x5'	9'x6'		
INLET 3-10	MH 3-2		50													1	11	
MH 3-2	MH 3-13			133												2	69	
INLET 3-12	MH 3-14	22														2	14	
INLET 3-13	MH 3-14	18														2	6	
INLET 3-14	MH 3-14	40														2	20	
MH 3-14	MH 3-13	58														2	37	
MH 3-3	MH 3-13		40													2	31	
INLET 3-3	MH 3-3	7														2	2	
MH 3-4	MH 3-3					134										2	180	
INLET 3-4	MH 3-4			65												2	97	
INLET 3-4A	INLET 3-4		7													2	5	
INLET 3-4B	INLET 3-4A		7													2	5	
INLET 3-4C	INLET 3-4B		7													2	5	
INLET 3-4D	INLET 3-4C		7													2	5	
INLET 3-4E	INLET 3-4D		7													2	4	
INLET 3-5	INLET 3-4E		22													2	17	
INLET 3-15	MH 3-4		99													2	101	
INLET 3-16	INLET 3-15	44														2	38	
INLET 3-16A	INLET 3-16	10														2	6	
MH 3-6	MH 3-4	84														2	138	
INLET 3-6	MH 3-6	21														2	17	
MH 3-16	MH 3-6	44														2	61	
MH 3-17	MH 3-16	48														2	63	
INLET 3-17	MH 3-17	7														2	5	
MH 3-18	MH 3-17	77														2	94	
INLET 4-1	MH 3-18	62														2	60	
INLET 3-18	MH 3-18	19														2	19	
SUBTOTAL (3)		561	246	198	0	134	0	0	0	0	0	0	0	0	0		1109	
SUBTOTAL (1)		1350	413	146	43	0	0	141	336	129	71	295	676	412	142	273	3040	
SUBTOTAL (2)		2824	413	247	467	126	386	0	0	0	0	70	0	0	0	0	2193	
SUBTOTAL (3)		561	246	198	0	134	0	0	0	0	0	0	0	0	0	0	1109	
TOTALS		4735	1072	591	510	260	386	141	336	129	71	365	676	412	142	273	6342	

EARTHWORK SCHEDULE				
LOCATION	EARTH EXCAVATION (CY)	EXCAVATION ADJUSTED FOR SHRINKAGE (CY)	EMBANKMENT (CY)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CY)
IL RTE 159				
102+00.00 TO 109+75.00	2107	1581	214	1367
109+75.00 TO 156+02.00	27124	20343	11545	8798
IDLEWOOD DR				
	40	30	14	16
S CLINTON ST				
	3013	2260	74	2186
MCKINLEY AVE				
	1725	1294	15	1279
TEMPORARY CONNECTOR @ MCKINLEY AVE				
	203	152	92	60
S LOOP ST / S CHESTNUT ST - PHASE 1				
	485	364	2175	-1811
S LOOP ST / S CHESTNUT ST - PHASE 2				
	2	2	1113	-1112
ANGLE ST				
	79	59	29	30
N LOOP ST				
	1885	1414	33	1381
HILL ST				
	187	140	0	140
ALLEY @ 149+27				
	445	334	0	334
JIM'S ALLEY				
	74	55	63	-7
CHURCH ST				
	505	379	3	376
ALLEY @ 156+02				
	74	55	0	55
TOTALS				
	37949	26881	15155	13093

Rev.

FILE NAME =	USER NAME = default	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
P:\Projects\51350\1\CAADD\GDN\0876830-sh	schedule.dgn	DRAWN -	REVISED -					600	60-(30,31,128)-1	MADISON/ST. CLAIR	399	33
	PLOT SCALE = 20.0000' / IN.	CHECKED -	REVISED -					CONTRACT NO. 76830				
	PLOT DATE = 12/16/2009	DATE -	REVISED -					SCALE: NTS	SHEET NO. 8 OF 16 SHEETS	STA. N/A TO STA. N/A	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT