

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN 80% FEDERAL 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		SUMMARY OF QUANTITIES			URBAN 80% FEDERAL 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		X271-2A	I000-2A	CODE NO	ITEM	UNIT		X271-2A	I000-2A	Y030-1E
58700300	CONCRETE SEALER	SQ FT	1531	1531		70106700	TEMPORARY RUMBLE STRIP	EACH	6	6		
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	274	274		70106800	CHANGEABLE MESSAGE SIGN	CAL MO	30	30		
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	247	247		70300100	SHORT-TERM PAVEMENT MARKING	FOOT	950	417	533	
60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	1	1		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	14846	5941	8905	
60260100	INLETS TO BE ADJUSTED	EACH	8	4	4	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2325	2325		
60404800	FRAMES AND GRATES, TYPE 11	EACH	8	4	4	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5265	2119	3146	
60500060	REMOVING INLETS	EACH	1	1		70400100	TEMPORARY CONCRETE BARRIER	FOOT	1325	1325		
60605600	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.06	FOOT	4300	2660	1640	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1000	1000		
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	10,745	6,645	4100	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	13840	4935	8905	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	525	525		78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1805	380	1425	
* 63000003	STEEL PLATE BEAM GUARD RAIL, TYPE A, 9 FOOT POSTS	FOOT	3850		3850	78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1006	1006		
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	3	2	1	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	61	61		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		* 78200300	PRISMATIC CURB REFLECTOR	EACH	120	80	40	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	8	5	3	78200410	GUARDRAIL MARKERS, TYPE A	EACH	49	12	37	
63200310	GUARDRAIL REMOVAL	FOOT	5109	1091	4018	78200520	BARRIER WALL MARKERS, TYPE B	EACH	6	6		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	20	20		78200530	BARRIER WALL MARKERS, TYPE C	EACH	6	6		
67100100	MOBILIZATION	L SUM	1	1		78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	5	3	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1	1		78300100	PAVEMENT MARKING REMOVAL	SQ FT	6152	2234	3918	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1		1	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	61	61		
70100455	TRAFFIC CONTROL AND PROTECTION, STANDARD 701206	L SUM	1		1	* 80300100	LOCATING UNDERGROUND CABLE	FOOT	2760			2760
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1		1	* 81603035	UNIT DUCT, 600V, 2-1C NO. 6, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	2960			2960
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1		1	* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	2760			2760
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1		1	* 83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	16			16
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1		1	84200806	REMOVAL OF FOUNDATION, CONCRETE	EACH	2			2
70101200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701431 (SPECIAL)	EACH	1	1		* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	2			2
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	1	1		X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	207	207		
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1		X0322400	PILE EXTRACTION	EACH	8	8		
<del>70103815</del>	<del>TRAFFIC CONTROL SURVEILLANCE</del>	<del>CAL DA</del>	<del>30</del>		<del>30</del>	X0502600	TEMPORARY LIGHTING	L SUM	1			1
70106600	TEMPORARY BRIDGE TRAFFIC SIGNALS (STATE FURNISHED CONTROLLER)	EACH	1	1		X4421000	PARTIAL DEPTH PATCHING	TON	100		100	
						X4422030	PARTIAL DEPTH REMOVAL 3"	SQ YD	570		570	
						X5080600	MECHANICAL SPLICERS	EACH	120	120		
						X6060500	CORRUGATED MEDIAN REMOVAL	SQ FT	535		535	

\* Specialty Items      Rev. 2-11-10      Rev.