

STAGING SCHEDULE

LOCATION	HOT-MIX ASPHALT BASE COURSE, 10"	HOT-MIX ASPHALT BASE COURSE, 11"	PAVEMENT REMOVAL	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE)	IMPACT ATTENUATOR, RELOCATE (NON-REDIRECTIVE)	TEMPORARY PAVEMENT MARKING - LINE 6"
	SQ YD	SQ YD	SQ YD	FOOT	FOOT	EACH	EACH	FOOT
PRE-STAGE I		990						
STAGE I	880	4780	139	1025		4		1325
STAGE II			115		1000		2	1000
IL 3 - NB				150				
IL 3 - SB				150				
TOTAL	880	5770	254 *	1325	1000	4	2	2325

* NOT A TOTAL QUANTITY. SEE REMOVAL SCHEDULE.

GUARDRAIL SCHEDULE

LOCATION	GUARDRAIL REMOVAL	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FT POSTS	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FT POSTS	TRAFFIC BARRIER TERMINAL, TYPE 1, (SPECIAL) TANGENT	TRAFFIC BARRIER TERMINAL, TYPE 6	TRAFFIC BARRIER TERMINAL, TYPE 2	GUARDRAIL MARKERS, TYPE A	BARRIER WALL MARKERS, TYPE B	BARRIER WALL MARKERS, TYPE C	TERMINAL MARKER - DIRECT APPLIED
	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH	EACH	EACH
IL 158										
NORTH SIDE							1	3	3	
SOUTH SIDE							2	3	3	
NW QUADRANT					1					
NE QUADRANT	79			1	1					1
SW QUADRANT	81	25		1	1					1
SE QUADRANT	194			1	1					1
IL 3										
WEST SIDE	424	212.5		1		1	5			1
EAST SIDE	313	287.5		1		1	4			1
RAMPS										
NB IL 3 TO EB IL 15	2431		2325	2			20			2
WB IL 158 TO NB IL 1587			1525	1		1	17			1
TOTAL	5109	525	3850	8	4	3	49	6	6	8

TEMPORARY RAMP SCHEDULE

LOCATION	WIDTH	LENGTH	TEMPORARY RAMP
	FOOT	FOOT	SQ YD
STA 106+28	32	5	18
STA 109+67	32	5	18
STA 112+24	32	5	18
STA 115+00	32	5	18
TOTAL			72