

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE - 100% STATE FUNDING						
CODE NO	ITEM	UNIT		ROADWAY J000	EXCHANGE AVE. BRIDGE S.N. 082-0378 X271 - 2A	RETAINING WALL S.N. 082-W301 Y007	LIGHTING Y030 - 1E	SIGNING Y002 - 1C	STRUCTURE DEMOLITION Y007	ITS Y032 - 1F
* 81603030	UNIT DUCT, 600V, 2-1/C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	950				950			
* 81702450	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 10	FOOT	500				500			
* 81800230	AERIAL CABLE, 2-1/C NO. 6 WITH MESSENGER WIRE	FOOT	1,100				1,100			
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	2,715				920		1795	
* 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	5				5			
* 82107300	UNDERPASS LUMINAIRE, 150 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	8				8			
* 83017600	LIGHT POLE, ALUMINUM, TRANSFORMER BASE, 45 FT. M.H., 15 FT. DAVIT ARM	EACH	5				5			
* 83057290	LIGHT POLE, WOOD, 50 FOOT, CLASS 4	EACH	8				8			
* 83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	33				33			
* 87100110	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 6F	FOOT	512						512	
* 87900200	DRILL EXISTING HANDHOLE	EACH	1						1	
* X0301576	COAXIAL CABLE IN CONDUIT	FOOT	220						220	
X0320870	BRACED EXCAVATION	CU YD	220		220					
X0322125	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	FOOT	64	64						
X5080600	MECHANICAL SPLICERS	EACH	239		239					
X0322400	PILE EXTRACTION	EACH	168		168					
* X0322925	ELECTRICAL CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	2,507						2,507	
X0323830	DRAINAGE SCUPPERS, DS-11	EACH	4		4					
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SO FT	1641		1641					
* X0324181	DISCONNECT SIGN LIGHTING AND REMOVE WIRING TO NEAREST SPLICE	EACH	1				1			

*SPECIALTY ITEMS

FILE NAME =	USER NAME = #USER#	DESIGNED - RRV	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#	PLOT SCALE = #SCALE#	DRAWN - JMC	REVISED -					70	82-2-1-IHB	ST. CLAIR	236	15
	PLOT DATE = #DATE#	CHECKED - DRH	REVISED -		SCALE:	SHEET NO. 11 OF 13 SHEETS	STA.	TO STA.	CONTRACT NO. 76C55			
		DATE - OCTOBER 15, 2009	REVISED -						ILLINOIS FED. AID PROJECT			