

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE - 100% STATE FUNDING					
CODE NO	ITEM	UNIT		ROADWAY	EXCHANGE AVE. BRIDGE S.N. 082-0378	RETAINING WALL S.N. 082-W301	LIGHTING	SIGNING	STRUCTURE DEMOLITION
			J000	X271 -2A	Y007	Y030 -1E	Y002 -1C	Y007	Y032 -1F
* X0325076	WIDE AREA NETWORK	L SUM							1
* X0325077	FIBER OPTIC UTILITY MARKER	EACH							12
* X0325271	ELECTRICAL CABLE IN CONDUIT NO. 12 3C	FOOT							220
* X0325462	MEDIA CONVERTER	EACH							3
* X0325751	DRIVING SOLDIER PILES	FOOT			1,351				
* X0329863	INTERCEPT EXISTING CONDUIT	EACH							2
X0342600	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH		1					
* X8100065	CONDUIT IN TRENCH, 4" DIA PVC TYPE C	FOOT							1,644
* X0321031	REMOVAL OF LUMINAIRE	EACH					12		
* X8710075	FIBER OPTIC CABLE IN CONDUIT, 72 COND. S.M. F.O.	FOOT							2,570
Z0007601	BUILDING REMOVAL NO. 1	L SUM						1	
Z0007602	BUILDING REMOVAL NO. 2	L SUM						1	
Z0013798	CONSTRUCTION LAYOUT	L SUM		1					
Z007603	BUILDING REMOVAL NO. 3	L SUM						1	
Z0017100	DOWEL BARS	EACH		40					
Z007604	BUILDING REMOVAL NO. 4	L SUM						1	
Z0018800	DRAINAGE SYSTEM	L SUM							
Z007605	BUILDING REMOVAL NO. 5	L SUM						1	
Z0022800	FENCE REMOVAL	FOOT		1,183					
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH		9					
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH		2					
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM		1					
* Z0049801	REMOVAL AND DISPOSAL OF FRIABLE ASBESTOS, BUILDING NO. 1	L SUM		1				1	
* Z0049901	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 1	L SUM		1				1	
* Z0049902	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 2	L SUM		1				1	
* Z0049903	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 3	L SUM		1				1	
* Z0049802	REMOVAL AND DISPOSAL OF FRIABLE ASBESTOS, BUILDING NO. 2	L SUM		1				1	

* SPECIALTY ITEMS

FILE NAME =	USER NAME = BUSER	DESIGNED - RRV	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN - JMC	REVISED -			70	82-2-1-1H	ST. CLAIR	236	16	
	PLOT SCALE = #SCALE#	CHECKED - DRH	REVISED -			SCALE: SHEET NO. 12 OF 13 SHEETS STA. TO STA.		CONTRACT NO. 76C55			
	PLOT DATE = #DATE#	DATE - OCTOBER 15, 2009	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

Rev