

### SUMMARY OF QUANTITIES

| PAY CODE  | CONSTRUCTION TYPE CODE: Y051                       | UNIT   | TOTAL QUANTITY |
|-----------|--|--------|----------------|
| 20200100  | EARTH EXCAVATION                                   | CU YD  | 476            |
| 20201000  | GRADING AND SHAPING ROADWAY                        | UNIT   | 12             |
| 20800150  | TRENCH BACKFILL                                    | CU YD  | 132            |
| 21101505  | TOPSOIL EXCAVATION AND PLACEMENT                   | CU YD  | 45             |
| 25000210  | SEEDING, CLASS 2A                                  | ACRE   | 0.03           |
| 25000400  | NITROGEN FERTILIZER NUTRIENT                       | POUND  | 2.8            |
| 25000500  | PHOSPHORUS FERTILIZER NUTRIENT                     | POUND  | 2.8            |
| 25000600  | POTASSIUM FERTILIZER NUTRIENT                      | POUND  | 2.8            |
| 25100105  | MULCH METHOD 1                                     | ACRE   | 0.03           |
| 28000400  | PERIMETER EROSION BARRIER                          | FOOT   | 78             |
| 28000510  | INLET FILTERS                                      | EACH   | 4              |
| 35100100  | AGGREGATE BASE COURSE, TYPE A                      | TON    | 45             |
| 35100500  | AGGREGATE BASE COURSE, TYPE A 6"                   | SQ YD  | 880            |
| 35100700  | AGGREGATE BASE COURSE, TYPE A 8"                   | SQ YD  | 1,000          |
| 40600100  | BITUMINOUS MATERIALS (PRIME COAT)                  | GALLON | 375            |
| 40603080  | HOT MIX ASPHALT BINDER COURSE IL-19.0 N50          | TON    | 120            |
| 40603310  | HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50       | TON    | 120            |
| 42300400  | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH | SQ YD  | 87             |
| 42400200  | PORTLAND CEMENT CONCRETE SIDEWALK 5-INCH           | SQ FT  | 5,565          |
| 44000161  | HOT-MIX ASPHALT SURFACE REMOVAL, 3"                | SQ YD  | 974            |
| 44000600  | SIDEWALK REMOVAL                                   | SQ FT  | 3,780          |
| 44004200* | PAVED FLUME REMOVAL                                | FOOT   | 15             |
| 44213200* | SAW CUTS   | FOOT   | 1,418          |

|            |   |       |     |
|------------|---|-------|-----|
| 50105220*  | PIPE CULVERT REMOVAL  | FOOT  | 60  |
| 542C0211   | PIPE CULVERTS, CLASS C, TYPE 1 6"                             | FOOT  | 51  |
| 542C0217   | PIPE CULVERTS, CLASS C, TYPE 1 12"                            | FOOT  | 37  |
| 542C0220   | PIPE CULVERTS, CLASS C, TYPE 1 15"                            | FOOT  | 12  |
| 54215550*  | METAL END SECTIONS 15"  | EACH  | 1   |
| 56109210*  | WATER VALVES TO BE ADJUSTED                                   | EACH  | 1   |
| 56300400*  | WATER SERVICE APPURTENANCE TO BE ADJUSTED                     | EACH  | 7   |
| 60242400*  | INLETS, SPECIAL   | EACH  | 3   |
| 60244240*  | GRATED INLET, SPECIAL   | EACH  | 1   |
| 60250500   | CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID | EACH  | 1   |
| 60603800   | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12             | FOOT  | 443 |
| 60604100*  | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (MODIFIED)  | FOOT  | 715 |
| 60617900*  | PAVED FLUME   | SQ YD | 10  |
| 66700110   | PERMENANT SURVEY MARKERS TO BE ADJUSTED                       | EACH  | 10  |
| 67100100*  | MOBILIZATION  | L SUM | 1   |
| 70103700*  | TRAFFIC CONTROL COMPLETE                                      | L SUM | 1   |
| X7240205*  | REMOVE SIGN COMPLETE  | EACH  | 5   |
| △ 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6"                      | FOOT  | 158 |
| △ 78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12"                     | FOOT  | 106 |
| XX006075   | DEPRESSED CURB RAMP ACCESSABLE TO THE DISABLED                | SQ FT | 276 |
| XX005468*  | TIMBER WALL REMOVAL   | FOOT  | 5   |
| 42400800   | DETECTABLE WARINGS  | SQ FT | 48  |
| XX006898   | STAMPED COLORED PORTLAND CEMENT CONCRETE                      | SQ FT | 595 |

\*SPECIAL PROVISION

△ SPECIALTY ITEMS

# MSA

PROFESSIONAL SERVICES  
TRANSPORTATION • MUNICIPAL  
DEVELOPMENT • ENVIRONMENTAL

|   |                     |                   |                           |
|---|---------------------|-------------------|---------------------------|
| FILE NAME = k:\plansh\3.SUMMARY OF QUAN.dgn | USER NAME = .Markw. | DESIGNED - MW, NW | REVISED - MAY 1, 2009     |
|   |                     | DRAWN - MW        | REVISED - MAY 12, 2009    |
|   |                     | CHECKED - PR      | REVISED - AUGUST 28, 2009 |
|   |                     | DATE -            | REVISED -                 |

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

| F.A. RTE.                 | SECTION        | COUNTY     | TOTAL SHEETS | SHEET NO. |
|---------------------------|----------------|------------|--------------|-----------|
|                           | 08-00043-00-SW | JO DAVIESS | 17           | 3         |
| CONTRACT NO.              |                |            |              |           |
| ILLINOIS FED. AID PROJECT |                |            |              |           |