

**SCHEDULE FOR LANDSCAPING ITEMS**

	21101505	25000210	25000400	25000500	25000600	25100105
	TOPSOIL EXCAVATION AND PLACEMENT	SEEDING, CLASS 2A	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH, METHOD 1
STATION	CU YD	ACRE	POUND	POUND	POUND	ACRE
20+91 - 32+76	45	0.03	2.8	2.8	2.8	0.03
TOTAL	45	0.03	2.8	2.8	2.8	0.03

**SCHEDULE FOR CULVERT REMOVAL**

	50105220*
	PIPE CULVERT REMOVAL
STATION	FOOT
27+21 - 27+55	36
27+55	14
29+64	10
TOTAL	60

**SCHEDULE OF PATCHING/SAWCUTS**

	44213200*	NOTES
STATION	SAW CUTS FOOT	
20+91 - 23+38	272	3 INCH BIT. PAVEMENT
23+38 - 23+58	67	3 INCH BIT. PAVEMENT
23+58 - 27+36	399	3 INCH BIT. PAVEMENT
27+36 - 27+47	50	3 INCH BIT. PAVEMENT
27+47 - 29+71	255	3 INCH BIT. PAVEMENT
29+71 - 29+87	60	3 INCH BIT. PAVEMENT
29+87 - 32+76	315	3 INCH BIT. PAVEMENT
TOTAL	1,418	

**SCHEDULE FOR EARTHWORK**

	20200100	20201000			
	EARTH EXCAVATION	GRADING AND SHAPING ROADWAY	FILL	CUT	EARTHWORK BALANCE
STATION	CU YD	UNIT	CY	CY	CY
20+91 - 32+76	476	12	0	476	476
TOTAL	476	12	0	476	476

**SCHEDULE FOR PIPE CULVERTS**

	20800150	54200211	54200217	54200220	54215550*
	TRENCH BACKFILL	PIPE CULVERTS, CLASS C TYPE 1 6"	PIPE CULVERTS, CLASS C TYPE 1 12"	PIPE CULVERTS, CLASS C TYPE 1 15"	METAL END SECTIONS 15"
STATION	CU YD	FOOT	FOOT	FOOT	EACH
21+04 - 21+10	6		6		
27+20 - 27+55	32		31		
27+55 LT	12			12	1
27+55 - 28+00	7	41			
29+64		10			
TOTAL	57	51	37	12	1

**SCHEDULE FOR CATCH BASINS/INLETS**

	20800150	60242400*	60244240*	60250500
	TRENCH BACKFILL	INLETS, SPECIAL	GRATED INLET, SPECIAL	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID
STATION	CY	EACH	EACH	EACH
21+04				1
21+10	24	1		
27+20	24	1		
27+55	24	1		
28+00	2		1	
TOTAL	75	3	1	1

**SCHEDULE FOR EROSION CONTROL**

	28000400	28000510
	PERIMETER EROSION BARRIER	INLET FILTERS
STATION	FOOT	EACH
20+93 - 21+01	9	
21+03		1
23+23 - 23+29	6	
23+58 - 23+62	5	
27+17 - 27+32	15	
27+20		1
27+55		1
27+50 - 27+66	15	
28+00		1
29+56 - 29+69	14	
29+91 - 30+05	14	
TOTAL	78	4

**SCHEDULE FOR UTILITY ADJUSTMENTS**

	56300400*	56109210*
	WATER SERVICE APPURTENANCE TO BE ADJUSTED	WATER VALVES TO BE ADJUSTED
STATION	EACH	EACH
21+77	1	
24+89	1	
25+56	1	
26+00	1	
26+70	1	
26+85	1	
27+99	1	
29+81		1
TOTAL	7	1

**SCHEDULE FOR SURFACE REMOVAL**

	44000161	44004200*	44000600
	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	PAVED FLUME REMOVAL	SIDEWALK REMOVAL
STATION	SQ YD	FOOT	SQ FT
20+91 - 23+38	150		
20+96 - 23+31			855
23+38 - 23+58	92		
23+58 - 27+36	238		
23+69 - 27+28			1,287
27+36 - 27+47	51		
27+52 - 29+67			909
27+55		15	
27+58 - 29+71	110		
29+71 - 29+87	68		
29+87 - 32+76	265		
30+00 - 32+76			729
TOTAL	974	15	3,780



FILE NAME = kt:\plan\shfts\5_SCHEDULE OF QUAN.dgn	USER NAME = .Markw.	DESIGNED - MW, NW	REVISED - MAY 1, 2009
		DRAWN - MW	REVISED - MAY 12, 2009
		CHECKED - PR	REVISED - AUGUST 28, 2009
		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>SCHEDULE OF QUANTITIES</b>			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	08-00043-00-SW	JO DAVIESS	17	5
CONTRACT NO.				
ILLINOIS FED. AID PROJECT				