

### SCHEDULE FOR PORTLAND CEMENT CONCRETE

	42300400	42400200	XX006075	42400800	XX006888
	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH SQ YD	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH SQ FT	DEPRESSED CURB RAMP ACCESSABLE TO THE DISABLED, SQ FT	DETECTABLE WARNINGS SQ FT	STAMPED COLORED POTRLAND CEMENT CONCRETE SQ FT
STATION					
20+96 - 21+07			41	6	
21+07 - 23+25		1,330			
23+25 - 23+33			34	6	
23+63 - 23+72			35	6	
23+72 - 24+84		728			
24+84 - 25+02	12				
25+02 - 25+33		189			
25+33 - 25+51	12				
25+51 - 25+80		175			
25+80 - 25+99	11				
25+99 - 26+21		123			
26+21 - 26+43	13				
26+43 - 27+13		348			
27+13 - 27+27	16				
27+27 - 27+31			16	6	
27+51 - 27+57			34	6	
27+52 - 29+75					595
27+57 - 29+59		1,241			
29+59 - 29+66			40	6	
29+93 - 30+01			37	6	
30+01 - 31+06		669			
31+06 - 31+23	11				
31+23 - 32+07		505			
32+07 - 32+25	12				
32+25 - 32+61		257			
32+61 - 32+70			39	6	
TOTAL	87	5565	276	48	595

### SCHEDULE FOR CURB AND GUTTER

	60603800	60604100*	60617900*
	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (MODIFIED)	PAVED FLUME
STATION	FOOT	FOOT	SQ YD
20+94 - 23+34		250	
23+61 - 25+02	142		
25+02 - 25+34		32	
25+34 - 25+99	65		
25+99 - 27+31		140	
27+49 - 29+68	236		
27+55			6
29+92 - 32+70		293	
29+64			4
TOTAL	443	715	10

### SCHEDULE FOR PAVEMENT MARKING

	78000400	78000600	
	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	REMARKS
STATION	FOOT	FOOT	
23+28 - 23+67	66	55	WHITE
27+31 - 27+51	38	21	WHITE
29+66 - 29+97	54	30	WHITE
TOTAL	158	106	

### SCHEDULE FOR SIGNS

	X7240205*
	REMOVE SIGN COMPLETE EACH
STATION	
20+91 - 32+76	5
TOTAL	5

### SCHEDULE FOR MARKERS

	66700110
	PERMANENT SURVEY MARKERS TO BE ADJUSTED EACH
STATION	
20+91 - 32+76	10
TOTAL	10

### SCHEDULE OF HOT-MIX ASPHALT

	40600100	40603080	40603310
	BITUMINOUS MATERIALS (PRIME COAT) GALLON	HOT-MIX ASPHALT BINDER COURSE, IL-19.0 N50 TON	HOT-MIX ASPHALT SURFACE COURSE, MIX "C" N50 TON
STATION			
20+91 - 32+76	375	120	120
TOTAL	375	120	120

### SCHEDULE OF BASE COURSE

		35100100	35100500	35100700
		AGGREGATE BASE COURSE, TYPE A TON	AGGREGATE BASE COURSE, TYPE A 6" SQ YD	AGGREGATE BASE COURSE TYPE A 8" SQ YD
STATION	LOCATION			
20+91 - 32+76		45	880	1,000
TOTAL		45	880	1,000

### SCHEDULE OF RETAINING WALL

	XX005468*
	TIMBER WALL REMOVAL
STATION	FOOT
23+67 LT	5
TOTAL	5



**PROFESSIONAL SERVICES**  
TRANSPORTATION • MUNICIPAL  
DEVELOPMENT • ENVIRONMENTAL

FILE NAME =	USER NAME = .Markw.	DESIGNED - MW, NW	REVISED - MAY 1, 2009
kt:\plansh\6.SCHEDULE OF QUAN.dgn		DRAWN - MW	REVISED - MAY 12, 2009
		CHECKED - PR	REVISED - AUGUST 28, 2009
		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

### SCHEDULE OF QUANTITIES

SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
				08-00043-00-SW	JO DAVIESS	17	6
						CONTRACT NO.	
ILLINOIS FED. AID PROJECT							