



ALIGNMENT DATA

ITEM	CONTROL POINT	STATION	NORTHING	EASTING	Direction	Distance
L1	BOA-BEGIN OF ALIGNMENT	20+00.00	2095650.42	2224568.72	N 42°06'13" W	333.66
L2	PI	23+33.66	2095897.97	2224345.01	N 38°53'58" W	28.17
L3	PI	23+61.83	2095919.90	2224327.32	N 41°55'42" W	368.82
L4	PI	27+30.65	2096194.30	2224080.87	N 50°29'26" W	19.23
L5	PI	27+49.89	2096206.53	2224066.03	N 35°48'33" W	217.89
L6	PI	29+67.78	2096383.24	2223938.54	N 33°16'11" W	24.93
L7	PI	29+92.71	2096404.08	2223924.86	N 34°56'38" W	277.26
L8	PI	32+69.97	2096631.35	2223766.06	N 35°22'51" W	30.22
	EOA-END OF ALIGNMENT	33+00	2096655.84	2223748.67		

CONTROL POINTS

#	Northing	Easting	Description	Elevation
53	2095716.00	2224498.16	NAIL	781.83
54	2095410.10	2224825.72	NAIL	785.61
58	2096201.05	2224121.38	CONTROL PNT	787.63
59	2097004.50	2223537.42	CONTROL PNT	794.16
60	2094972.36	2224783.34	NAIL	785.61



FILE NAME = k:\plansh\7.ALIGNMENT CONTROL.dgn	USER NAME = Markw.	DESIGNED - MW, NW	REVISED - MAY 1, 2009
		DRAWN - MW	REVISED - MAY 12, 2009
		CHECKED - PR	REVISED - AUGUST 28, 2009
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCALE:	SHEET NO. OF SHEETS	STA. TO STA.
--------	---------------------	--------------

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	08-00043-00-SW	JO DAVIESS	17	7
CONTRACT NO.				
ILLINOIS FED. AID PROJECT				