


FAU. ROUTE NO.	SECTION	ILLINOIS PROJECT	CONTRACT NO.	COUNTY	TOTAL SHEETS	SHEET NUMBER
VARIES	09-00161-00-SW	SRTS-4008(108)	87408	LASALLE	15	3

	CURB & GUTTER REMOVAL & REPLACEMENT (FOOT)	SIDEWALK REMOVAL (SQUARE FOOT)	DRIVEWAY PAVEMENT REMOVAL (SQUARE YARD)	TOPSOIL EXCAVATION & PLACEMENT (CUBIC YARD)	AGGREGATE BASE COURSE, TYPE B, 2" (TON)	AGGREGATE BASE COURSE, TYPE B, 4" (TON)	PCC SIDEWALK, 4" (SQUARE FOOT)	ALUMINUM RAILING (FOOT)	PCC DRIVEWAY PAVEMENT, 7" (SQUARE YARD)	PAVEMENT REMOVAL & REPLACEMENT (SQUARE YARD)	DETECTABLE WARNING (SQUARE FOOT)	SEEDING, FERTILIZER & EROSION CONTROL BLANKET (SQUARE YARD)	TREE REMOVAL (6-15 UNIT DIAMETER) (UNIT)	TREE REMOVAL (OVER 15 UNIT DIAMETER) (UNIT)
<b>MCKINLEY SCHOOL (STATE STREET)</b>														
STA. 5+57 - LT.	13.0	36.0					2035.0				6	1.8		
STA. 5+92 TO STA. 10+00 - LT.	13.0			70.0	26.0						6	226.7		
STA. 5+96 - LT.		74.0					9.0							
STA. 6+39 - LT.			13.6	4.0		3.0		13.6				4.0		
STA. 7+10 - LT.			21.1	6.0		5.0		21.1				1.3		
STA. 7+71 - LT.			25.4	6.0		6.0		25.4				4.9		
STA. 8+50 - LT.			34.5	4.0		8.0		34.5				92.7		
STA. 9+47 - LT.				31.0	13.0		1020.0					3.1		
STA. 10+00 TO STA. 12+04 - LT.			22.7	4.0		5.0		22.7				0.9		
STA. 10+12 - LT.			16.8	3.0		4.0		16.8						
STA. 10+30 - LT.			10.1	2.0		2.0		10.1						
STA. 10+87 - LT.			12.3	2.0		3.0		12.3						
STA. 11+61 - LT.														
<b>MCKINLEY SCHOOL (VIEW STREET)</b>														
STA. 20+50 TO STA. 23+37 - LT.				33.0	18.0		1455.0					80.6		
STA. 20+50 TO STA. 22+13 - RT.	10.0			19.0	4.0		834.0				6	47.5		
STA. 20+53 - RT.	10.0										6		12	
STA. 20+53 - LT.														
STA. 21+21 - RT.			29.9	9.0		7.0		29.9				12.0		
STA. 21+23 - LT.			20.9	3.0		5.0		20.9				3.0		
STA. 21+67 - LT.	11.0										6			
STA. 22+10 - RT.														
STA. 22+43 TO STA. 23+44 - RT.	12.0			14.0	6.0		504.0				6			
STA. 22+46 - RT.														
STA. 22+50 - LT.			44.7	12.0		10.0		44.7				10.3		18
STA. 22+96 - LT.														
<b>MCKINLEY SCHOOL (W. MCKINLEY RD.)</b>														
STA. 10+88.5 TO STA. 16+11.5 - LT.				50.0	34.0		2673.0							
STA. 16+05 - LT.											12			
STA. 16+61 - LT.											6			
STA. 16+53 TO STA. 18+18 - LT.				15.0	10.0		804.0							
STA. 18+42 TO STA. 19+00 - LT.				5.0	4.0		279.0							
STA. 19+23 TO STA. 19+75 - LT.				5.0	3.0		246.0							
STA. 20+10 TO STA. 20+55 - LT.				4.0	3.0		209.0							
STA. 20+91 TO STA. 21+36 - LT.				4.0	3.0		213.0							
STA. 21+71 TO STA. 22+16 - LT.				4.0	3.0		212.0							
STA. 22+54 TO STA. 22+97 - LT.				4.0	3.0		206.0							
STA. 23+34 TO STA. 23+77 - LT.				4.0	3.0		204.0							
STA. 24+11 TO STA. 24+74 - LT.				6.0	4.0		308.0				6			
STA. 25+04 TO STA. 25+49 - LT.				4.0	3.0		209.0							
STA. 25+43 - LT.														
STA. 25+95 TO STA. 26+53 - LT.				12.0	8.0		638.0				12			
STA. 25+99 - LT.														
STA. 26+78 TO STA. 28+09 - LT.				12.0	8.0		642.0							
STA. 28+34 TO STA. 30+77 - LT.				24.0	17.0		1310.0				6			
STA. 30+72 - LT.														
<b>MCKINLEY SCHOOL (STATE &amp; CATHERINE)</b>														
M1	60.0				0.3		23.0					1.0		
M2		23.0			0.3		23.0					1.0		
M3		23.0			0.6		45.0			1.7	6	2.0		
M4		45.0			0.9		75.0							
M5	15.0	75.0												
<b>MCKINLEY SCHOOL (East Entrance)</b>		2069.0		16.0	40.0		1839.0	43.0				71.0		
<b>LINCOLN SCHOOL</b>														
L1		295.0			3.7		295.0							
L2		265.0			3.4		265.0					23.6		
L3		631.0			8.0	0.8	631.0		3.3			40.0		
L4			3.3											
L5		495.0			6.3		495.0					35.1		
L6		70.0			0.9		70.0					6.2		
L7		200.0			2.5		200.0					8.9		
<b>SHEPHERD SCHOOL</b>														
S1	10.0						430.0			1.1	6	35.6		
S2				8.0	5.4					1.1	6	2.2		
S3	10.0						160.0			2.2	6	93.3		
S4	20.0	160.0		22.0	15.1		1195.0			1.1	6	3.1		
S5										1.1	6	3.1		
S6	10.0						29.0			1.1	6			
S7	10.0	29.0			0.4		41.0			1.1	6			
S8	10.0	41.0			0.5					1.1	6			
<b>CENTRAL SCHOOL</b>														
C1		30.0			0.4		30.0					1.1		
C2		30.0			0.4		30.0					1.1		
C3		48.0			0.6		48.0					1.8		
C4		72.0			0.9		72.0					2.7		
C5		72.0			0.9		72.0					2.7		
C6		30.0			0.4		30.0					1.1		
C7		144.0			1.8		144.0					5.3		
C8		72.0			0.9		72.0					2.7		
C9		72.0			0.9		72.0					2.7		
C10		30.0			0.4		30.0					1.1		
C11		30.0			0.4		30.0					1.1		
<b>JEFFERSON SCHOOL</b>														
J1	9.0	550.0			7.0		550.0			2.8	6	45.3		
J2		50.0			0.6		50.0					4.4		
J3		108.0			1.4		108.0					1.3		
J4		126.0			1.6		126.0					1.3		
J5	13.0						50.0			1.4		4.4		
J6		50.0			0.6		50.0							
J7	10.0	50.0			0.6		50.0			1.1	6			
J8	18.0	261.0			3.3		261.0				12			
J9	10.0	42.0			0.5		42.0			1.1	6	2.2		
<b>TOTALS</b>	<b>274</b>	<b>6398</b>	<b>255</b>	<b>420</b>	<b>286.9</b>	<b>59</b>	<b>21693</b>	<b>43</b>	<b>255.3</b>	<b>15.9</b>	<b>144</b>	<b>897.3</b>	<b>12</b>	<b>18</b>

**SUMMARY OF QUANTITIES AND DETAILS**  
**SAFE ROUTES TO SCHOOLS SIDEWALK IMPROVEMENTS**

**RENWICK & ASSOCIATES, INC.**

228 West Main Street  
Ottawa, Illinois 61350  
TEL: 815-434-3200  
FAX: 815-434-3968



PROFESSIONAL DESIGN FIRM # 184-004857 FILE NO. 09.2.1  
DRAWN BY: RTF CHECKED BY: DAP DATE PLOTTED: DECEMBER 21, 2009  
FILE PATH: C:\CITY OF OTTAWA\09.2.1-MCKIN SCHOOL\DETAIL SHEET.DGN