

TABULATION OF QUANTITIES

FAS ROUTE NO.	COUNTY	SECTION	CONTRACT	SHEET NO.	TOTAL SHEETS
1254	PUTNAM	07-00020-00-RS	89413	2	4

40600300 AGGREGATE (PRIME COAT)

LOCATION	WIDTH	QUANTITY REQUIRED
STA. 0+63-104+00	29.0'	<u>50 TON</u> 50 TON
RATE OF APPL. = 3 LB/S.Y.		TOTAL 50 TON (USE 50 TON)

70300100 SHORT-TERM PAVEMENT MARKING

LOCATION	WIDTH	QUANTITY REQUIRED
STA. 0+63-104+00 2 APPLICATIONS	4"	<u>2068.0 FOOT</u> 2068.0 FOOT
		TOTAL 2068.0 FOOT (USE 2068 FOOT)

40600100 BITUMINOUS MATERIALS (PRIME COAT)

LOCATION	WIDTH	QUANTITY REQUIRED
STA. 0+63-104+00 (MAIN LANES)	29	3330.8
ENTIRE SECTION (ENTRANCES)	VAR.	<u>26.7 GAL</u>
RATE OF APPL. = 0.1 GAL/S.Y.		TOTAL 3357.5 GAL (USE 3358 GAL)

70300220 TEMPORARY PAVEMENT MARKING LINE 4"

LOCATION	WIDTH	QUANTITY REQUIRED
	4"	<u>27372.0 FOOT</u> 27372.0 FOOT
		TOTAL 27372.0 FOOT (USE 27372 FOOT)

40600982 HOT-MIX ASPHALT SURFACE REMOVAL BUTT JOINT

LOCATION	WIDTH	QUANTITY REQUIRED
STA. 0+63	VAR.	98.0 SQ YD
STA. 104+00	VAR.	<u>54.0 SQ YD</u> 152.0 SQ YD
		TOTAL 152.0 SQ YD (USE 152 SQ YD)

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

LOCATION	WIDTH	QUANTITY REQUIRED
STA. 0+63-104+00	4"	<u>345.0 SQ FT</u> 345.0 SQ FT
		TOTAL 345.0 SQ FT (USE 345 SQ. FT)

40603310 HOT-MIX ASPHALT SURFACE COURSE MIX "C" N50

LOCATION	WIDTH	QUANTITY REQUIRED
STA. 0+63-104+00 (MAIN LANES)	29.0'	2797.8 TON
ENTIRE SECTION (ENTRANCES)	VAR.	22.3 TON
ENTIRE SECTION (MAILBOX TURNOUTS)	VAR.	2.4 TON
		<u>2822.5 TON</u>
RATE OF APPL. = 112 LB./S.Y./IN.		TOTAL 2822.3 (USE 2823 TON)

78001110 PAINT PAVEMENT MARKING - 4"

LOCATION	WIDTH	QUANTITY REQUIRED
STA. 6+15-99+00 (CENTERLINE)	4"	2322 FOOT
STA. 0+63-104+00 (EDGE LINES)	4"	20674 FOOT
ENTIRE SECTION (NO PASSING)	4"	<u>4376 FOOT</u> 27372 FOOT
		TOTAL 27372 FOOT

48101200 AGGREGATE SHOULDERS, TYPE B

LOCATION	WIDTH	QUANTITY REQUIRED
LT. STA. 0+63-104+00	1.0'	99.5 TON
RT. STA. 11+40-20+50	1.0'	8.76 TON
RT. STA. 57+90-59+10	1.0'	1.15 TON
RT. STA. 61+90-104+00	1.0'	<u>40.54 TON</u> 149.95 TON
RATE OF APPL. = 2.08T/C.Y.		TOTAL 149.95 TON (USE 150 TON)