

CONTRACT NO. 89476

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
358	86-00075-01-AS	WOODFORD	66	3
STA.	TO STA.			
FED. ROAD DIST. NO. 4	ILLINOIS	FED. AID	PROJECT	

SUMMARY OF QUANTITIES

PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	28881
20400800	FURNISHED EXCAVATION	CU YD	231
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	500
25000100	SEEDING, CLASS 1	ACRE	0.86
25000200	SEEDING, CLASS 2	ACRE	20.06
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1883
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1883
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1883
25100115	MULCH, METHOD 2	ACRE	20.92
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	1533
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	6277
28000305	TEMPORARY DITCH CHECKS	FOOT	2430
28000400	PERIMETER EROSION BARRIER	FOOT	16693
28000500	INLET AND PIPE PROTECTION	EACH	25
28100107	STONE RIPRAP, CLASS A4	SQ YD	3106
28200200	FILTER FABRIC	SQ YD	3106
35101400	AGGREGATE BASE COURSE, TYPE B	TON	32432
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	1082
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	800
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	63
50105200	REMOVE EXISTING CULVERTS	EACH	28
54000900	BOX CULVERT END SECTIONS, SPECIAL	EACH	2
54001000	BOX CULVERT END SECTIONS	EACH	4
54010602	PRECAST CONCRETE BOX CULVERT 6' X 2'	FOOT	78
54020403	PRECAST CONCRETE BOX CULVERT 4' X 3' (M273)	FOOT	68
54213879	STEEL END SECTIONS 24"	EACH	3
54213885	STEEL END SECTIONS 30"	EACH	3

SUMMARY OF QUANTITIES

PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
54213891	STEEL END SECTIONS 36"	EACH	2
54215139	STEEL END SECTIONS, EQUIVALENT ROUND-SIZE 24"	EACH	4
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	490
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	288
542D5479	PIPE CULVERTS, CLASS D, TYPE 1, EQUIVALENT ROUND-SIZE 24"	FOOT	146
542C0229	PIPE CULVERTS, CLASS C, TYPE 1 24"	FOOT	139
542C1069	PIPE CULVERTS, CLASS C, TYPE 2 24"	FOOT	72
542C1075	PIPE CULVERTS, CLASS C, TYPE 2 30"	FOOT	132
542C1081	PIPE CULVERTS, CLASS C, TYPE 2 36"	FOOT	64
542C5479	PIPE CULVERTS, CLASS C, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	72
60222250	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 37 GRATE	EACH	1
60222900	MANHOLES, TYPE A, 5'-DIAMETER	EACH	2
61139900	STORM SEWERS, SPECIAL 6"	FOOT	300
61140000	STORM SEWERS, SPECIAL 8"	FOOT	300
61140100	STORM SEWERS, SPECIAL 10"	FOOT	300
61140200	STORM SEWERS, SPECIAL 12"	FOOT	300
61140400	STORM SEWERS, SPECIAL 15"	FOOT	300
61140600	STORM SEWERS, SPECIAL 18"	FOOT	300
67100100	MOBILIZATION	L SUM	1
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
X0324079	EXISTING FIELD TILE REMOVAL	FOOT	30
XX006675	FIELD TILE REPLACEMENT	FOOT	30
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
54020812	PRECAST CONCRETE BOX CULVERT 8' X 2.5' (M273)	FOOT	64

PLOT DATE = 09/15/09
 PLOT SCALE = 1"=40'
 PLOT SCALE = 1"=40'
 USER NAME = MUSEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DESIGNED BY: AMPH & KLM
 DATE: NOVEMBER 2009

DRAWN BY: AMPH & KLM
 CHECKED BY: JLH & RAH