

F.A. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
358	B6-00075-01-AS	WOODFORD	66	11
STA.	TO STA.			
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

TEMPORARY DITCH CHECK SCHEDULE (5 OF 6)				
LOCATION	DISTANCE	SLOPE	AVG. SPACING	28000305
STATION TO STATION	FEET	%	FEET	TEMPORARY DITCH CHECKS FOOT
LEFT SIDE				
STA. 61+00.00 LT TO STA. 61+70.00 LT	70	0.56	200	
STA. 63+67.00 LT TO STA. 65+00.00 LT	133	1.00	150	
STA. 65+00.00 LT				10
STA. 65+00.00 LT TO STA. 67+00.00 LT	200	0.59	200	
STA. 67+00.00 LT				10
STA. 67+00.00 LT TO STA. 71+00.00 LT	400	1.65	94	
STA. 67+90.00 LT				10
STA. 68+80.00 LT				10
STA. 69+70.00 LT				10
STA. 70+60.00 LT				10
STA. 71+00.00 LT TO STA. 72+00.00 LT	100	2.20	68	
STA. 71+40.00 LT				10
STA. 72+00.00 LT				10
STA. 72+00.00 LT TO STA. 73+90.00 LT	190	2.76	56	
STA. 72+50.00 LT				10
STA. 73+00.00 LT				10
STA. 73+50.00 LT				10
STA. 73+90.00 LT TO STA. 77+00.00 LT	310	2.54	60	
STA. 74+00.00 LT				10
STA. 74+60.00 LT				10
STA. 75+20.00 LT				10
STA. 75+80.00 LT				10
STA. 76+40.00 LT				10
STA. 77+00.00 LT				10
STA. 77+00.00 LT TO STA. 79+00.00 LT	200	1.79	88	
STA. 77+80.00 LT				10
STA. 78+60.00 LT				10
STA. 79+00.00 LT TO STA. 79+80.00 LT	80	2.70	56	
STA. 79+30.00 LT				10
STA. 79+80.00 LT TO STA. 80+20.00 LT	40	5.40	28	
STA. 80+20.00 LT TO STA. 82+00.00 LT	180	0.50	200	
STA. 80+50.00 LT				10
STA. 82+00.00 LT TO STA. 86+00.00 LT	400	0.40	200	
STA. 84+00.00 LT				10
STA. 86+00.00 LT				10
STA. 86+00.00 LT TO STA. 86+68.00 LT	68	1.04	150	
STA. 86+68.00 LT TO STA. 88+00.00 LT	132	1.39	115	
STA. 87+50.00 LT				10
STA. 88+00.00 LT TO STA. 93+50.00 LT	550	2.56	60	
STA. 88+20.00 LT				10
STA. 90+60.00 LT				10
STA. 91+20.00 LT				10
STA. 91+80.00 LT				10
STA. 92+40.00 LT				10
STA. 93+50.00 LT TO STA. 95+50.00 LT	200	1.20	125	
STA. 93+00.00 LT				10
STA. 94+25.00 LT				10
STA. 96+43.00 LT TO STA. 98+00.00 LT	157	0.30	200	
STA. 97+40.00 LT				10
STA. 98+00.00 LT TO STA. 101+00.00 LT	300	1.17	136	
STA. 98+90.00 LT				10
STA. 100+25.00 LT				10
STA. 101+00.00 LT TO STA. 103+79.50 LT	279.5	0.66	200	
STA. 103+79.50 LT TO STA. 109+00.00 LT	520.5	0.30	200	
STA. 105+75.00 LT				10
STA. 107+75.00 LT				10
STA. 109+00.00 LT TO STA. 111+25.00 LT	225	0.91	200	
STA. 109+75.00 LT				10
STA. 111+25.00 LT TO STA. 114+00.00 LT	275	0.72	200	
STA. 112+00.00 LT				10
STA. 114+00.00 LT TO STA. 115+75.00 LT	175	1.30	115	
STA. 115+00.00 LT				10
STA. 116+67.00 LT TO STA. 118+00.00 LT	133	2.50	60	
STA. 117+30.00 LT				10
STA. 117+90.00 LT				10
SUBTOTAL 5				410

TEMPORARY DITCH CHECK SCHEDULE (6 OF 6)				
LOCATION	DISTANCE	SLOPE	AVG. SPACING	28000305
STATION TO STATION	FEET	%	FEET	TEMPORARY DITCH CHECKS FOOT
LEFT SIDE				
STA. 118+00.00 LT TO STA. 121+00.00 LT	300	1.19	136	
STA. 119+00.00 LT				10
STA. 121+00.00 LT TO STA. 122+50.00 LT	150	1.54	100	
STA. 121+50.00 LT				10
STA. 125+00.00 LT TO STA. 126+00.00 LT	100	2.10	71	
STA. 125+75.00 LT				10
STA. 126+00.00 LT TO STA. 128+50.00 LT	250	1.76	88	
STA. 126+50.00 LT				10
STA. 127+40.00 LT				10
STA. 128+30.00 LT				10
STA. 128+50.00 LT TO STA. 133+00.00 LT	450	0.40	200	
STA. 130+00.00 LT				10
STA. 132+00.00 LT				10
STA. 133+00.00 LT TO STA. 134+50.00 LT	150	0.85	200	
STA. 136+00.00 LT				10
STA. 134+50.00 LT TO STA. 140+15.00 LT	565	0.13	200	
STA. 138+00.00 LT				10
STA. 140+15.00 LT TO STA. 141+50.00 LT	135	0.80	200	
STA. 141+00.00 LT				10
STA. 141+50.00 LT TO STA. 144+00.00 LT	250	2.08	75	
STA. 142+00.00 LT				10
STA. 144+00.00 LT TO STA. 145+00.00 LT	100	1.83	83	
STA. 144+25.00 LT				10
STA. 145+00.00 LT				10
STA. 145+00.00 LT TO STA. 149+00.00 LT	400	0.85	200	
STA. 147+00.00 LT				10
STA. 149+00.00 LT				10
STA. 149+00.00 LT TO STA. 151+00.00 LT	200	0.30	200	
STA. 151+00.00 LT TO STA. 155+00.00 LT	400	1.50	100	
STA. 152+00.00 LT				10
STA. 153+00.00 LT				10
STA. 154+00.00 LT				10
STA. 155+00.00 LT				10
STA. 155+00.00 LT TO STA. 157+00.00 LT	200	0.50	200	
STA. 157+00.00 LT				10
STA. 157+00.00 LT TO STA. 160+00.00 LT	300	1.17	136	
STA. 158+25.00 LT				10
STA. 159+60.00 LT				10
STA. 160+00.00 LT TO STA. 162+00.00 LT	200	0.55	200	
STA. 161+40.00 LT				10
STA. 162+00.00 LT TO STA. 165+00.00 LT	300	0.30	200	
STA. 163+40.00 LT				10
STA. 165+00.00 LT TO STA. 167+00.00 LT	200	1.31	115	
STA. 165+50.00 LT				10
STA. 166+50.00 LT				10
ALONG TR 1500 N				
STA. 1500+50 RT				10
STA. 1503+00 RT				10
SUBTOTAL 6				290
SUBTOTAL 1				480
SUBTOTAL 2				420
SUBTOTAL 3				360
SUBTOTAL 4				470
SUBTOTAL 5				410
SUBTOTAL 6				290
GRAND TOTAL				2430

PLOT DATE = 11/04/09
 FILE NAME = 89476.DWG
 USER = JAH

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

DESIGNED BY: AMPH & KLM DRAWN BY: AMPH & KLM
 DATE: NOVEMBER 2009 CHECKED BY: JAH & RAH