

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAU 6679	09-00066-01-SW	PEORIA	24	4
FEDERAL ROAD DIST NO.		ILLINOIS	CONTRACT NO. 8969	

**CURB & GUTTER REMOVAL**

LOCATION	QUANTITY
<b>PFEIFFER ROAD</b>	
LT. STA. 119+36 TO LT. STA. 119+48.3	18
LT. STA. 119+79.3 TO LT. STA. 130+65.6	1109
LT. STA. 131+00.3 TO LT. STA. 138+48.8	771
LT. STA. 138+79.4 TO LT. STA. 142+62.4	414
LT. STA. 142+90.0 TO LT. STA. 145+40.6	269
LT. STA. 145+84.7 TO LT. STA. 155+62.7	1015
PROJECT TOTAL	3596

**COMB. CONCRETE CURB & GUTTER  
TYPE B-6.12**

LOCATION	QUANTITY
<b>PFEIFFER ROAD</b>	
LT. STA. 119+36 TO LT. STA. 119+48	19
LT. STA. 119+77.9 TO LT. STA. 123+81.9	422
LT. STA. 124+01.9 TO LT. STA. 130+61.2	663
LT. STA. 130+66.4 TO LT. STA. 130+66.4	2
LT. STA. 131+02.7 TO LT. STA. 138+49.10	773
LT. STA. 138+78.4 TO LT. STA. 142+36.9	378
LT. STA. 142+49.8 TO LT. STA. 142+57.0	9
LT. STA. 142+63.1 TO LT. STA. 142+63.9	23
LT. STA. 142+89.9 TO LT. STA. 143+76.4	114
LT. STA. 143+96.4 TO LT. STA. 145+40.6	152
LT. STA. 145+84.7 TO LT. STA. 145+80.1	9
LT. STA. 145+82.9 TO LT. STA. 155+62.7	1010
PROJECT TOTAL	3574

**PAVEMENT REMOVAL**

LOCATION	QUANTITY
<b>PFEIFFER ROAD</b>	
LT. STA. 119+79 TO LT. STA. 130+66	1296 S.Y.
LT. STA. 131+00 TO LT. STA. 138+49	920
LT. STA. 138+78.4 TO LT. STA. 142+63.9	477
LT. STA. 142+90 TO STA. 145+40.6	286
LT. STA. 145+85 TO STA. 155+63	1127
PROJECT TOTAL	4106 S.Y.

**P.C.C SIDEWALK, 4"**

LOCATION	QUANTITY
<b>PFEIFFER ROAD</b>	
LT. STA. 118+15.20 TO LT. STA. 118+35.4	59 S.F.
LT. STA. 118+59.60 TO LT. STA. 119+42.7	798
LT. STA. 119+79.7 TO LT. STA. 120+73.0	1019
LT. STA. 121+17.1 TO LT. STA. 128+89.9	7729
LT. STA. 129+33.9 TO LT. STA. 129+41.1	72
LT. STA. 129+33.9 TO LT. STA. 130+55.0	615
LT. STA. 131+11.4 TO LT. STA. 132+58.0	1462
LT. STA. 133+02.0 TO LT. STA. 133+84.3	823
LT. STA. 134+28.3 TO LT. STA. 134+47.3	190
LT. STA. 134+95.5 TO LT. STA. 135+17.1	216
LT. STA. 135+69.1 TO LT. STA. 136+20.4	513
LT. STA. 136+92.7 TO LT. STA. 138+42.9	322
LT. STA. 138+84.2 TO LT. STA. 139+35.1	505
LT. STA. 139+82.9 TO LT. STA. 140+68.9	860
LT. STA. 141+41.0 TO LT. STA. 141+62.0	210
LT. STA. 142+06.0 TO LT. STA. 142+61.8	747
LT. STA. 142+92.6 TO LT. STA. 144+74.9	2003
LT. STA. 145+15.9 TO LT. STA. 145+28.7	113
LT. STA. 145+87.3 TO LT. STA. 147+54.5	1664
LT. STA. 147+98.5 TO LT. STA. 148+40.0	416
LT. STA. 148+88.6 TO LT. STA. 149+02.5	139
LT. STA. 149+57.6 TO LT. STA. 149+82.7	251
LT. STA. 150+30.7 TO LT. STA. 150+58.8	281
LT. STA. 151+02.8 TO LT. STA. 151+31.1	284
LT. STA. 151+80.7 TO LT. STA. 152+03.3	226
LT. STA. 152+47.0 TO LT. STA. 153+37.0	911
LT. STA. 153+92.2 TO LT. STA. 155+61.0	1796
PROJECT TOTAL	24224 S.F.

**SIDEWALK REMOVAL**

LOCATION	QUANTITY
<b>PFEIFFER ROAD</b>	
LT. STA. 118+15.2 TO LT. STA. 118+35.40	99 S.F.
LT. STA. 118+59.7 TO LT. STA. 119+06	210
LT. STA. 142+36.63 TO LT. STA. 142+63.9	309
LT. STA. 142+92.64 TO LT. STA. 144+90.50	1072
LT. STA. 155+54	43
PROJECT TOTAL	1733 S.F.

**PAVEMENT MARKING REMOVAL**

LOCATION	QUANTITY
<b>PFEIFFER ROAD</b>	
CL. STA. 143+17	20 S.F.
CL. STA. 143+03 & 143+11	28

**PAVEMENT MARKINGS**

LOCATION	QUANTITY
<b>THERMOPLASTIC PAVEMENT MARKINGS, LINE 24"</b>	
<b>PFEIFFER ROAD</b>	
LT. STA. 119+64, 30' LT	14 FT
LT. STA. 130+83.5, 30' LT	18
LT. STA. 138+64, 30' LT	15
LT. STA. 142+75.5, 30' LT	15
CL. STA. 143+17	10
LT. STA. 145+56, 30' LT	16
PROJECT TOTAL	88 FT

**DETECTABLE WARNINGS**

LOCATION	QUANTITY
<b>PFEIFFER ROAD</b>	
LT. STA. 119+43.0	15 S.F.
LT. STA. 119+81.5	10
LT. STA. 130+47.0	28
LT. STA. 131+20.0	28
LT. STA. 138+36.5	28
LT. STA. 139+91.0	28
LT. STA. 142+52.0	18
LT. STA. 143+04.0	36
LT. STA. 145+28.0	30
LT. STA. 145+89.0	26
LT. STA. 155+52.0	15
PROJECT TOTAL	262 S.F.

**THERMOPLASTIC PAVEMENT MARKINGS, LINE 6"**

LOCATION	QUANTITY
<b>PFEIFFER ROAD</b>	
LT. STA. 119+64, 26' & 32' LT	69 FT
LT. STA. 130+83.5, 14' & 24' LT	107
LT. STA. 138+64, 14' & 24' LT	79
LT. STA. 142+75.5, 14' & 24' LT	91
CL. STA. 143+03	31
CL. STA. 143+11	28
LT. STA. 145+56, 14' & 24' LT	112
PROJECT TOTAL	517 FT

**SIGN SCHEDULE**

LOCATION	SIGN	SIGN CODE	SIGN PANEL - TYPE 1 (SF)	REMOVE SIGN PANEL - TYPE 1 (SF)	RELOCATE SIGN PANEL - TYPE 1 (SF)	METAL POST - TYPE A (EACH)	METAL POST - TYPE B (EACH)
<b>PFEIFFER ROAD</b>							
LT. STA 119+05	NO PARKING	R7-4	1.5	1.5		1	
LT. STA 119+10 (3 SIGNS)	SCHOOL	S4-3			3		2
	SPEED LIMIT 20	R2-1			5		
	WHEN CHILDREN PRESENT	S4-2			4.5		
LT. STA 120+11	NO PARKING	R7-4	1.5	1.5		1	
LT. STA 120+62	SIGNAL AHEAD	W3-3			9	2	
LT. STA 122+32	NO PARKING	R7-4	1.5	1.5		1	
LT. STA 122+94	SCHOOL SPEED ZONE	NA			9		2
LT. STA 128+52	NO PARKING	R7-4	1.5	1.5		1	
LT. STA 128+82	NO PARKING	R7-4	1.5	1.5		1	
LT. STA 131+82	NO PARKING	R7-4	1.5	1.5		1	
LT. STA 134+56	NO PARKING	R7-4	1.5	1.5		1	
LT. STA 137+73	NO PARKING	R7-4	1.5	1.5		1	
LT. STA 139+24	SPEED LIMIT 35	R2-1	5	5			1
LT. STA 141+06	NO PARKING	R7-4	1.5	1.5		1	
LT. STA 142+57 (2 SIGNS)	STOP	R1-1	6.3	6.3			1
	4-WAY	R1-3	0.5	0.5			
LT. STA 143+15 (2 SIGNS)	STOP	R1-1	6.3	6.3			1
	4-WAY	R1-3	0.5	0.5			
LT. STA 143+62	NO PARKING	R7-4	1.5	1.5		1	
LT. STA 144+00	SCHOOL CROSSWALK	S2-1	6.3	6.3		1	
LT. STA 144+28	NO PARKING	R7-4	1.5	1.5		1	
LT. STA 143+52	STOP AHEAD	W3-1	6.3	6.3			1
LT. STA 146+07 (2 SIGNS)	NO U TURN	R3-4	4	4		1	
	NO PARKING	R7-4	1.5	1.5			
LT. STA 147+20	NO PARKING	R7-4	1.5	1.5		1	
LT. STA 147+99	SCHOOL SPEED LIMIT	S4-1100	8	8		2	
LT. STA 150+38	CHILDREN PRESENT	S1-1	6.3	6.3			1
LT. STA 150+93	NO PARKING	R7-4	1.5	1.5		1	
LT. STA 150+93 (2 SIGNS)	SPEED LIMIT 35	R2-1			3		1
	EMERGENCY CALL 911	NA	2	2			
LT. STA 154+13	WEIGHT LIMIT 10 TONS	R12-1			5		1
LT. STA 154+84	NO PARKING	R7-4	1.5	1.5		1	
	TOTAL		74	74	38.5	20	11

**SEEDING SCHEDULE**

FERTILIZER TO BE APPLIED @ 270 LB. PER ACRE @ 1-1-1 RATIO

LOCATION	FURNISHING AND PLACING TOPSOIL, 6" (S.Y.) *	SEEDING (ACRE)	NITROGEN FERTILIZER NUTRIENT (POUND)	PHOSPHORUS FERTILIZER NUTRIENT (POUND)	POTASSIUM FERTILIZER NUTRIENT (POUND)	MULCH METHOD 2 (ACRE)**
<b>PFEIFFER ROAD</b>						
LT. STA. 118+15.20 TO LT. STA. 155+61.00	3462	0.72	65	65	65	0.72
PROJECT TOTALS	3462 S.Y.	0.72 ACRES	65 LB.	65 LB.	65 LB.	0.72 ACRES

\* 3462 S.Y. EQUATES TO 577 C.Y. OF TOPSOIL AT 6" THICK

SURVEYED	MDP	CLIENT:	VILLAGE OF BARTONVILLE PEORIA COUNTY, ILLINOIS
DRAWN	DEH	TITLE:	PFEIFFER ROAD SIDEWALK IMPROVEMENTS SCHEDULE OF QUANTITIES
CHECKED	SKK	PROJECT NO.	09-122
SCALE	NONE	SHEET 4 OF 24	
DATE	12-02-09	DRAWING NO.	4