

F.A.I. SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57 15,21-25HB-2)BR	DOUGLAS	65	3
FED. ROAD DIST. NO. ILLINOIS		FED. AID PROJECT	
CONTRACT NO. 90952			

SUMMARY OF QUANTITIES			S.N. 021-0024 100% STATE
CODE NO.	ITEM	UNIT	CONSTRUCTION TYPE CODE X771-2A
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	282
25100630	EROSION CONTROL BLANKET	SQ YD	216
35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	SQ YD	2,019
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	673
40600300	AGGREGATE (PRIME COAT)	TON	9
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	179
40600990	TEMPORARY RAMP	SQ YD	148
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	391
42001300	PROTECTIVE COAT	SQ YD	374
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	374
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	132
44000100	PAVEMENT REMOVAL	SQ YD	135
44000182	HOT-MIX ASPHALT SURFACE REMOVAL, 8"	SQ YD	1,315
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1,707
44000700	APPROACH SLAB REMOVAL	SQ YD	258
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	452
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	3,360
44003100	MEDIAN REMOVAL	SQ FT	716
44003700	MEDIAN REMOVAL (SPECIAL)	SQ FT	7,204
44004250	PAVED SHOULDER REMOVAL	SQ YD	94
44200553	CLASS A PATCHES, TYPE II, 10 INCH	SQ YD	27
44213000	PATCHING REINFORCEMENT	SQ YD	27
44213200	SAW CUTS	FOOT	303
48101200	AGGREGATE SHOULDERS, TYPE B	TON	36
48203100	HOT-MIX ASPHALT SHOULDERS	TON	183
48300300	PORTLAND CEMENT CONCRETE SHOULDERS 8"	SQ YD	26
50102400	CONCRETE REMOVAL	CU YD	46.9
50104650	SLOPE WALL REMOVAL	SQ YD	132
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1
50157300	PROTECTIVE SHIELD	SQ YD	832

SUMMARY OF QUANTITIES			S.N. 021-0024 100% STATE
CODE NO.	ITEM	UNIT	CONSTRUCTION TYPE CODE X771-2A
50200100	STRUCTURE EXCAVATION	CU YD	311
50300100	FLOOR DRAINS	EACH	8
50300225	CONCRETE STRUCTURES	CU YD	11.8
50300255	CONCRETE SUPERSTRUCTURE	CU YD	487.9
50300260	BRIDGE DECK GROOVING	SQ YD	654
50300300	PROTECTIVE COAT	SQ YD	1,557
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	3,530
50500505	STUD SHEAR CONNECTORS	EACH	4,995
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	18
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	105,095
50800515	BAR SPLICERS	EACH	788
51100100	SLOPE WALL 4 INCH	SQ YD	200
51205200	TEMPORARY SHEET PILING	SQ FT	519
51500100	NAME PLATES	EACH	2
52100110	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	18
52100520	ANCHOR BOLTS, 1"	EACH	36
54213447	END SECTIONS 12"	EACH	4
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	112
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	3
60100070	SHOULDER REMOVAL AND REPLACEMENT	FOOT	88
60100945	PIPE DRAINS 12"	FOOT	352
60107600	PIPE UNDERDRAINS 4"	FOOT	1,416
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	111
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	190
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	3,360
60621900	CONCRETE MEDIAN, TYPE SM (SPECIAL)	SQ FT	5,219
60622354	CONCRETE MEDIAN, TYPE SM-6 (DOWELLED)	SQ FT	940
60624600	CORRUGATED MEDIAN	SQ FT	123
60624610	CORRUGATED MEDIAN (DOWELLED)	SQ FT	542
60625900	P.C.C. RAMPED MEDIAN TERMINAL	EACH	2

* SPECIALTY ITEM

SUMMARY OF QUANTITIES
FAI ROUTE 57
SECTION (15, 21-25HB-2)BR
DOUGLAS COUNTY
S.N. 021-0024

CUMMINS ENGINEERING CORPORATION

JOB #: 2114.1
FILE: 21140TY.DGN
DATE: 2/27/07