

SUMMARY OF QUANTITIES			S.N. 021-0024 100% STATE
CODE NO.	ITEM	UNIT	CONSTRUCTION TYPE CODE X771-2A
60900515	CONCRETE THRUST BLOCKS	EACH	4
61000115	TYPE E INLET BOX, STANDARD 610001	EACH	4
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	350
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2
63200310	GUARDRAIL REMOVAL	FOOT	576
63301000	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL	FOOT	200
63302700	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1
66101150	HOT-MIX ASPHALT SHOULDER CURB	FOOT	85
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12
67100100	MOBILIZATION	L SUM	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	12
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	304
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	94
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	5,357
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	102
70400100	TEMPORARY CONCRETE BARRIER	FOOT	800
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	750
70500200	TEMPORARY STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	25
70500665	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1
70500685	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 10	EACH	1
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	94
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	5,357
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	64
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	10
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	6

SUMMARY OF QUANTITIES			S.N. 021-0024 100% STATE
CODE NO.	ITEM	UNIT	CONSTRUCTION TYPE CODE X771-2A
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	6
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,409
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	12
* 81021550	CONDUIT, AUGERED 2" DIA., PVC	FOOT	200
* 81603035	UNIT DUCT, 600V, 2-1C NO. 6, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	1,616
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1,416
X0320887	POLYMER CONCRETE	CU FT	2.2
X0321475	PIPE ELBOW, 12"	EACH	8
X0323710	REMOVE CONDUIT ATTACHED TO STRUCTURE	FOOT	273
X0323830	DRAINAGE SCUPPERS, DS-11	EACH	2
X0324865	DIAMOND GRINDING (BRIDGE SECTION)	SQ YD	997
X6330103	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, TANGENT	EACH	1
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28
X7050167	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	2
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1
** Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
** Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0037300	PAVEMENT GROOVING	SQ YD	374
Z0038700	PERMANENT BENCH MARKS	EACH	1

* SPECIALTY ITEM
** SFTY - 3N

SUMMARY OF QUANTITIES
 FAI ROUTE 57
 SECTION (15, 21-25HB-2)BR
 DOUGLAS COUNTY
 S.N. 021-0024

CUMMINS ENGINEERING CORPORATION
 JOB #: 2114.1
 FILE: 2114QTY.DGN
 DATE: 2/27/07