

SUMMARY OF QUANTITIES

ITEM DESCRIPTION			BICYCLE	
CODE NO.	ITEM	UNIT	ROUTE 66 BIKEWAY 01-00001-01-BT	
			YO47	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	74	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	24	
20200100	EARTH EXCAVATION	CU YD	5880	
20400800	FURNISHED EXCAVATION	CU YD	5105	
20800150	TRENCH BACKFILL	CU YD	42.0	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	35422	
25000310	SEEDING, CLASS 4	ACRE	7.3	
25000775	SELECTIVE MOWING STAKES	EACH	72	
25100115	MULCH, METHOD 2	ACRE	7.3	
25100630	EROSION CONTROL BLANKET	SQ YD	217.0	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1464	
28000305	TEMPORARY DITCH CHECKS	FOOT	790	
28000400	PERIMETER EROSION BARRIER	FOOT	5110	
28000500	INLET AND PIPE PROTECTION	EACH	21	
31101300	SUB-BASE GRANULAR MATERIAL, TYPE B 5"	SQ YD	110	
31101600	SUB-BASE GRANULAR MATERIAL, TYPE B 8"	SQ YD	22215	
35400400	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 9"	SQ YD	56	
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	12260	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	1722	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1716	
42300200	PORTLAND CONCRETE CEMENT DRIVEWAY PAVEMENT 6"	SQ YD	93	
44000100	PAVEMENT REMOVAL	SQ YD	14	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	24	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	222	
44003800	MEDIAN SURFACE REMOVAL	SQ FT	471	
44004000	PAVED DITCH REMOVAL	FOOT	45	
44004250	PAVED SHOULDER REMOVAL	SQ YD	19	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	5607	
50102400	CONCRETE REMOVAL	CU YD	0.9	
50104400	CONCRETE HEADWALL REMOVAL	EACH	4	

ITEM DESCRIPTION			BICYCLE	
CODE NO.	ITEM	UNIT	ROUTE 66 BIKEWAY 01-00001-01-BT	
			YO47	
50105220	PIPE CULVERT REMOVAL	FOOT	157	
50300300	PROTECTIVE COAT	SQ YD	93	
50800105	REINFORCEMENT BARS	POUND	4620	
54003000	CONCRETE BOX CULVERTS	CU YD	24.4	
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	51	
54205053	PIPE CULVERTS, SPECIAL 18"	FOOT	146	
54205059	PIPE CULVERTS, SPECIAL 24"	FOOT	136	
54213453	END SECTIONS 18"	EACH	6	
54213459	END SECTIONS 24"	EACH	8	
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	4	
54215970	REINFORCED CONCRETE PIPE ELBOW 15"	EACH	2	
54248510	CONCRETE COLLAR	CU YD	0.60	
*56400100	FIRE HYDRANTS TO BE MOVED	EACH	1	
*56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	2	
60260300	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	
60266900	VALVE BOXES TO BE MOVED	EACH	3	
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	3	
60600097	CLASS SI CONCRETE (OUTLET), SPECIAL	CU YD	1.0	
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	58.0	
60614600	PAVED DITCH (SPECIAL)	FOOT	20	
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	221	
63200310	GUARDRAIL REMOVAL	FOOT	102	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	1	
67100100	MOBILIZATION	L SUM	1	
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	8	
72000100	SIGN PANEL - TYPE 1	SQ FT	264	
72000105	SIGN PANEL - TYPE 1 (SPECIAL)	SQ FT	3	
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	878	
73000100	WOOD SIGN SUPPORT	FOOT	14.5	

* SPECIALTY ITEMS

FILE NAME = I:\01\jobs\01520244\CADD\Road\Sheet\C-691.SUM00.dgn	USER NAME = Heyen00951	DESIGNED - heyen	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 1:8000 1/4 in.	DRAWN - pop00275	CHECKED - heyen	REVISED -			01-00001-01-BT	MCLEAN	50	3	
PLOT DATE = 11/19/2009	DATE - 11/03/2009					C-95-301-10	CONTRACT NO. 91429			
						SCALE: N.T.S.	SHEET NO. 1 OF 2 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT