

SEEDING SCHEDULE					
LOCATION	21101615	25000310	25000775	25100115	28000250
	TOPSOIL FURNISH AND PLACE, 4"	SEEDING, CLASS 4	SELECTIVE MOWING STAKES	MULCH, METHOD 2	TEMPORARY EROSION CONTROL SEEDING
	SQ YD	ACRE	EACH	ACRE	POUND
<b>FRONTAGE ROAD - CH 34</b>					
BEGIN STATION	END STATION	OFFSET			
557+10.74	566+91.77		814	0.17	0.17
557+25.00		LT/RT			2
562+00.00		LT/RT			2
565+00.00		LT/RT			2
SUBTOTAL			814	0.17	6
<b>CH 34 - US 66 CROSSING</b>					
BEGIN STATION	END STATION	OFFSET			
568+00.00	608+93.12		7484	1.55	1.55
568+00.00		LT/RT			2
569+00.00		LT/RT			2
570+00.00		LT/RT			2
573+00.00		LT/RT			2
575+00.00		LT/RT			2
576+00.00		RT			1
578+00.00		RT			1
579+00.00		LT/RT			2
580+00.00		RT			1
584+00.00		LT/RT			2
589+00.00		LT/RT			2
596+00.00		LT/RT			2
597+40.00		LT/RT			2
597+75.00		LT/RT			2
604+00.00		LT/RT			2
608+00.00		LT/RT			2
608+50.00		RT			1
SUBTOTAL			7484	1.55	30
<b>US 66 CROSSING - STRINGTOWN ROAD</b>					
BEGIN STATION	END STATION	OFFSET			
609+26.61	666+00.00		11876	2.45	2.45
609+25.00		LT			1
615+00.00		LT			1
620+00.00		LT			1
625+00.00		LT			1
630+00.00		LT			1
635+00.00		LT			1
640+00.00		LT			1
645+00.00		LT			1
650+00.00		LT			1
655+00.00		LT			1
660+00.00		LT			1
663+00.00		LT			1
665+00.00		LT			1
666+00.00		LT			1
SUBTOTAL			11876	2.45	14
<b>STRINGTOWN ROAD - POPPY STREET</b>					
BEGIN STATION	END STATION	OFFSET			
668+00.00	673+76.81		1274	0.26	0.26
668+00.00		LT			1
671+00.00		LT			1
SUBTOTAL			1274	0.26	2
<b>POPPY STREET - GERANIUM AVENUE</b>					
BEGIN STATION	END STATION	OFFSET			
674+47.54	679+82.77		1570	0.32	0.32
677+00.00		LT			1
SUBTOTAL			1570	0.32	1
<b>GERANIUM AVENUE - BLUE BONNET DRIVE</b>					
BEGIN STATION	END STATION	OFFSET			
681+00.00	682+92.26		513	0.11	0.11
682+00.00		LT			1
SUBTOTAL			513	0.11	1
<b>BLUE BONNET DRIVE - FULLER COURT</b>					
BEGIN STATION	END STATION	OFFSET			
683+89.75	697+81.63		4341	0.90	0.90
685+00.00		LT			1
690+00.00		LT			1
695+00.00		LT			1
SUBTOTAL			4341	0.90	3
<b>FULLER COURT - ASHLEY DRIVE</b>					
BEGIN STATION	END STATION	OFFSET			
698+60.88	709+59.98		1924	0.40	0.40
700+00.00		LT			1
705+00.00		LT			1
709+00.00		LT			1
SUBTOTAL			1924	0.40	3
<b>ASHLEY DRIVE - ACCESS WAY</b>					
BEGIN STATION	END STATION	OFFSET			
710+29.22	716+39.26		1001	0.21	0.21
710+30.00		LT			1
714+00.00		LT			1
716+00.00		LT			1
SUBTOTAL			1001	0.21	3

SEEDING SCHEDULE					
LOCATION	21101615	25000310	25000775	25100115	28000250
	TOPSOIL FURNISH AND PLACE, 4"	SEEDING, CLASS 4	SELECTIVE MOWING STAKES	MULCH, METHOD 2	TEMPORARY EROSION CONTROL SEEDING
	SQ YD	ACRE	EACH	ACRE	POUND
<b>ACCESS WAY - NESTLE PLANT C.E. SOUTH</b>					
BEGIN STATION	END STATION	OFFSET			
717+08.54	727+45.91		1559	0.32	0.32
717+00.00		LT			1
720+00.00		LT			1
725+00.00		LT			1
SUBTOTAL			1559	0.32	3
<b>NESTLE PLANT C.E. SOUTH - NESTLE PLANT C.E. NORTH</b>					
BEGIN STATION	END STATION	OFFSET			
727+97.49	731+80.39		474	0.10	0.10
730+00.00		LT			1
SUBTOTAL			474	0.10	1
<b>NESTLE PLANT C.E. NORTH - IBEW LOCAL 197 C.E.</b>					
BEGIN STATION	END STATION	OFFSET			
733+14.25	746+38.49		1957	0.40	0.40
735+00.00		LT			1
740+00.00		LT			1
745+00.00		LT			1
SUBTOTAL			1957	0.40	3
<b>IBEW LOCAL 197 C.E. - FOX CREEK ROAD</b>					
BEGIN STATION	END STATION	OFFSET			
747+19.43	751+85.16		635	0.13	0.13
749+00.00		LT			1
751+75.00		LT			1
SUBTOTAL			635	0.13	2
TOTAL			35422	7.32	72

UTILITY ADJUSTMENT SCHEDULE											
LOCATION	EXISTING ELEVATION	PROPOSED ELEVATION	ELEVATION DIFFERENCE	56400100	56400300	BY OTHERS	BY OTHERS	60266900	60300305	LOCATION NOTE	NOTES
				FIRE HYDRANTS TO BE MOVED	FIRE HYDRANTS TO BE ADJUSTED	GUY WIRE RELOCATION	UTILITY STRUCTURES TO BE ADJUSTED	VALVE BOXES TO BE MOVED	FRAMES AND LIDS TO BE ADJUSTED		
PLAN CALLOUT	STATION	OFFSET		EACH	EACH	L SUM	EACH	EACH	EACH		
<b>US 66 BIKEWAY - STRINGTOWN ROAD TO FOX CREEK ROAD</b>											
UT2	707+85.74	25.01'	LT	770.14	771.87	1.73		1			ROW
UT3	710+72.05	32.59'	LT	769.80	771.08	1.28		1			ROW
UT4	713+83.05	6.05'	LT	777.21	777.72	0.51			1		ROW WATER VALVE
UT5	713+83.54	10.05'	LT	777.06	777.64	0.58			1		ROW WATER VALVE
UT6	713+83.59	21.74'	LT	776.47	775.73	-0.74		1			ROW
UT7	713+86.86	6.12'	LT	777.19	777.72	0.53			1		ROW WATER VALVE
UT8	713+88.41	6.16'	LT	777.18	777.72	0.54	1				ROW
UT9	719+53.63	14.02'	LT	771.48	774.84	3.36		1			ROW
UT10	719+54.21	13.86'	LT	771.48	774.90	3.42		1			ROW
UT11	722+15.03	10.36'	LT	773.30	774.63	1.33		1			ROW
UT12	722+15.58	11.10'	LT	773.23	774.60	1.37		1			ROW
UT13	722+29.63	19.72'	LT	772.82	772.16	-0.66			1		PROP. EASEMENT GAS VALVE
UT14	722+30.64	19.84'	LT	772.85	772.13	-0.72			1		PROP. EASEMENT GAS VALVE
UT15	722+31.72	22.16'	LT	772.80	772.13	-0.67			1		PROP. EASEMENT GAS VAULT
UT16	724+59.83	9.73'	LT	775.29	776.60	1.31		1			PROP. EASEMENT
UT17	724+60.17	11.01'	LT	775.32	776.56	1.24		1			PROP. EASEMENT
UT18	727+01.26	8.80'	LT	777.77	779.23	1.46			1		ROW PHONE SPLICE BOX TO BE MOVED
UT19	727+08.38	13.16'	LT	777.61	778.85	1.24		1			ROW
UT20	727+08.55	9.29'	LT	777.29	779.31	2.02		1			ROW
UT21	727+08.73	13.18'	LT	777.59	778.85	1.26		1			PROP. EASEMENT
UT22	727+08.84	9.72'	LT	777.30	779.30	2.00		1			PROP. EASEMENT
UT23	727+08.93	13.54'	LT	777.60	778.73	1.13		1			PROP. EASEMENT
SUBTOTAL								1	2	3	3
TOTAL								1	2	3	3