

SCHEDULE OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL
20800150	TRENCH BACKFILL	CU YD	238
• 40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,454
40600300	AGGREGATE (PRIME COAT)	TON	30
• 40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	467
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	451
40600990	TEMPORARY RAMP	SQ YD	304
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,815
42001300	PROTECTIVE COAT	SQ YD	66
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	1,173
42400800	DETECTABLE WARNINGS	SQ FT	27
• 44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	336
• 44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	358
• 44000600	SIDEWALK REMOVAL	SQ FT	1,189
• 44201337	CLASS C PATCHES, TYPE I, 9 INCH	SQ YD	100
• 44201341	CLASS C PATCHES, TYPE II, 9 INCH	SQ YD	209
• 44201345	CLASS C PATCHES, TYPE III, 9 INCH	SQ YD	71
• 44201347	CLASS C PATCHES, TYPE IV, 9 INCH	SQ YD	512
55100300	STORM SEWER REMOVAL - 8"	FOOT	94
55100400	STORM SEWER REMOVAL - 10"	FOOT	98
△ 56106200	ADJUSTING WATER MAIN, 4"	FOOT	100
△ 56106300	ADJUSTING WATER MAIN, 6"	FOOT	100
△ 56300100	ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS	FOOT	40
△ 56300300	ADJUSTING WATER SERVICE LINES	FOOT	40
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3
60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	3
60240310	INLETS, TYPE B, TYPE 11 FRAME AND GRATE	EACH	1
• 60242820	INLETS, SPECIAL, TYPE E	EACH	2
60255500	MANHOLES TO BE ADJUSTED	EACH	23
• 60266600	VALVE BOXES TO BE ADJUSTED	EACH	14
• 60500050	REMOVING CATCH BASINS	EACH	1
• 60500060	REMOVING INLETS	EACH	6
60500105	FILLING MANHOLES	EACH	2
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6,12	FOOT	358

SCHEDULE OF QUANTITIES (CONTINUED)

CODE NO.	ITEM	UNIT	TOTAL
• 61139800	STORM SEWERS, SPECIAL 4"	FOOT	100
• 61139900	STORM SEWERS, SPECIAL 6"	FOOT	100
67100100	MOBILIZATION	L SUM	1
• 70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	880
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1,210
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,418
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	317
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	307
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,337
△ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1,210
△ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,418
△ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	317
△ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	307
• X0322034	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	144
• X0322035	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	172
• X0322127	STORM SEWER (WATER MAIN REQUIREMENTS) 30 INCH	FOOT	302
• X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	7,440

• SEE SPECIAL PROVISIONS
 NOTE: ALL ITEMS ARE UNDER CONSTRUCTION TYPE CODE I000
 △ SPECIALTY ITEMS

FILE NAME =
 V:\2788\27880001.dgn

USER NAME = jwhite

DESIGNED - JRB

REVISED -

DRAWN - RLR

REVISED -

PLOT SCALE = 1/8" = 1' IN.

CHECKED - JRB

REVISED -

PLOT DATE = 11/23/2009

DATE - 2009

REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

LAFAYETTE AVENUE (FAU ROUTE 8169)
 SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. 1 OF 1 SHEETS STA. N/A TO STA. N/A

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8169	09-00123-00-RS	MORGAN	13	3
CONTRACT NO. 93514				
ILLINOIS FED. AID PROJECT				