



GENERAL NOTES

THE CONTRACT UNIT PRICE FOR INLET, SPECIAL, TYPE E SHALL INCLUDE THE COST OF THE LID AS SHOWN, THE REINFORCED CONCRETE COVER, A SAND CUSHION WHEN REQUIRED, EXCAVATION AND FURNISHING AND COMPACTING THE SPECIFIED BACKFILL MATERIAL. ADDITIONALLY IT WILL BE NECESSARY TO MEET ALL OTHER REQUIREMENTS OF ART. 602.16 OF THE STANDARDS SPECIFICATIONS.

FRONT EDGE OF TOP SLAB SHALL CONFORM WITH THE RADIUS OF ADJACENT CURB WHERE INLET IS LOCATED WITHIN CURB RETURNS AT INTERSECTIONS.

COST OF REINFORCING BARS INCLUDED IN THE COST OF INLET.

*5 REBARS SHALL BE PLACED HORIZONTALLY & VERTICALLY AT 12" CENTERS IN WALLS ALL AROUND, WITH 18" x 18" L BARS AT CORNERS.

FILE NAME = V:\2786\2786D002.dgn	USER NAME = jwhite	DESIGNED - JRB	REVISED -
		DRAWN - JMO	REVISED -
		CHECKED - JRB	REVISED -
		DATE - 2009	REVISED -
PLOT SCALE = 1/8" = 1' IN.			
PLOT DATE = 11/23/2009			

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

LAFAYETTE AVENUE (FAU 8169) SPECIAL DETAILS		
SCALE: N/A	SHEET NO. 1 OF 1 SHEETS	STA. N/A TO STA. N/A

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8169	09-00123-00-RS	MORGAN	13	13
CONTRACT NO. 093514				
ILLINOIS FED. AID PROJECT				