

# SUMMARY OF QUANTITIES

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7982	*	SANGAMON	68	4
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* 09-00447-03-PV		CITY OF SPRINGFIELD		

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	ROADWAY	LANDSCAPING	TRAFFIC SIGNALS
				CAPITOL AVENUE 09-00447-03-PV STA. 42+11.00 TO STA. 49+62.70	CAPITOL AVENUE 09-00447-03-PV	CAPITOL AVENUE 09-00447-03-PV
				J000-2A	Y003 (S)	Y031-1F (S)
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	175	175		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	145	145		
20800150	TRENCH BACKFILL	CU YD	104	104		
28000510	INLET FILTERS	EACH	11	11		
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	3806	3806		
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	556	556		
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	237	237		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	64	64		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	289	289		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	72	72		
42000201	PORTLAND CEMENT CONCRETE PAVEMENT 7" (JOINTED)	SQ YD	2609	2609		
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ YD	744	744		
42001300	PROTECTIVE COAT	SQ YD	6285	6285		
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	264	264		
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	20317	20317		
* 42400610	TEMPORARY SIDEWALK	SQ FT	3910	3910		
42400800	DETECTABLE WARNINGS	SQ FT	112	112		
* 44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	178	178		
50200100	STRUCTURE EXCAVATION	CU YD	48	48		
50300225	CONCRETE STRUCTURES	CU YD	25.6	25.6		
50800105	REINFORCEMENT BARS	POUND	3740	3740		
550B0030	STORM SEWERS, CLASS B, TYPE 1 8"	FOOT	124	124		
55100200	STORM SEWER REMOVAL 6"	FOOT	26	26		
55100500	STORM SEWER REMOVAL 12"	FOOT	43	43		
* 60107600	PIPE UNDERDRAINS 4"	FOOT	1906	1906		
* 60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	104	104		

\* PAY ITEM REQUIRES A SPECIAL PROVISION

(S) DENOTES SPECIALTY ITEMS

LAYOUT	TCJ	03/27/01
DRAWN	TCJ	03/27/01
REVIEWED	MH	/ /

PLOT DATE = 11/24/2009  
 FILE NAME = I:\02\jobs\0252841\A\CADD\Road\Microstation\Sheet\Section\_2\_E\h-7th\c-004\_S00.dgn  
 PLOT SCALE = 50.0000 / 1 in.  
 USER NAME = Hagan00951

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES  
 FAU RTE 7982 CAPITOL AVE  
 SEC NO. 09-00447-03-PV  
 SANGAMON COUNTY, ILLINOIS  
 SCALE: VERT.      DRAWN BY TCJ  
 HORIZ.              CHECKED BY MH  
 DATE 10/9/09