

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7982	*	SANGAMON	68	10
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* 09-00447-03-PV		CITY OF SPRINGFIELD		

PAVEMENT SCHEDULE

LOCATION			SUB-BASE GRANULAR MATERIAL, TYPE A 4"	BITUMINOUS MATERIALS (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	PORTLAND CEMENT CONCRETE PAVEMENT 7" (JOINTED)	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)
BEGIN STATION	END STATION	OFFSET	SQ YD	GALLON	TON	SQ YD	SQ YD
CAPITOL AVENUE 5TH STREET - 6TH STREET							
42+11.00	42+40.00	LT-RT		36	40		
42+31.51	42+88.56	RT	111				
42+88.56	43+30.56	RT	119				
43+30.56	44+25.23	RT	185				
44+25.23	45+11.23	RT	244				
45+11.23	45+68.23	RT	111				
42+31.51	42+88.56	LT	111				
42+88.56	43+74.56	LT	244				
43+74.56	45+68.23	LT	378				
42+39.56	45+60.23	LT/RT				1257	
SUBTOTAL			1504	36	40	1257	
CAPITOL AVENUE/6TH STREET INTERSECTION							
45+68.23	46+68.23	LT/RT	894				
45+72.83	46+29.03	LT		16	17		
45+77.19	46+24.72	RT		13	15		
45+60.23	46+42.26	LT/RT					744
SUBTOTAL			894	29	32		744
CAPITOL AVENUE 6TH STREET - 7TH STREET							
46+68.23	46+91.26	RT	45				
46+91.26	47+77.26	RT	244				
47+77.26	48+27.71	RT	99				
48+27.71	49+13.71	RT	244				
49+13.71	49+55.96	RT	83				
46+68.23	46+91.25	LT	45				
46+91.25	47+55.25	LT	181				
47+55.25	48+27.70	LT	142				
48+27.70	49+13.70	LT	244				
49+13.70	49+55.96	LT	83				
46+42.26	49+62.71	LT/RT				1352	
SUBTOTAL			1408			1352	
TOTAL			3806	64	72	2609	744

DRIVEWAY AND SIDEWALK SCHEDULE

LOCATION			PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	DETECTABLE WARNINGS
BEGIN STATION	END STATION	OFFSET	SQ YD	SQ FT	SQ FT
CAPITOL AVENUE 5TH STREET - 6TH STREET					
42+23.00	42+38.00	LT			56
42+23.00	42+38.00	RT			56
42+22.60	44+40.22	LT		3605.0	
42+22.60	43+52.56	RT		2290.0	
43+74.56	45+68.22	RT		3005.0	
44+52.22	45+68.22	LT		1844.0	
	43+64.15	RT		68	
	44+46.62	LT		43	
SUBTOTAL			111	10744.0	112
CAPITOL AVENUE/6TH STREET INTERSECTION					
45+68.22	45+81.18	LT		262.0	
45+68.22	45+81.14	RT		341.0	
46+21.34	46+49.22	LT		548.0	
46+22.19	46+49.22	RT		442.0	
SUBTOTAL				1593.0	
CAPITOL AVENUE 6TH STREET - 7TH STREET					
46+49.22	47+72.25	LT		1324.0	
46+49.22	47+89.59	RT		2142.0	
48+05.05	49+55.95	LT		2294.0	
48+10.49	49+55.95	RT		2220.0	
	47+88.42	LT		90	
	48+02.06	RT		63	
SUBTOTAL			153	7980.0	
TOTAL			264	20317.0	112

CURB AND GUTTER SCHEDULE

LOCATION			CONCRETE CURB	CONCRETE GUTTER	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	REMOVE AND RESINTALL BRICK PAVER
BEGIN STATION	END STATION	OFFSET	FOOT	FOOT	FOOT	FOOT
CAPITOL AVENUE 5TH STREET - 6TH STREET						
42+22.60	42+93.56	LT			87.1	
42+22.60	42+93.56	RT			87.1	
42+93.56	43+25.56	RT		32.0		
42+93.56	43+69.56	LT		76.0		
43+25.56	44+30.23	RT			104.7	
43+69.56	45+68.23	LT			198.7	
44+30.23	45+06.23	RT		76.0		
45+06.23	45+68.23	RT			62.0	
SUBTOTAL				184.0	539.5	
CAPITOL AVENUE/6TH STREET INTERSECTION						
45+68.23	45+76.32	LT			63.0	
45+68.23	45+80.32	RT			63.0	
45+72.52	45+72.23	LT	28.0			42.0
45+76.50	45+76.34	RT	27.0			41.0
46+21.54	46+68.23	RT			69.0	
46+25.50	46+25.39	RT	27.0			40.0
46+25.51	46+68.23	LT			77.0	
46+29.78	46+29.82	LT	28.0			42.0
SUBTOTAL			110.0		272.0	165.0
CAPITOL AVENUE 6TH STREET - 7TH STREET						
46+68.23	46+96.25	LT			28.0	
46+68.23	46+96.26	RT			28.0	
46+96.25	47+50.25	LT		54.0		
46+96.26	47+72.26	RT		76.0		
47+50.25	48+32.70	LT			82.4	
47+72.26	48+32.71	RT			60.4	
48+09.00	49+50.00	RT	\$155			
48+32.70	49+08.70	LT		76.0		
48+32.71	49+08.71	RT		76.0		
49+08.70	49+55.96	LT			47.3	
49+08.71	49+55.96	RT			47.3	
49+62.70	49+71.20	LT/RT				276.0
SUBTOTAL			155.0	282.0	293.5	276.0
TOTAL			265.0	466.0	1105.0	441.0

REMOVAL SCHEDULE

LOCATION			HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT
BEGIN STATION	END STATION	OFFSET	SQ YD	SQ YD
CAPITOL AVENUE 5TH - 6TH STREET				
42+11.00	42+41.50	LT/RT	178	
SUBTOTAL			178	
CAPITOL AVENUE/6TH STREET INTERSECTION				
45+72.83	46+29.03	LT		156
45+77.19	46+24.72	RT		133
SUBTOTAL				289
TOTAL			178	289

TREE REMOVAL SCHEDULE

LOCATION		TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)	NOTE
BEGIN STATION	OFFSET	UNIT	UNIT	
CAPITOL AVENUE 5TH STREET - 6TH STREET				
42+58.68	28.89	LT	17	
42+47.08	48.7	LT	8	EASEMENT
42+58.61	45.3	LT	8	EASEMENT
42+77.05	28.61	LT	11	
42+94.29	28.64	LT	15	
43+13.00	28.78	LT	11	
43+30.53	28.91	LT		16
43+48.46	28.59	LT		17
43+84.68	28.33	LT		21
44+02.66	28.65	LT		17
44+07.32	27.28	RT	9	
44+21.86	28.39	LT		19
44+28.17	27.6	RT	7	
SUBTOTAL		69	107	
CAPITOL AVENUE 6TH STREET - 7TH STREET				
46+84.22	29.9	LT	7	
47+14.87	29.9	LT	8	
47+44.79	29.8	LT	7	
47+62.27	30.1	LT	7	
48+08.26	31.18	LT		19
48+29.30	45.56	RT	12	EASEMENT
48+32.47	30.64	LT	16	
48+55.89	30.58	LT		19
48+57.92	45.34	RT	11	EASEMENT
48+86.11	45.27	RT	11	EASEMENT
49+03.93	30.58	LT	16	
49+44.29	44.64	RT	11	EASEMENT
SUBTOTAL		106	38	
TOTAL		175	145	

TEMPORARY ACCESS AND FENCING SCHEDULE

LOCATION				AGGREGATE FOR TEMPORARY ACCESS	TEMPORARY SIDEWALK	TEMPORARY CONSTRUCTION FENCE	NOTE
BEGIN STATION	OFFSET	END STATION	OFFSET	TON	SQ FT	FOOT	
CAPITOL AVENUE 5TH STREET - 6TH STREET							
43+47.29	25.00	RT	43+47.29	30			IL MUN LG
43+63.29	25.00	RT	43+63.29	30			IL MUN LG
43+79.29	25.00	RT	43+79.29	30			IL MUN LG
42+31.77	37.55	LT	43+71.89		700		METH CHRCH
42+31.48	37.37	RT	43+73.92		725		IL MUN LGE
44+00.00	37.97	RT	45+69.41		850		VARIOUS
45+07.78	37.55	LT	45+68.54		310		ICC
42+31.77	35.00	LT	43+71.89			145	METH CHRCH
42+31.48	35.00	RT	43+73.92			145	IL MUN LGE
44+00.00	35.00	RT	45+69.41			170	VARIOUS
45+07.78	35.00	LT	45+68.54			65	ICC
VARIOUS						380	
SUBTOTAL				91	2585	905	
CAPITOL AVENUE 6TH STREET - 7TH STREET							
47+73.58	40.00	LT	47+73.58	49			PRSB CHRCH
47+89.58	40.00	LT	47+89.58	49			PRSB CHRCH
48+05.58	40.00	LT	48+05.58	49			PRSB CHRCH
47+88.30	37.68	LT	48+72.75		425		PRSB CHRCH
47+82.00	35.00	RT	49+63.00		900		PARK GARAGE
47+88.30	35.00	LT	48+72.75			85	PRSB CHRCH
48+10.06	40.00	RT	49+62.79			155	PARK LOT
VARIOUS						240	
SUBTOTAL				146	1325	480	
TOTAL				237	3910	1385	

REVISIONS

NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FAU RTE 7982 CAPITOL AVE
 SEC NO. 09-00447-03-PV
 SANGAMON COUNTY, ILLINOIS

SCALE: VERT. _____
 HORIZ. _____
 DATE 10/9/09
 DRAWN BY TCJ
 CHECKED BY MH



LAYOUT: TCJ 03/27/01
 DRAWN: TCJ 03/27/01
 REVIEWED: MH / /
 PLOT DATE: 11/25/2009
 FILE NAME: I:\2009\09\0252041A\CADD\Road\Workstation\Sheet\Section_2_5th-7th-C-0205_SCH.dwg
 PLOT SCALE: 1/8" = 1'-0"
 USER NAME: Hagan00951