

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7982	*	SANGAMON	68	11
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* 09-00447-03-PV		CITY OF SPRINGFIELD		

PAVEMENT MARKING SCHEDULE									
LOCATION				TEMPORARY PAVEMENT MARKING - LINE 4"	WORK ZONE PAVEMENT MARKING REMOVAL	EPOXY PAVEMENT MARKING - LINE 5"	EPOXY PAVEMENT MARKING - LINE 6"	EPOXY PAVEMENT MARKING - LINE 24"	NOTE
BEGIN STATION	OFFSET	END STATION	OFFSET	FOOT	SQ FT	FOOT	FOOT	FOOT	
CAPITOL AVENUE 5TH - 6TH STREET									
42+11.00	LT	42+21.00					21		CROSSWALK
42+30.00	LT/RT	42+38.00	LT/RT				68		CROSSWALK
42+11.00	RT	42+21.00	RT				21		CROSSWALK
SUBTOTAL							110		
CAPITOL AVENUE/6TH STREET INTERSECTION									
45+95.26	38.00	LT	45+95.26	93.00	LT	10	3	14	SKIP DASH
46+07.28	38.00	LT	46+07.28	93.00	LT	10	3	14	SKIP DASH
45+95.22	42.00	RT	45+95.22	93.00	RT	9	3	13	SKIP DASH
46+07.22	42.00	RT	46+07.22	93.00	RT	9	3	13	SKIP DASH
45+83.22	42.00	RT	46+19.30	42.00	RT	216	72		STOP BAR
SUBTOTAL				254	85	53		36	
TOTAL				254	85	53	110	36	

EARTHWORK SCHEDULE				
LOCATION		REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	SUB-BASE GRANULAR MATERIAL, TYPE C	SPECIAL EXCAVATION
BEGIN STATION	END STATION	CU YD	TON	CU YD
CAPITOL AVENUE 5TH STREET - 6TH STREET				
42+31.51	45+68.23		278	1118
SUBTOTAL			278	1118
CAPITOL AVENUE/6TH STREET INTERSECTION				
45+68.23	46+50.00		31	542
SUBTOTAL			31	542
CAPITOL AVENUE 6TH STREET - 7TH STREET				
46+50.00	49+55.98		247	1181
SUBTOTAL			247	1181
TOTAL			556	2841

PAVER PAVEMENT SCHEDULE						
LOCATION			CONCRETE PAVEMENT	CONCRETE PAVEMENT SIDEWALK	DETECTABLE WARNINGS, SPECIAL	PAVE-EDGE PAVEMENT RETAINING SYSTEM
BEGIN STATION	END STATION	OFFSET	SQ YD	SQ YD	SQ FT	FOOT
CAPITOL AVENUE 5TH STREET - 6TH STREET						
41+56.00	45+58.00		1198.0	452.2	96	126.0
SUBTOTAL			1198.0	452.2	96	126.0
CAPITOL AVENUE 6TH STREET - 7TH STREET						
45+58.00	49+61.00		1197.5	557.2	96	106.0
SUBTOTAL			1197.5	557.2	96	106.0
TO BE DETERMINED BY THE ENGINEER					40	

STREETSCAPE SCHEDULE														
LOCATION			MARKER FOOTINGS	BENCH	METAL BENCH, 6" SECTION	TRASH RECEPTACLES	RECYCLING RECEPTACLES	PRECAST PLANTER EDGE TYPE 1	PRECAST PLANTER EDGE TYPE 2	CUSTOM FENCE STONE PIER FOOTINGS	CUSTOM PLANTER FOOTINGS	DECORATIVE STEEL RAILING	STREET LIGHT FOR INFORMATION ONLY	PEDESTRIAN LIGHT - FOR INFORMATION ONLY
BEGIN STATION	END STATION	OFFSET	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	FOOT	EACH	EACH
CAPITOL AVENUE 5TH STREET - 6TH STREET														
41+56.00	45+58.00		6	14	4	3	3	6	5		5	126	6	11
SUBTOTAL			6	14	4	3	3	6	5		5	126	6	11
CAPITOL AVENUE 6TH STREET - 7TH STREET														
45+58.00	49+61.00		6	8	8	4	4	5	7	5	10	144	6	12
SUBTOTAL			6	8	8	4	4	5	7	5	10	144	6	12
TOTAL			12	22	12	7	7	11	12	5	15	270	12	23

LANDSCAPING SCHEDULE													
LOCATION			TREE GLEDITSIA TRIACANTHOS INERMIS SKYLINE (SKYLINE THORNLESS COMMON HONEYLOCUST), 3" CALIPER, BALLED AND BURLAPPED	SHRUB, ROSA NEARLY WILD (NEARLY WILD SHRUB ROSE), 24" HEIGHT, CONTAINER	PERENNIAL PLANTS, SPOROBOLUS HETEROLEPIS, (PRAIRIE DROPSEED), 1-GALLON	LIRIOPE SPICATA (1 QUART)	SEDUM 'AUTUMN JOY' (1 GAL)	TREE - ACER X FREEMANI 'ARMSTRONG' (ARMSTRONG FREEMAN MAPLE), 3" CALIPER, BALLED AND BURLAPPED	ILLEX GLABRA 'SHAMROCK' (SHAMROCK INKBERRY HOLLY), 5 GAL. WELL DEVELOPED	CALAMAGROSTIS ACUTIFLORA 'OVERDAM' (FEATHER REED GRASS), 1 GAL. WELL DEVELOPED	JUNIPERUS SABINA 'BUFFALO' (BUFFALO JUNIPER), 3 GAL. WELL DEVELOPED	RUDBECKIA FULGIDA 'GOLDSTURM' (POT OF GOLD), 1 GAL. WELL DEVELOPED	
BEGIN STATION	END STATION	OFFSET	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	
CAPITOL AVENUE 5TH STREET - 6TH STREET													
			2		56	124	219	209	1	32	170	12	269
SUBTOTAL			2		56	124	219	209	1	32	170	12	269
CAPITOL AVENUE 6TH STREET - 7TH STREET													
			2		32	68	310	124	1	36	80	36	124
SUBTOTAL			2		32	68	310	124	1	36	80	36	124
TOTAL			4		88	192	529	333	2	68	250	48	393



LAYOUT: TCJ 03/27/07
 DRAWN: TCJ 03/27/07
 REVIEWED: MH / /
 PLOT DATE = 11/27/2009
 FILE NAME = I:\V2\09-00447-03-PV\Sheet\Sheet1.dwg
 PLOT SCALE = 50/200 / in.
 USER NAME = Hagan08951

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FAU RTE 7982 CAPITOL AVE
 SEC NO. 09-00447-03-PV
 SANGAMON COUNTY, ILLINOIS
 SCALE: VERT. / HORIZ.
 DATE 10/9/09
 DRAWN BY TCJ
 CHECKED BY MH