

COMBINATION CONCRETE CURB AND GUTTER TYPE B-6.24		
STA. 11+00.1 LT TO STA. 53+53.1 LT	4252.9 FOOT	
STA. 53+53.1 LT TO STA. 54+15.3 LT	61.4 FOOT	
STA. 11+00.1 LT TO STA. 54+08.0 RT	4307.8 FOOT	
STA. 53+53.1 LT TO STA. 54+46.2 RT	39.7 FOOT	
TOTAL: 8662.0 FOOT		

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED 25% FOR SHRINKAGE	EMBANKMENT	ADDITIONAL EXCAVATED MATERIAL FROM STORM SEWER CONSTRUCTION ADJUSTED FOR SHRINKAGE	FURNISHED EXCAVATION	CU YDS				
STA. 8+59.5 TO STA. 11+00.1	30	23	264	-	-					
STA. 11+11.1 TO STA. 54+15.3	1933	1449	7030	1838	-3984					
TOTALS	1963	1472	7294	1838	-3984					

SEEDING SCHEDULE

LOCATION	SEEDING CL 2 [ACRE] 25000200	TEMP EROS CONTR SEED [POUND] 28000250	NUTRIENTS				MULCH METHOD 2 [ACRE] 25100115
			NITROGEN FERT NUTR [POUND] 25000400	PHOSPHOROUS FERT NUTR [POUND] 25000500	POTASSIUM FERT NUTR [POUND] 25000600		
STA. 8+59.46 - STA. 11+00.14 LT	0.070	7.0	6.3	6.3	6.3		
STA. 8+59.46 - STA. 11+00.14 RT	0.036	3.6	3.2	3.2	3.2		
STA. 11+00.14 - STA. 16+29.85 LT	0.188	18.8	16.9	16.9	16.9		
STA. 11+00.14 - STA. 13+14.07 RT	0.082	8.2	7.4	7.4	7.4		
STA. 13+20.39 - STA. 23+37.51 RT	0.294	29.4	26.5	26.5	26.5		
STA. 16+43.40 - STA. 34+31.00 LT	0.508	50.8	45.7	45.7	45.7		
STA. 23+50.60 - STA. 25+80.73 RT	0.057	5.7	5.1	5.1	5.1		
STA. 25+94.64 - STA. 34+31.00 RT	0.228	22.8	20.5	20.5	20.5		
STA. 34+31.00 - STA. 50+82.44 LT	0.442	44.2	39.8	39.8	39.8		
STA. 34+31.00 - STA. 34+41.21 RT	0.002	0.2	0.2	0.2	0.2		
STA. 34+58.89 - STA. 39+82.89 RT	0.125	12.5	11.3	11.3	11.3		
STA. 39+92.80 - STA. 40+98.50 RT	0.026	2.6	2.3	2.3	2.3		
STA. 41+13.00 - STA. 49+99.71 RT	0.231	23.1	20.8	20.8	20.8		
STA. 50+16.84 - STA. 54+47.32 RT	0.112	11.2	10.1	10.1	10.1		
STA. 50+84.29 - STA. 54+19.83 LT	0.085	8.5	7.7	7.7	7.7		
TOTALS	2.5	250	225	225	225	2.5	

ENTRANCE SCHEDULE

LOCATION	ENTRANCE TYPE	EXISTING MATERIAL	DRIVE PAVEMENT REM [SQ YD] 44000200	PIPE CULVERT REMOY [FOOT] 50105220	AGG BASE CSE B 4 [SQ YD] 35101600	AGG BASE CSE B 6 [SQ YD] 35101800	PCC DRIVEWAY PVT 6 [SQ YD] 42300200	BIT MATLS PR CT [GALLON] 40800010	AGG PR CT [TON] 40800030	INCIDENTAL HMA SURF [TON] 40800050	AGG BASE CSE A 4 [SQ YD] 35100300	APRON
STA. 9+68 RT	CE	ROCK				78.1						N/A
STA. 13+21 RT	PE	ROCK		21.7	52.2							17.4'
STA. 16+37 LT	PE	ROCK		29.8	15.6							20.0'
STA. 22+93 RT	FE	DIRT		21.7								16.6'
STA. 23+43 RT	PE	ROCK		21.0	13.0							14.1'
STA. 25+87 RT	PE	ROCK		32.0	15.1							18.4'
STA. 33+03 RT	FE	DIRT										19.5'
STA. 34+51 RT	PE	BIT	40.9	20.0				4.2	0.04	1.3	11.9	18.1'
STA. 36+72 LT	FE	DIRT		48.0								24.0'
STA. 39+88 RT	PE	ROCK		26.0	4.3							12.0'
STA. 41+06 RT	PE	CONC	7.9	24.0								14.8'
STA. 50+09 RT	PE	ROCK		27.1	17.1							19.8'
STA. 50+76 LT	PE	ROCK		30.4	8.7							24.0'
TOTALS			48.8	301.7	126.0	78.1	207.7	4.2	0.04	1.3	11.9	

PAVEMENT SCHEDULE

LOCATION	PROCESS MOD. SOIL 12 [SQ YD] 30200650	LIME [TON] 30201500	PORTLAND CEMENT [TON] 30201700	SUB GRAN MAT A 4 [SQ YD] 31100300	SUB GRAN MAT A 8 [SQ YD] 31100700	BIT MATLS PR CT [GALLON] 40600100	AGG PR CT [TON] 40600300	HMA BC 1L-19.0 N70 [TON] 40603085	HMA SC "C" N70 [TON] 40603315	AGGREGATE SHLDS A 6 [SQ YD] 48100500
STA. 8+59.5 - STA. 11+11.04					642.3	275.5	2.3		132.21	172.6
STA. 11+00.14 - STA. 34+00	7962.63	218.97		7962.63				2511.45	1116.20	
STA. 34+00 - STA. 34+31.00	107.33		4.44	107.33				33.85	15.04	
STA. 34+31.00 - STA. 38+00	1277.56		52.89	1277.56				402.95	179.09	
STA. 38+00 - STA. 53+75.40	5454.39	150.00		5454.39				1720.34	764.60	
STA. 53+75.40 - STA. 54+46.18	164.90	4.54		164.90				50.01	22.23	
TOTALS	14967	373.5	57.3	14967	642	276	2.3	4718.6	2229.4	172.6

PAVEMENT REMOVAL SCHEDULE

LOCATION	PAVEMENT REM [SQ YD] 44000100
STA. 8+59.5 - STA. 11+11.04	788.50
STA. 11+00.14 - STA. 34+31	5591.57
STA. 34+31 - STA. 53+60.13	4573.73
STA. 53+60.13 - STA. 54+15.29	159.79
TOTALS	11114

PLOT DATE: 02.08.2010

INITIALS	DATE
DESIGNED R GEORGEN	OCT 2008
CHECKED T HOLDENER	DEC 2008
DRAWN R GEORGEN	OCT 2008
CHECKED T HOLDENER	DEC 2008

Revised 2-17-10