PATCHING SCHEDULE

LOCATION	WIDTH (FT)	PATCHES CLASS B, TYPE II 10" (SQ YD)	PATCHES CLASS B, TYPE III 10" (SQ YD)	PATCHES CLASS B, TYPE IV 10" (SQ YD)	PAVEMENT FABRIC (SQ YD)	DOWEL BARS 1 1/2" (EACH)	TIE BARS 3/4" (EACH)	SAW CUTS (FOOT)
BROADWAY AVENUE								
STA. 10+60.35 - 01.94' RT TO STA. 10+83.35 - 01.92' RT	12.1			30.94	30.94	20	22	105
STA. 10+60.35 - 14.04' RT TO STA. 10+83.35 - 14.04' RT	13.28			33.94	33.94	22	11	96
STA. 10+91.55 - 118.66' RT TO STA. 11+06.93 - 118.66' RT	12		20.49		20.49	56		82
STA. 11+06.93 - 118.66' RT TO STA. 11+22.77 - 118.66' RT	12		21.05		21.05	56		83
STA. 10+91.55 - 139.66' RT TO STA. 11+06.93 - 139.66' RT	15			25.69	25.69	56		91
STA. 11+06.93 - 139.66' RT TO STA. 11+22.63 - 139.66' RT	15			26.12	26.12	56		92
STA. 11+30.64 - 14.00' RT TO STA. 11+42.17 - 14.00' RT	13.35		17.09		17.09	22		75
STA. 13+80.48 - 2.00' LT TO STA. 13+96.41 - 2.00' LT	12.22		21.46		21.46	22		72
STA. 13+80.48 - 14.22' LT TO STA. 13+96.41 - 14.22' LT	13.19		23.35		23.35	24		87
STA. 13+76.46 - 2.00' RT TO STA. 13+96.47 - 2.00' RT	12.01			26.66	26.66	20		84
STA. 13+76.46 - 14.01' RT TO STA. 13+96.47 - 14.04' RT	13.3			29.65	29.65	24		100
STA. 21+94.75 - 14.66' RT TO STA. 21+98.55 - 14.66' RT	12.94	5.45				22		50
TOTAL		5	103	173	276	400	33	1017

PAVING SCHEDULE

LOCATION	BIT MATL PR CT (GALLON)	AGGREGATE (PRIME COAT) (TON)	HOT-MIX ASPHALT SURFACE COURSE, MIX "D" N90, 2 1/4" (TON)
BROADWAY AVENUE			
STA. 8+55.71 TO STA. 26+94.62	863.7	24.6	1554.6
KLEIN STREET			
STA. 50+66.78 TO STA. 52+03.38	39.6	1.1	71.3
TOTAL	903	26	1626

CURB AND GUTTER SCHEDULE

LOCATION	C & G TYPE B (FOOT)	C & G TYPE B-6.12 (FOOT)
BROADWAY AVENUE		
STA. 7+30.59 - 29.61' LT TO STA. 7+48.92 - 39.28' LT	21.6	
STA. 7+93.76 - 28.32' RT TO STA. 8+11.16 - 28.32' RT		17.4
STA. 8+60.81 - 28.32' RT TO STA. 8+71.14 - 28.31' RT		10.3
STA. 10+60.35 - 28.48' RT TO STA. 10+81.07 - 31.04' RT		21.06
STA. 11+24.97 - 42.46' RT TO STA. 11+34.62 - 29.17' RT		17.23
STA. 16+99.95 - 109.74' RT TO STA. 16+99.95 - 126.81' RT		17.07
STA. 19+12.33 - 28.19' LT TO STA. 16+26.37 - 28.23' LT		14.04
STA. 19+12.28 - 28.27' RT TO STA. 19+25.44 - 28.22' RT		13.16
TOTAL	22	110

SIDEWALK SCHEDULE

LOCATION	P.C.C. SIDEWALK 4" (SQFT)
BROADWAY AVENUE	
STA. 7+36.75 - 39.28' LT TO STA. 7+48.45 - 39.28' LT	100.40
STA. 7+77.41 - 41.87' RT TO STA. 8+06.98 - 45.07' RT	271.38
STA. 8+5.64 -38.75' LT TO STA. 8+14.40 - 38.75' LT	35.38
STA. 10+78.61 - 41.74' RT TO STA. 10+78.61 - 41.74' RT	65.39
STA. 11+25.55 - 42.42' RT TO STA. 11+35.53 - 42.42' RT	70.68
STA. 12+10.15 - 39.17' LT TO STA. 12+16.35 - 39.17' LT	24.68
STA. 12+49.03 - 40.65' LT TO STA. 12+55.24 - 40.65' LT	25.48
STA. 15+73.03 - 40.14' LT TO STA. 15+78.95 - 40.14' LT	23.95
STA. 16+14.40 - 39.88' LT TO STA. 16+55.24 - 39.88' LT	23.89
STA. 16+88.60 - 41.74' RT TO STA. 16+98.01 - 41.74' RT	63.82
STA. 17+35.51 - 41.93' RT TO STA. 17+45.46 - 41.93' RT	66.71
STA. 23+31.90 - 39.91' LT TO STA. 23+38.99 - 39.91' LT	29.45
STA. 23+85.95 - 34.29' LT TO STA. 24+00.00 - 33.56' LT	44.53
STA. 23+29.16 - 42.26' RT TO STA. 23+38.45 - 34.28' RT	64.77
STA. 23+79.51 - 34.02' RT TO STA. 23+88.50 - 33.46' RT	23.79
TOTAL	934

MEDIAN SCHEDULE

LOCATION	CORRUGATED MEDIAN (SQ FT)
BROADWAY AVENUE	
STA. 8+68.26 TO STA. 8+78.54	40
STA. 11+35.16 TO STA. 11+43.08	30
STA. 14+39.96 TO STA. 14+53.54	55
STA. 16+85.48 TO STA. 17+18.80	131
STA. 17+31.69 TO STA. 17+40.79	36
STA. 17+60.24 TO STA. 17+80.37	81
STA. 22+19.26 TO STA. 22+53.45	143
STA. 22+79.86 TO STA. 23+29.90	183
TOTAL	699

STRIP REFLECTIVE CRACK CONTROL SCHEDULE

LOCATION	STRIP REFLECTIVE CRACK CONTROL (FT)
BROADWAY AVENUE	
STA. 8+55.71 - 13.65' LT TO STA. 26+94.62 - 12.30' LT	1839
STA. 11+06.93 - 27.44' RT TO STA. 11+06.93 - 154.66' RT	127
STA. 12+32.82 - 27.55' LT TO STA. 12+32.82 - 133.07' LT	106
STA. 15+96.57 - 27.48' LT TO STA. 15+96.57 - 127.56' LT	100
STA. 17+17.00 - 27.16' RT TO STA. 17+17.00 - 127.31' RT	100
STA. 23+29.20 TO STA. 26+94.32	365
STA. 23+57.08 - 29.78' LT TO STA. 23+57.08 - 127.47' LT	100
STA. 8+55.71 - 14.06' RT TO STA. 26+94.62 - 12.42' RT	1839
TOTAL	4576

TEMPORARY RAMP SCHEDULE

LOCATION	TEMPORARY RAMP (SQ YD)
BROADWAY AVENUE	
STA. 8+55.71 - 13.92' LT	23
STA. 8+55.71 - 14.05' RT	22
STA. 11+06.93 - 154.66' RT	28
STA. 12+32.82 - 133.07' LT	24
STA. 15+96.57 - 127.59' LT	26
STA. 17+17.00 - 127.29' RT	28
STA. 23+57.07 - 127.38' LT	29
STA. 23+57.07 - 46.66' RT	30
STA. 26+94.62	43
KLEIN STREET	
STA. 50+66.78	41
STA. 52+03.38	33
TOTAL	326

FILE NAME = $FILEL$	USER NAME = jeremy	DESIGNED - BFK	REVISED -
		DRAWN - JDH	REVISED -
	PLOT SCALE = $SCALE$	CHECKED - BFK	REVISED -
	PLOT DATE = 12/29/2009	DATE - 4/22/09	REVISED -

CITY OF VENICE
BROADWAY AVENUE

QUANTITY SCHEDULES

SCALE: N.T.S. | SHEET NO. 1 OF 4 SHEETS | STA. | TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9097	09-00048-00-RS	MADISON	24	11
		CONTRACT NO. 97417		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		