



BLR 10-6 P.C.C. PAVEMENT SPECIAL, 8"	STATION TO STATION	SQ. YDS.
21+25 - 26+00	1,497.77	
SHEET TOTAL	1,497.77	
PAVEMENT REMOVAL	STATION TO STATION	SQ. YDS.
21+25 - 26+00	1,137.45	
SHEET TOTAL	1,137.45	
AGGREGATE SHOULDERS TYPE A, 6"	STATION TO STATION	TONS
LT 25+51 - 26+00	7.47	
RT 25+56 - 26+00	6.73	
SHEET TOTAL	14.20	

SUB-BASE --- GRANULAR MATERIAL, TYPE A, 4"	STATION TO STATION	SQ. YDS.
21+25 - 26+00	1,695.95	
SHEET TOTAL	1,695.95	
COMB. CONCRETE CURB & GUTTER TYPE B6.18	STATION TO STATION	FT.
21+25 - 26+00	823.20	
SHEET TOTAL	823.20	

LOCATION	P.C. CONCRETE SIDEWALK 4"	LOCATION	DRIVEWAY PAVEMENT TO BE REMOVED	P.C. CONCRETE DRIVEWAY PAVEMENT, 6"
①	462.89	Ⓐ	-	15.34
②	216.20	Ⓑ	63.98	45.51
③	50.74	Ⓒ	115.06	87.29
④	541.88	SHT. TOTAL	179.04	148.14
⑤	1,370.51			
⑥	67.37			
TOTAL	2,709.59			

TREE REMOVAL OVER 15 INCH	STATION	IN. DIA.
23+39.54, 18.6' LT	25	
SHEET TOTAL	25	

PIPE CULVERT REMOVAL	STATION TO STATION	FT.
(LT.) 21+88 - 22+29	41.0	
(LT.) 22+57 - 22+87	30.0	
(LT.) 23+78 - 24+55	77.0	
SHEET TOTAL	148.0	

