

CODE NO.	ITEM	UNIT	TOTAL QUANTITY URBAN	CONSTRUCTION CODE	
				80% FED 20% STATE ROADWAY	100% STATE ROADWAY
				0005	0005
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	395	395	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,672	2,672	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	857	857	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,216	1,216	
	78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,216	1,216	
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	7	7	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	3,366	3,366	
* 89500400	RELOCATE EXISTING PEDESTRIAN PUSH-BUTTON	EACH	11	11	
* 89502376	REBUILD EXISTING HANDHOLE	EACH	7	7	
X0320050	CONSTRUCTION LAYOUT (SPECIAL)	L SUM	1	1	
X2010100	TREE LIMB REMOVAL (4 TO 10 INCHES DIAMETER)	EACH	27	27	
X2010350	TREE REMOVAL, ACRES (SPECIAL)	ACRE	0.25	0.25	⚠
X2100002	PRUNING FOR SAFETY AND EQUIPMENT CLEARANCE	UNIT	4.6	4.6	
X4400501	COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT LESS THAN OR EQUAL TO 10 FEET	FOOT	2,804	2,804	

⚠ REVISED SHEET 2/2/2021

\* SPECIALTY ITEMS

REV-SEP

MODEL: D:\p\h\it  
FILE NAME: S:\2019\1811028\_PTB1B1\_003\WO 11-HicksRd Resurficing 02118\CADD\CADD\_Sheets\142930-ht-003-009-500.dgn



USER NAME = wmoahammed	DESIGNED - LEG / AWM	REVISED -
	DRAWN - LEG / AWM	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED - JA / MMO	REVISED -
PLOT DATE = 12/10/2020	DATE - 11/25/2020	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES 6 OF 7  
IL. RTE 53 / HICKS RD. : LAKE-COOK RD. - U.S. 14 (NORTHWEST HWY)  
SCALE: SHEET 6 OF 7 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2592	2020-046-R5	COOK	58	8
			CONTRACT NO. 62L18	
			ILLINOIS FED. AID PROJECT	