

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				80% FEDERAL	20% STATE
				BRIDGE	
				0047	
				036-0042	
28200200	FILTER FABRIC	SQ YD	71	71	
35400475	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 9 3/4"	SQ YD	100	100	
40600295	POLYMERIZED BITUMINOUS MATERIALS (TACK COAT)	POUND	334	334	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	210	210	
40604050	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "C", N50	TON	45	45	
50102400	CONCRETE REMOVAL	CJ YD	8.8	8.8	
50300255	CONCRETE SUPERSTRUCTURE	CJ YD	9.4	9.4	
50300260	BRIDGE DECK GROOVING	SQ YD	411	411	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1080	1080	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1425	1425	
50800515	BAR SPLICERS	EACH	16	16	
50800530	MECHANICAL SPLICERS	EACH	20	20	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	106	106	
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	10	10	
52100520	ANCHOR BOLTS, 1"	EACH	20	20	
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	775	775	



MODEL: D:\default
 FILE NAME: P:\pjancom.dwg
 ILLINOIS DOT
 PROJECT: 68F67
 SHEET: 3
 CONTRACT NO. 68F67

USER NAME = \$USERS	DESIGNED -	REVISED -
PLOT SCALE = 1:100	DRAWN -	REVISED -
PLOT DATE = 12/11/2020	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 1 OF 4 SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1412	[(106C)BR]BDR,BJR	HENDERSON	55	3
ILLINOIS FED. AID PROJECT			CONTRACT NO. 68F67	