

80% FED
20% STATE

80% FED
20% STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005	0004	0047
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	6	6		
20700220	POROUS GRANULAR EMBANKMENT	CU YD	37		37	
28200200	FILTER FABRIC	SO YD	40		40	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	21	21		
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	103094	103094		
40600990	TEMPORARY RAMP	SO YD	752	752		
40602970	HOT-MIX ASPHALT BINDER COURSE, IL-9.5FG, N70	TON	10679	10679		
40604052	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "C", N70	TON	12834	12834		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	540	540		
42000070	PAVEMENT CONNECTOR (HMA) FOR BRIDGE APPROACH SLAB	SO YD	71		71	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	150870	150870		
44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SO YD	1506	1506		
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SO YD	296	296		
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	296	296		
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SO YD	32	32		
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	32	32		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005	0004	0047
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	91	53	38	
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SO YD	91	53	38	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	5535	5535		
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SO YD	170	170		
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		1	
50300225	CONCRETE STRUCTURES	CU YD	21.2		21.2	
50300260	BRIDGE DECK GROOVING	SO YD	781		781	
50300300	PROTECTIVE COAT	SO YD	844		844	
50301350	CONCRETE SUPERSTRUCTURE (APPROACH SLAB)	CU YD	95.8		95.8	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	37850		37850	
50800515	BAR SPLICERS	EACH	290		290	
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2		2	
54010803	PRECAST CONCRETE BOX CULVERTS 8' X 3'	FOOT	42		42	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	53		53	
60260100	INLETS TO BE ADJUSTED	EACH	4		4	

REVISED 2-17-2021

REV. - MS

Model: Default
File: \\msc01\pub\hls\mcom\del\illinois\pvt\mjd\DOT\Documents\DOT\Office\District 7\Projects\74945\CAD\Drawings\CAD\Drawings\74945-ph-500.dgn

USER NAME = steffemk	DESIGNED -	REVISED -
PLOT SCALE = 100.0000 ' / in.	DRAWN -	REVISED -
PLOT DATE = 12/17/2020	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 1 OF 3 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
832	(113.114)RS-4	CLARK	46	3
CONTRACT NO. 74945				
ILLINOIS FED. AID PROJECT				

80% FED
20% STATE

80% FED
20% STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005	0004	0047
* 63301210	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	100		100	
* 63302700	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 6	EACH	4		4	
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	3	3		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2		2	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2		2	
70107005	PAVEMENT MARKING BLACKOUT TAPE, 5"	FOOT	2024		2024	
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	28	28		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005	0004	0047
70300100	SHORT TERM PAVEMENT MARKING	FOOT	16974	16974		
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	1886	1886		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	134253	134253		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	938		938	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	938		938	
70600250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	4		4	
70600350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	4		4	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	134253	134253		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	708	708		
X0326440	SURFACE REMOVAL, VARIABLE DEPTH (SPECIAL)	SQ YD	4525	4525		
X0900064	MEMBRANE WATERPROOFING SYSTEM FOR BURIED STRUCTURES	SQ YD	53		53	
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	268	268		
Z0001495	BRIDGE APPROACH SHOULDER REMOVAL	SQ YD	18		18	

* SPECIALTY ITEM

△ REVISED 2-17-2021

MODEL: Default
 FILE: M:\METS_Plan\planroom.dwg
 PROJECT: 12/17/2020
 USER: steffemk
 DESIGNED: -
 DRAWN: -
 CHECKED: -
 DATE: -
 PLOT SCALE = 100.0000' / in.
 PLOT DATE = 12/17/2020

USER NAME = steffemk	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 12/17/2020	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET 2 OF 3 SHEETS STA. TO STA.

F.A.P. RTE. 832	SECTION (113.114)RS-4	COUNTY CLARK	TOTAL SHEETS 46	SHEET NO. 4
CONTRACT NO. 74945			ILLINOIS FED. AID PROJECT	