

80% FED
20% STATE

80% FED
20% STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005	0004	0047
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	6	6		
20700220	POROUS GRANULAR EMBANKMENT	CU YD	37		37	1
28200200	FILTER FABRIC	SO YD	40		40	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	21	21		
28100105	STONE RIPRAP, CLASS A3	SO YD	40		40	
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	103094	103094		2
40600990	TEMPORARY RAMP	SO YD	752	752		
40602970	HOT-MIX ASPHALT BINDER COURSE, IL-9.5FG, N70	TON	10679	10679		
40604052	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "C", N70	TON	12834	12834		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	540	540		
42000070	PAVEMENT CONNECTOR (HMA) FOR BRIDGE APPROACH SLAB	SO YD	71			71
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	150870	150870		
44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SO YD	1506	1506		1
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SO YD	296	296		
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	296	296		
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SO YD	32	32		
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	32	32		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005	0004	0047
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	91	53	38	1
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SO YD	91	53	38	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	5535	5535		
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SO YD	170	170		
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1			1
50300225	CONCRETE STRUCTURES	CU YD	21.2			21.2
50300260	BRIDGE DECK GROOVING	SO YD	781			781
50300300	PROTECTIVE COAT	SO YD	844			844
50301350	CONCRETE SUPERSTRUCTURE (APPROACH SLAB)	CU YD	95.8			95.8
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	37850			37850
50800515	BAR SPLICERS	EACH	290			290
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2			2
54010803	PRECAST CONCRETE BOX CULVERTS 8' X 3'	FOOT	42			42
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	53			53
60260100	INLETS TO BE ADJUSTED	EACH	4			4

2 REVISED 2-19-2021

1 REVISED 2-17-2021

REV. - MS

MODEL: Default
 FILE: \\miller\pub\hshannon.dwg
 ILLINOIS DEPARTMENT OF TRANSPORTATION
 PROJECT: 74945
 CAD: \\miller\pub\hshannon.dwg
 OFFICE: District 7
 PROJECT: 74945
 CAD: \\miller\pub\hshannon.dwg

USER NAME = steffemk	DESIGNED -	REVISED -
PLOT SCALE = 100.0000' / in.	DRAWN -	REVISED -
PLOT DATE = 12/17/2020	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 1 OF 3 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
832	(113.114)RS-4	CLARK	46	3
CONTRACT NO. 74945			ILLINOIS FED. AID PROJECT	