

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				80% FED 20% STATE ROADWAY	80% FED 20% CITY TRAFFIC SIGNALS
				0005	0021
				URBAN	URBAN
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	504	504	
40600990	TEMPORARY RAMP	SQ YD	320	320	
40603200	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, 1L-4.75, N50	TON	2491	2491	
40604000	HOT-MIX ASPHALT SURFACE COURSE, 1L-9.5FG, MIX "C", N50	TON	34	34	
40604172	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, 1L-9.5, MIX "E", N70	TON	3734	3734	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	232	232	
* 42400800	DETECTABLE WARNINGS	SQ FT	42	42	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	400	400	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	43,952	43,952	1
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	72	72	
44000600	SIDEWALK REMOVAL	SQ FT	191	191	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	38	38	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	34	34	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	

\*= SPECIALTY ITEM

MODEL: MODELNAME\$  
FILE NAME: FILE\$

USER NAME = \$USERS	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = \$SCALE\$	CHECKED -	REVISED -
PLOT DATE = \$DATE\$	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET 1 OF 3 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
673	101RS-4	Tazewell	32	3
ILLINOIS FED. AID PROJECT			CONTRACT NO. 68F69	

Mainline Schedule												
Location	Length	Width	Area	Temp Ramp	Bit Mat Tack Coat Special	Polymerized HMA Binder (MM), IL-4.75, N50	Hot-Mix Asphalt Surf Rem Butt Joint	Hot-Mix Asphalt Surf Rem 1.5"	Hot-Mix Asphalt Surf Rem 2.5"	Polymerized HMA Surf Course Mix E, N70, 1.5"	HMA Surf Course IL-9.5FG Mix C, N50	Material Transfer Device
Station	Foot	Foot	Sq FT	Sq Yd	Pound	Ton	Sq Yd	Sq Yd	Sq Yd	Ton	Ton	Ton
Sta 29+65 To Sta 29+95	30	87.3	2619	49	430	17	299			25		42
Sta 29+95 To Sta 37+05	710	87.3	61983		10178	397			7084	595		992
Sta 37+05 To Sta 39+66	261	81.1	21154		3480	136			2423	204		340
Sta 39+66 To Sta 50+16	1050	74.8	78540		12951	505			9018	758		1263
Sta 50+16 To Sta 53+70	354	78.75	27878		4590	179			3196	268		447
Sta 53+70 To Sta 54+75	105	82.7	8684		1428	56			994	83		139
Sta 54+75 To Sta 60+65	590	88.6	52265		8611	336			5996	504		840
Sta 60+65 To Sta 61+23	58	100.4	5823		957	37			666	56		93
Sta 61+23 To Sta 65+67	444	87.4	38795		6395	249			4453	374		623
Sta 65+67 To Sta 70+13	446	76.7	34208		5637	220			3925	330		550
Sta 70+13 To Sta 74+23	410	55.4	22714		3720	145			2587	217		362
Sta 74+23 To Sta 76+50	227	73.4	16650		2731	87		353	1549	130	30	247
Sta 76+50 To Sta 76+80	30	73.4	2201	41	357	11	205	47		17	4	32
<b>Total</b>				90	61465	2375	504	400	41891	3561	34	5970

\*Mixture for shoulders

Sideroad Schedule									
Location				Resurf Area	Temp Ramp	HMA Surf Rem 2.5"	Bit Mat (Tack Coat) Special	Poly HMA Binder (MM) L-4.75, N50	Poly HMA Surf Course Mix E, N70, 1.5"
Sideroads	Station	Side	Width Foot	Sq Ft	Sq Yd	Sq Yd	Pound	Ton	Ton
National St	34+24	LT	113	5875	63	653	940	37	55
Cat Trail Access	34+41	RT	48	980	27	109	157	6	9
Blackjack Blvd	60+14	LT	142	6910	79	768	1106	43	64
Blackjack Blvd	60+14	RT	110	4782	61	531	765	30	45
<b>Total</b>					230	2061	2968	116	173

Traffic Control & Protection			
Location	STD 701602	STD 701701	STD 701801
	L SUM	L SUM	L SUM
Main St (IL 116/US 24/ US 150)	1	1	1
<b>Total</b>	1	1	1

Mobilization	
Location	L SUM
Main St (IL 116/US 24/ US 150)	1
<b>Total</b>	1

Changeable Message Sign	
Location	Cal Days
Main St (IL 116/US 24/ US 150)	150
<b>Total</b>	150

ADA Schedule								
Location			Portland Cement Concrete Sidewalk 5"	Sidewalk Removal	Detectable Warnings	CCC&G Type B 6.24	CCC&G Type SM-6.12	CC&G Rem
Description	Side	Corner	Sq Ft	Sq Ft	Sq Ft	Ft	Ft	Ft
Blackjack Blvd	Lt	SW	81	58	10	17		17
Blackjack Blvd - Island	Lt	SW	71	57	22		38	38
Blackjack Blvd	Rt	SE	80	76	10	17		17
<b>Total</b>			232	191	42	34	38	72

MODEL: Default  
FILE: \\bls01c:\pub\lanscom\dat\illinois\pwr\WIDOT\Documents\DOT\_Offices\lansct\l\Projects\114\_68F69\CADD\Drawings\CAD\Drawings\11468F69-shc-schedule.dgn

USER NAME = wallenfangt	DESIGNED - AOF	REVISED -
	DRAWN - AOF	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 2/17/2021	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULES OF QUANTITIES**

SCALE: SHEET 1 OF 2 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
673	101RS-4	TAZEWELL	32	9
CONTRACT NO. 68F69			ILLINOIS FED. AID PROJECT	

REV. 2/17/21