

SCHEDULE OF QUANTITIES

East Moline Section						
PAY ITEM NUMBER	PAY ITEM NAME					
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTION 12"					
COLUMN ID	A	B	C	D	QTY	
Drawing #	STA.	STA.	LT/RT		EACH	
	23+48				1	
				TOTAL	1	EACH

East Moline-Breezy Hollow Section						
PAY ITEM NUMBER	PAY ITEM NAME					
54213705	PRECAST REINFORCED CONCRETE FLARED END SECTION 60"					
COLUMN ID	A	B	C	D	QTY	
Drawing #	STA.	STA.	LT/RT		EACH	
	23+04				1	
	23+52				1	
				TOTAL	2	EACH

East Moline-Breezy Hollow Section						
PAY ITEM NUMBER	PAY ITEM NAME					
55100500	STORM SEWER REMOVAL, 12"					
COLUMN ID	A	B	C	D	QTY	
Drawing #	STA.	STA.	LT/RT		FOOT	
	23+18		LT		3.0	
				TOTAL	3.0	FOOT

East Moline-Breezy Hollow Section						
PAY ITEM NUMBER	PAY ITEM NAME					
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYLE 1 FRAME, CLOSED LID					
COLUMN ID	A	B	C	D	QTY	
Drawing #	STA.	STA.	LT/RT	EACH	EACH	
	23+18.19				1	
				TOTAL	1	EACH

Breezy Hollow Section						
PAY ITEM NUMBER	PAY ITEM NAME					
60236200	INLET, TYPE A, TYPE 8 GRATE					
COLUMN ID	A	B	C	D	QTY	
Drawing #	STA.	STA.	LT/RT		EA	
	19+61		10' RT		1	
				TOTAL	1	EA

East Moline Section						
PAY ITEM NUMBER	PAY ITEM NAME					
60236200	INLET, TYPE A, TYPE 8 GRATE					
COLUMN ID	A	B	C	D	QTY	
Drawing #	STA.	STA.	LT/RT		EA	
	98+55		LT		1	
	102+83		LT		1	
				TOTAL	2	EA

Silvis Section						
PAY ITEM NUMBER	PAY ITEM NAME					
60236200	INLET, TYPE A, TYPE 8 GRATE					
COLUMN ID	A	B	C	D	QTY	
Drawing #	STA.	STA.	LT/RT		EA	
	125+63.51				1	
	129+59.11				1	
				TOTAL	2	EA

East Moline-Breezy Hollow Section						
PAY ITEM NUMBER	PAY ITEM NAME					
60255500	MANHOLES TO BE ADJUSTED					
COLUMN ID	A	B	C	D	QTY	
Drawing #	STA.	STA.	LT/RT	EACH	EACH	
	18+74.00		5.54L		1	
	19+80.64		7.26L		1	
	20+81.12		4.38L		1	
				TOTAL	3	EACH

East Moline Section						
PAY ITEM NUMBER	PAY ITEM NAME					
60255500	MANHOLES TO BE ADJUSTED					
COLUMN ID	A	B	C	D	QTY	
Drawing #	STA.	STA.	LT/RT	EACH	EACH	
	58+44.05		3.5L		1	
	58+58.30		3.67L		1	
	93+90.75		5.39L		1	
	94+01.71		2.13R		1	
	97+33.42		6.22R		1	
	100+34.10		5.27R		1	
	106+32.91		6.45R		1	
	108+83.20		6.21R		1	
				TOTAL	8	EACH

Silvis Section						
PAY ITEM NUMBER	PAY ITEM NAME					
60255500	MANHOLES TO BE ADJUSTED					
COLUMN ID	A	B	C	D	QTY	
Drawing #	STA.	STA.	LT/RT	EACH	EACH	
	122+18.57		5.44L		1	
	125+63.51		5.66L		1	
	129+60.42		6.07L		1	
	132+99.68		4.97L		1	
				TOTAL	4	EACH

East Moline-Breezy Hollow Section						
PAY ITEM NUMBER	PAY ITEM NAME					
60257900	MANHOLES TO BE RECONSTRUCTED					
COLUMN ID	A	B	C	D	QTY	
Drawing #	STA.	STA.	LT/RT	EACH	EACH	
	17+68.65		1.06L		1	
	17+98.70		2.93R		1	
				TOTAL	2	EACH

East Moline Section						
PAY ITEM NUMBER	PAY ITEM NAME					
60257900	MANHOLES TO BE RECONSTRUCTED					
COLUMN ID	A	B	C	D	QTY	
Drawing #	STA.	STA.	LT/RT	EACH	EACH	
	86+43		6 RT		1	
	98+77		LT		1	
				TOTAL	2	EACH

East Moline Section						
PAY ITEM NUMBER	PAY ITEM NAME					
60260100	INLETS TO BE ADJUSTED					
COLUMN ID	A	B	C	D	QTY	
Drawing #	STA.	STA.	LT/RT	EACH	EACH	
	58+13		LT		1	
	98+77		13'LT		1	
				TOTAL	2	EACH

East Moline-Breezy Hollow Section						
PAY ITEM NUMBER	PAY ITEM NAME					
60300405	VALVE BOX FRAMES TO BE ADJUSTED					
COLUMN ID	A	B	C	D	QTY	
Drawing #	STA.	STA.	LT/RT		EACH	
	27+24.09		2.58R		1	
	27+30		8.3 RT		1	
	27+31		31 RT		1	
				TOTAL	3	EACH

East Moline Section						
PAY ITEM NUMBER	PAY ITEM NAME					
60300405	VALVE BOX FRAMES TO BE ADJUSTED					
COLUMN ID	A	B	C	D	QTY	
Drawing #	STA.	STA.	LT/RT		EACH	
	58+33.36		4.52L		1	
	58+95.33		5.17L		1	
				TOTAL	2	EACH

East Moline-Breezy Hollow Section						
PAY ITEM NUMBER	PAY ITEM NAME					
60605000	Combination Curb & Gutter, Type B-6.24					
COLUMN ID	A	B	C	D	QTY	
Drawing #	STA.	STA.	LT/RT		FOOT	
	17+45.42		17+64.65		30	
	17+94.77		18+07.94		13	
	18+14.05		18+23.10		9	
	18+14.45		18+23.48		8	
	23+05.45		23+51.33		31	
	27+53.79		27+69.75		24	
	28+00.31		28+14.53		20	
	46+19.55		46+30.62		18	
				TOTAL	153	FOOT

East Moline Section						
PAY ITEM NUMBER	PAY ITEM NAME					
60605000	Combination Curb & Gutter, Type B-6.24					
COLUMN ID	A	B	C	D	QTY	
Drawing #	STA.	STA.	LT/RT		FOOT	
	58+09.48		93+28.95		3,520	
	94+08.53		94+21.53		20	
	94+50.03		94+65.40		22	
	98+45.99		99+05.93		60	
	113+73.43		113+55.28		32	
	114+22.41		114+62.14		43	
				TOTAL	3,697	FOOT

SilvisSection						
PAY ITEM NUMBER	PAY ITEM NAME					
60605000	Combination Curb & Gutter, Type B-6.24					
COLUMN ID	A	B	C	D	QTY	
Drawing #	STA.	STA.	LT/RT		FOOT	
	115+29.85		115+61.68		36	
	119+46.95		119+56.98		12	
	119+86.82		119+98.21		18	
	144+10.84		144+30.82		24	
				TOTAL	90	FOOT

East Moline-Breezy Hollow Section						
PAY ITEM NUMBER	PAY ITEM NAME					
66400105	CHAIN LINK FENCE, 4'					
COLUMN ID	A	B	C	D	QTY	
Drawing #	Wall #	STA.	STA.	LT/RT		FOOT
	1	19+68.89	20+47.78			79
	2	22+23.99	23+19.21			144
	3	23+38.25	25+80.82			246
	5	29+00.05	31+89.94			290
	6	36+45.97	39+12.69			267
				TOTAL	1,026	FOOT

East Moline Section						
PAY ITEM NUMBER	PAY ITEM NAME					
66400105	CHAIN LINK FENCE, 4'					
COLUMN ID	A	B	C	D	QTY	
Drawing #	WALL	STA.	STA.	LT/RT		FOOT
	7	48+97.84	59+24.24			426
	8	73+02.92	76+05.40			303
	9	80+49.68	81+95.19			146
	10	86+47.58	88+35.02			188
	11	99+44.44	100+89.53			146
	12	103+58.01	105+88.31			234
	13	106+45.62	106+84.25			46
	14	107+08.35	108+23.18			115
	15	108+59.18	109+75.26			117
	16	111+36.90	112+31.79			95
				TOTAL	1,816	FOOT

Silvis Section						
PAY ITEM NUMBER	PAY ITEM NAME					
66400105	CHAIN LINK FENCE, 4'					
COLUMN ID	A	B	C	D	QTY	
Drawing #	WALL	STA.	STA.	LT/RT		FOOT
	17	138+27.48	141+01.85			275
				TOTAL	275	FOOT

East Moline-Breezy Hollow Section						
PAY ITEM NUMBER	PAY ITEM NAME					
#NVA	SIGN PANEL - TYPE 1					
COLUMN ID	A	B	C	D	QTY	
Drawing #	LOC.	OFF.	TYP.	H	W	SQ FT
	17+57.35		RT	R5-3	24	4
	17+66.92		LT	R1-1	18	2.25
	27+48.56		LT	R5-3	24	4
	27+51.20		RT	R1-1	18	2.25
	28+14.17		RT	R5-3	24	4
	28+17.79		LT	R1-1	18	2.25
	45+95.48		RT	MV1-1	18	2.25
	45+95.48		RT	M1-9	12	1.5
				TOTAL	23	SQ FT

East Moline-Breezy Hollow Section						
PAY ITEM NUMBER	PAY ITEM NAME					
X100003	CLEARING AND GRUBBING					
COLUMN ID	A	B	C	D	QTY	
Drawing #	STA.	STA.	LT/RT		SQ YD	
	17+60		RT		2	
	18+29		RT		14	
				TOTAL	16	SQ YD

East Moline Section						
PAY ITEM NUMBER	PAY ITEM NAME					
X100003	CLEARING AND GRUBBING					
COLUMN ID	A	B	C	D	QTY	
Drawing #	STA.	STA.	LT/RT		SQ YD	
	71+53		72+30		67	
	72+61		73+62		138	
	74+45		76+43		599	
	80+12		81+91		280	
	86+29		88+05		400	
				TOTAL	1,484	SQ YD

Silvis Section						
PAY ITEM NUMBER	PAY ITEM NAME					
X100003	CLEARING AND GRUBBING					
COLUMN ID	A	B	C	D	QTY	
Drawing #	STA.	STA.	LT/RT		SQ YD	
	138+35.79		140+77.85		500	
				TOTAL	500	SQ YD

East Moline Section								
PAY ITEM NUMBER	PAY ITEM NAME							
#NVA	SIGN PANEL - TYPE 1							
COLUMN ID	A	B	C	D	QTY			
Drawing #	LOC.	OFF.	TYP.	H	W	SQ FT		
	PM1		EM WELCOME CTR	M1-9	12	1.5		
	PM1		EM WELCOME CTR	M6-4	12	9.075		
	PM1		QUARTER PATH	LT	D11-1	24	18	3
	PM1		QUARTER PATH	LT	M1-9	12	18	1.5
	PM1		QUARTER PATH	RT	D11-1	24	18	3
	PM1		QUARTER PATH	RT	M1-9	12	18	1.5
	PM2		QUARTER PATH	RT	D11-1	24	18	3
	PM2		QUARTER PATH	RT	M1-9	12	18	1.5
	PM2		QUARTER PATH	LT	D11-1	24	18	3
	PM2		QUARTER PATH	LT	M1-9	12	18	1.5
	PM3		QUARTER PATH	LT	D11-1	24	18	3
	PM3		QUARTER PATH	LT	M1-9	12	18	1.5
	PM3		QUARTER PATH	LT	M6-1	12	9	0.75
	PM3		7TH ST @ QUARTER	RT	D11-1	24	18	1.5
	PM3		7TH ST @ QUARTER	RT	M1-9	12	18	1.5
	PM3		7TH ST @ 13TH AVE	RT	D11-1	24	18	3
	PM3		7TH ST @ 13TH AVE	RT	M1-9	12	18	1.5
	PM3		7TH ST @ 13TH AVE	LT	D11-1	24	18	3
	PM3		7TH ST @ 13TH AVE	LT	M1-9	12	18	1.5
	PM3		7TH ST @ 15TH AVE	RT	D11-1	24	18	3
	PM3		7TH ST @ 15TH AVE	RT	M1-9	12	18	1.5
	PM3		7TH ST @ 15TH AVE	LT	D11-1	24	18	3
	PM3		7TH ST @ 15TH AVE	LT	M1-9	12	18	1