

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES URBAN	0005 100% STATE					CODE NO	ITEM	UNIT	TOTAL QUANTITIES URBAN	0005 100% STATE				
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	540	540					* 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	2035	2035				
40604062	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70	TON	116	116					* 78009005	MODIFIED URETHANE PAVEMENT MARKING - LINE 5"	FOOT	100	100				
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	1033	1033					* 78009008	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	100	100				
X4405020	LONGITUDINAL PARTIAL DEPTH REMOVAL 2"	FOOT	950	950					* 78009012	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	100	100				
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SO YD	10	10					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	15	15				
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	120	120					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	15	15				
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	70	70					* X1400337	WIRELESS IN PAVEMENT DETECTOR	EACH	5	5				
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	30	30					X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1				
X4420900	LONGITUDINAL PARTIAL DEPTH PATCHING	TON	36	36					X7030005	TEMPORARY PAVEMENT MARKING REMOVAL	SO FT	715	715				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					* X8730312	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 4/C, TWISTED, SHIELDED	FOOT	225	225				
67100100	MOBILIZATION	L SUM	1	1					* X8850102	INDUCTION LOOP	FOOT	950	950				
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	180	180					Ø Z0076604	TRAINEES - TRAINING PROGRAM GRADUATE	HOURS	500	500				
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1													
70300904	PAVEMENT MARKING TAPE, TYPE IV 4"	FOOT	2035	2035													
70300905	PAVEMENT MARKING TAPE, TYPE IV 5"	FOOT	100	100													

△ REVISED SHEET

Ø 0042

\* = SPECIALTY ITEMS

REV-SEP

