IDOT LETTING MARCH 5, 2021 ITEM NO. 03A

INDEX TO SHEETS

- COVER SHEET 1.
- 2. GENERAL NOTES AND DETAILS
- 3. SITE PLAN-TYPICAL SECTIONS-PROJECT CONTROL
- 4. CONSTRUCTION ACTIVITY PLAN 1
- **CONSTRUCTION ACTIVITY PLAN 2** 5.
- 6. CONSTRUCTION ACTIVITY PLAN NOTES AND DETAILS
- 7. **EXISTING CONDITIONS-REMOVALS - SHEET 1**
- 8. STORMWATER POLLUTION PREVENTION PLAN
- 9. STORMWATER POLI UTION PREVENTION PLAN NOTES AND DETAILS
- 10. GRADING PLAN 1
- 11. GRADING PLAN 2
- 12. PAVEMENT MARKING AND LIGHTING PLAN

Lansing

APPROVED BY

TITLE

CRAWFORD MURPHY & TILLY, INC

CONSULTING ENGINEERS

SUBMITTED BY

DATE

Municipal Airport

raveny 5

JANUAM

DANIEL PODGORSKI

CITY ADMINISTRATOR

ANTONIO R. MARIN, P.E.

20 -1/

190297-02-00

LICENSE EXPIRATION DATE: 11-30-2021

20 2/


VILLAGE OF LANSING LANSING, ILLINOIS

CONSTRUCTION PLANS FOR LANSING MUNICIPAL AIRPORT

REHABILITATE PORTIONS OF TAXIWAY C AND F; REMOVE TAXIWAY F2 AND ABANDONED TAXIWAYS

ILLINOIS PROJECT: IGQ-4658 SBGP PROJECT: 3-17-SBGP-156

JANUARY 8, 2021



LOCATION MAP

.vn wood

East

Heights

Burnhar

Calumet

City

 $\sim \sim$ RЛ

Lansing

*

LANSING

AIRPOR

83

Ν 312

Munster

Dyer

SITE PLAN

19029702\GI000.DWG

DATE

LA042 TOTAL SHEETS = 12

SUMMARY OF QUANTITIES

			ESTIMATED	RECORD
ITEM NO.	DESCRIPTION	UNIT	QUANTITY	QUANTITY
AR108066	REIL CABLE	LF	700	
AR108158	1/C #8 5 KV UG CABLE IN UD	LF	775	
AR110901	CONCRETE DUCT REMOVAL	LF	60	
AR125565	SPLICE CAN	EACH	2	
AR125901	REMOVE STAKE MOUNTED LIGHT	EACH	7	
AR125902	REMOVE BASE MOUNTED LIGHT	EACH	2	
AR125912	REMOVE RETROREFLECTIVE MARKER	EACH	6	
AR125941	ADJUST STAKE MOUNTED LIGHT	EACH	1	
AR150510	ENGINEER'S FIELD OFFICE	LS	1	
AR152410	UNCLASSIFIED EXCAVATION	CY	740	
AR152540	SOIL STABILIZATION FABRIC	SY	120	
AR156520	INLET PROTECTION	EACH	6	
AR208515	POROUS GRANULAR EMBANKMENT	CY	40	
AR209606	CRUSHED AGG. BASE COURSE - 6"	SY	120	
AR401610	BITUMINOUS SURFACE COURSE	TON	245	
AR401650	BITUMINOUS PAVEMENT MILLING	SY	2000	
AR401900	REMOVE BITUMINOUS PAVEMENT	SY	2200	
AR401910	REMOVE & REPLACE BIT. PAVEMENT	SY	120	
AR603510	BITUMINOUS TACK COAT	GAL	400	
AR620520	PAVEMENT MARKING - WATERBORNE	SF	800	
AR620525	PAVEMENT MARKING - BLACK BORDER	SF	1400	
AR620900	PAVEMENT MARKING REMOVAL	SF	400	
AR751940	ADJUSTINLET	EACH	1	
AR800140	2 1/C #6 XLP-USE, 1/C #10 GND - 1" UD	LF	140	
AR901510	SEEDING	ACRE	1.2	
AR905530	TOPSOILING	SY	5800	
AR908515	HEAVY-DUTY HYDRAULIC MULCH	ACRE	1.2	



84

Know what's below. Call before you dig.

J.U.L.I.E. JOINT UTILITY LOCATING INFORMATION FOR EXCAVATORS www.illinois1call.com

THE LOCATION SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ON THE PLANS IS NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE ACTUAL LOCATIONS OF ALL SUCH FACILITIES. INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY UTILITY COMPANIES OF HIS OPERATIONAL PLANS, OBTAIN FROM RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE BELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE O THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVEN AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JUBISDICTION AND THE ONE-CALL NOTICE SYSTEM THE ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY SUCH UTILITY OR SERVICES SHALL BI RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT

CALL J.U.L.I.E. FOR UTILITY INFORMATION AT 811


DESIGN INFORMATION APPROACH CATEGORY B **DESIGN GROUP II**

LANSING MUNICIPAL AIRPORT

TOWNSHIP: 35 NORT RANGE: 15 EAST COOK COUNT

BLOOM TOWNSHIP (SECTION: 8 AND 17) OPPOSITE GLENWOOD-LANSING ROAD


UNICOM RADIO FREQUENCY - 122.7




NOT TO SCALE

SHEET

OF



HORIZONTAL CONTROL (NAD 27)			
POINT	STATION	NORTHING	EASTING
CP-1	STA. 7+31.80 & TAXIWAY A	1776370.03	717848.66
CP-2	STA. 2+50 မူ TAXIWAY F	1775888.25	717851.57
CP-3	STA. 5+50 ငူ TAXIWAY C	1776345.11	718838.09
CP-4	STA. 10+00 & TAXIWAY C	1775895.11	718841.22



NOTES

- CONTRACTOR SHALL NOTIFY THE AIRPORT MANAGER THROUGH THE RESIDENT ENGINEER PRIOR TO THE INITIATION OF ANY WORK WHICH REQUIRES CLOSURE OF ACTIVE AIRFIELD PAVEMENT
- 2. ALL WORK AREAS SHALL BE SWEPT AND CLEANED TO THE SATISFACTION OF THE AIRPORT PRIOR TO RE-OPENING PAVEMENT TO AIRCRAFT OPERATIONS.
- 3. BUNWAY 18/36 SHALL BEMAIN OPEN AT ALL TIMES.
- CONTRACTOR SHALL NOTIFY THE AIRPORT AND RESIDENT ENGINEER A MINIMUM OF 2 CALENDAR DAYS IN ADVANCE OF THE ANTICIPATED WORK ON TAXIWAY C ADJACENT TO TAXIWAY IN ORDER TO NOTIFY 4. AIRFIELD TENANTS
- 5 TAXIWAY C: ADDITIONAL CONTRACTOR RESTRICTIONS (WORK AREA 2)
- a. WHEN WORKING BETWEEN TAXIWAY A EDGE OF PAVEMENT AND TAXIWAY C. CONTRACTOR SHALL BE REQUIRED TO BE IN RADIO CONTACT WITH AIRFIELD TRAFFIC.
- b. CONTRACTOR SHALL BE REQUIRED TO MOVE PERSONNEL, EQUIPMENT AND MATERIALS TO PROVIDE A MINIMUM 65.5 FOOT OF CLEARANCE FROM THE TAXIWAY A CENTERLINE TO ALLOW THE PASSAGE OF THE AIRCRAFT.
- c. CONTRACTOR SHALL BE REQUIRED TO FURNISH FLAGGERS TO DIRECT AND CONTROL ALL CONSTRUCTION EQUIPMENT AND PERSONNEL TO THE REQUIRED SET BACK DISTANCE FOR THE SAFE PASSAGE OF AIRCRAFT, AIRFIELD PERSONNEL AND/OR AIRPORT PERSONNEL AIRPORT PERSONNEL SHALL ALSO BE ON-SITE AND IN CONJUNCTION WITH THE CONTRACTOR'S FLAGGER SHALL ACT AS A WING WALKER FOR AIRCRAFT PASSING THROUGH THE WORK ZONE
- CONTRACTOR SHALL MAINTAIN AIRFIELD GATES CLOSED WHEN NOT IN 6. USE. IF THE CONTRACTOR REQUIRES THE GATE TO REMAIN OPEN FOR LONG DURATIONS, A GATE GUARD SHALL BE PROVIDED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT.

ELECTRICAL NOTES

- CONTRACTOR SHALL COVER ALL AIRFIELD SIGNS AND TAXIWAY LIGHTS ON CLOSED TAXIWAYS UNTIL THE TAXIWAY IS RE-OPENED FOR AIRCRAFT USE. THE METHOD AND MATERIALS USED TO COVER THE SIGNS AND LIGHTS SHALL MEET THE ENGINEER'S AND AIRPORT'S APPROVAL, COST INCIDENTAL TO THE CONTRACT. REMOVING LAMPS FROM ENERGIZED FIXTURES AS A MEANS TO REMOVE THE LIGHTS OR FIXTURES FROM SERVICE SHALL NOT BE ACCEPTABLE
- CONTRACTOR SHALL TURN OFF RUNWAY EDGE LIGHTING REGULATOR AND LOCK-OUT/TAG-OUT CIRCUIT BREAKER AND CUT OUT INSIDE THE ELECTRICAL VAULT, DUBING ALL BUNWAY CLOSUBES, CONTRACTOR SHALL COORDINATE ACCESS TO THE VALUE WITH THE AIRPORT MANAGER/RESIDENT ENGINEER PRIOR TO RE-OPENING THE RUNWAY, THE CONTRACTOR SHALL COORDINATE WITH AIRPORT MANAGER/RESIDENT ENGINEER TO RE-ENERGIZE THE RUNWAY CIRCUIT.

ALLOWABLE

WORK PERIODS

NO RESTRICTIONS

AOA

AOA

тхү к

RUNWAY 18/36

125'

125'

WORK

AREA

AREA 1

202ND STREET

TXY L

LYNWOOD

5 8

SUGGESTED SEQUENCE OF CONSTRUCTION

- NOTIFY RESIDENT ENGINEER/AIRPORT MANAGER 10 DAYS PRIOR TO THE START OF CONSTRUCTION TO ISSUE APPROPRIATE NOTAMS.
- WORK AREA 1
 - REQUIRED PAVEMENT CLOSURES FOR WORK AREA.

 - COVER AND/OR DE-ENERGIZE SIGNS AND LIGHTS FOR CLOSED TAXIWAYS AND RUNWAYS.
 - COMPLETE IMPROVEMENTS
 - WORK AREA LIMITS.

 - COORDINATE WITH RESIDENT ENGINEER AND AIRPORT MANAGER PAVEMENT CLOSURES FOR NEXT WORK AREA.
 - RELOCATE BARRICADES AND PAVEMENT CLOSURE MARKERS FOR NEXT WORK AREA
- RESTORE STAGING AREAS.


⊗—⊗—⊗

7.1.7.1.7.2


_____ AOA _____

X

 \bigcirc







GENERAL NOTES

- THE SUGGESTED SEQUENCE OF CONSTRUCTION SHOWN IS INTENDED TO ALLOW FOR THE ORDERLY CONSTRUCTION OF THE PROPOSED IMPROVEMENTS WHILE MAINTAINING AIRCRAFT ACCESS AT ALL TIMES. THE PHASING SHOWN IS A SUGGESTED SEQUENCE OF CONSTRUCTION ONLY. THIS SEQUENCE MAY BE MODIFIED. HOWEVER, AI TERNATE STAGING PLANS MUST MAINTAIN AIRPORT OPERATIONS TO THE SATISFACTION OF THE AIRPORT MANAGER AND RESIDENT ENGINEER AND BE APPROVED BY THE DIVISION OF AERONAUTICS AND FEDERAL AVIATION ADMINISTRATION.
- 2. ALL OPERATIONS SHALL BE IN CONFORMANCE WITH AC 150/5370-2G (LATEST EDITION) OPERATIONAL SAFETY ON
- 3. CONTRACTOR'S EQUIPMENT SHALL BE STORED IN THE EQUIPMENT AND MATERIAL STORAGE AREA WHEN CONSTRUCTION IS NOT IN PROGRESS
- THE AIRPORT MANAGER IN CONSULTATION WITH THE RESIDENT ENGINEER SHALL HAVE FINAL SAY IN THE APPROVAL OF THE CONSTRUCTION OPERATING SEQUENCE AS IT RELATES TO PEDESTRIAN. VEHICULAR AND AIRCRAFT SAFETY.
- ALL EXISTING PAVEMENTS, DRIVES OR ANY OTHER AREAS USED AS A HAUL ROAD OR STORAGE AREA BY THE CONTRACTOR SHALL BE RESTORED IN KIND TO THEIR PRE-CONSTRUCTION CONDITION OR TO THE SATISFACTION OF THE RESIDENT ENGINEER AND AIRPORT MANAGER. THE COST OF MAINTAINING, REPAIRING OR CONSTRUCTING THESE PAVEMENTS AND AREAS SHALL BE INCIDENTAL TO THE CONTRACT. EXISTING AREAS OUTSIDE THE PROJECT LIMITS WHICH ARE DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED BY HIM AT HIS EXPENSE TO THE SATISFACTION OF THE RESIDENT ENGINEER AND THE AIRPORT MANAGER.
- THE CONTRACTOR SHALL KEEP ALL TRUCKS, EQUIPMENT AND MATERIALS OFF OF THE EXISTING TAXIWAYS, APRONS AND RUNWAYS OUTSIDE OF THE PROJECT LIMITS EXCEPT AS SHOWN OR WITH THE PRIOR PERMISSION OF THE ENGINEER
- WORK PERFORMED BY THE CONTRACTOR OUTSIDE OF DAYLIGHT HOURS SHALL BE DONE UNDER SUFFICIENT ARTIFICIAL LIGHTING TO ALLOW FOR PROPER CONSTRUCTION METHODS AND INSPECTIONS. LIGHT SHALL CONSIST OF MOVABLE POLE MOUNTED FLOODLIGHTS AND/OR SPOTLIGHTS OF SUFFICIENT NUMBER TO ILLUMINATE THE WORK AREA. VEHICLE HEADLIGHTS WILL BE ALLOWED ONLY IN ADDITION TO OTHER LIGHTS MENTIONED ABOVE LIGHTING SHALL BE AS APPROVED BY THE ENGINEER AND SHALL NOT BE USED IF THEY AFFECT FLIGHT SAFETY CONTRACTOR'S WORK HOURS SHALL BE IN ACCORDANCE WITH LOCAL ORDINANCES.
- THE CONTRACTOR SHALL PROVIDE PORTABLE FLOOD LIGHTING FOR NIGHTTIME CONSTRUCTION. SUFFICIENT UNITS SHALL BE PROVIDED SO THAT WORK AREAS ARE ILLUMINATED TO A LEVEL OF FIVE HORIZONTAL FOOT CANDLES. THE LIGHTING LEVELS SHALL BE CALCULATED AND MEASURED IN ACCORDANCE WITH THE CURRENT STANDARDS OF THE ILLUMINATION ENGINEERING SOCIETY. LIGHTS SHALL BE POSITIONED SO AS NOT TO INTERFERE WITH AIRPORT
- 9. THE CONTRACTOR WILL BE REQUIRED TO HAVE A SWEEPER AVAILABLE FOR USE AT ALL TIMES. WHEN ACTIVE AIRFIELD PAVEMENTS ARE UTILIZED AS HAUL ROADS BY THE CONTRACTOR, MATERIAL TRACKED ON TO THE PAVEMENT SHALL BE CONTINUALLY REMOVED WITH SAID SWEEPER. THIS SWEEPING SHALL NOT BE PAID FOR SEPERATELY BUT SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT.
- 10. MATERIALS REMOVED FROM THE PROJECT WILL BE DISPOSED OF OFF AIRPORT PROPERTY, UNLESS NOTED
- FOR WORK ON AIRPORT PROPERTY: PAYMENT FOR TRAFFIC CONTROL INCLUDING, BUT NOT LIMITED TO BARRICADES, SIGNING, TAXIWAY AND RUNWAY CLOSED MARKERS, AIR OPERATIONS AREA (A.O.A.) LATHE AND RIBBON, ETC. SHALL NOT BE PAID SEPARATELY, BUT SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT. BARRICADES AT 10-FOOT CENTERS WITH ONE ORANGE FLAG (20" x 20") BETWEEN EACH SET OF BARRICADES SHALI BE PLACED AT THE LOCATIONS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER. BARRICADES SHALL BE WEIGHTED TO PREVENT BLOWING OVER. BARRICADES SHALL HAVE A FLASHING RED LIGHT AND CONFORM TO IDOT STANDARD 702001, TYPE II. BARRICADE INSTALLATION WILL BE REQUIRED PRIOR TO ACCESS TO THE A.O.A. BY CONTRACTOR'S WORKERS, FOUIPMENT OR MATERIAL, SIGNS SHALL BE PLACED AT EACH TAXIWAY/BUNWAY CLOSURE LOCATION AND SHALL BE ATTACHED TO THE BARRICADES. EACH BARRICADE LOCATION SHALL CONSIST OF ONE "DO NOT ENTER" SIGN AND ONE "AIRCRAFT MOVEMENT AREA" SIGN. SIGNS SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT.
- 12. THE CONTRACTOR SHALL CONTACT THE AIRPORT MANAGER TEN (10) WORKING DAYS IN ADVANCE OF THE START OF CONSTRUCTION SO THAT THE APPROPRIATE NOTAMS MAY BE ISSUED.
- 13. THE CONTRACTOR SHALL BE RESPONSIBLE FOR KEEPING ALL CONSTRUCTION ACCESS GATES CLOSED DURING NON WORKING HOURS. THE CONTRACTOR SHALL PROVIDE A SIGN AT THE ACCESS GATE SAVING "AUTHORIZED PERSONNEL ONLY". THE CONTRACTOR SHALL CLOSE AND LOCK THE ACCESS GATE UPON LEAVING THE SITE THROUGHOUT THE DUBATION OF THE CONTRACT, ANY DAMAGES TO THE ACCESS BOAD, ACCESS GATE OF FENCING ADJACENT TO THE PROJECT SHALL BE REPARED BY THE CONTRACTOR TO THE SATISFACTION OF THE RESIDENT ENGINEER, ALL COST RELATING TO CONTRACTOR'S ACCESS AND SECURITY SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR
- 14. CONTRACTOR WILL BE REQUIRED TO PUT AIRPORT FLAGS AND HAVE BEACON LIGHTS ON ALL EQUIPMENT AT ALL TIMES DURING CONSTRUCTION. SEE FLAG DETAIL, THIS SHEET.
- 15. IN THE CASE OF AN EMERGENCY, CONTRACTOR SHALL NOTIFY AIRPORT MANAGER AND THE ENGINEER IMMEDIATELY
- 16. DURING ADVERSE WEATHER, THE CONTRACTOR SHALL MAKE PROVISIONS FOR ACCESS TO THE WORK AT NO ADDITIONAL COST TO THE CONTRACT. NO EXTENSION OF CONTRACT TIME WILL BE CONSIDERED FOR DELAYS DUE TO LACK OF ADEQUATE ACCESS TO THE WORK
- 17. THE TALLEST PIECE OF CONSTRUCTION EQUIPMENT IS ANTICIPATED TO BE A TRUCK WHICH HAS A MAXIMUM HEIGHT OF 15 FEET
- 18. IF RUNWAY NUMERALS ARE PRESENT DURING CONSTRUCTION THEN CONTRACTOR SHALL PLACE CLOSED RUNWAY MARKER OVER NUMERALS AS DETAILED, OTHERWISE PLACE RUNWAY CLOSED MARKER IN TURF AT ENDS OF RUNWAY AS DETAILED
- 19. LANSING MUNICIPAL AIRPORT WILL BE IN OPERATION DURING THE CONSTRUCTION OF THIS PROJECT. COORDINATION OF WORK WITH THE AIRPORT IS MANDATORY SO AS TO MINIMIZE IMPACTS ON AIRPORT OPERATIONS.
- 20. APPROXIMATE LOCATION OF HAUL ROUTES ON THE AIRPORT SITE ARE SHOWN ON THE CONSTRUCTION ACTIVITY. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE OFF-SITE HAUL ROUTES (STATE HIGHWAYS, COUNTY BOADS OR CITY STREETS) WITH THE APPROPRIATE OWNER WHO HAS JUBISDICTION OVER THE AFFECTED ROUTE: ON-SITE ROADS USED AS HAUL ROUTES SHALL BE MAINTAINED BY THE CONTRACTOR AND SHALL BE RESTORED AT THE CONTRACTOR'S EXPENSE TO THEIR ORIGINAL CONDITION UPON COMPLETION OF BEING USED AS A HAUL ROUTE. THE BEFORE AND AFTER CONDITION OF ON-SITE HAUL ROUTES SHALL BE JOINTLY INSPECTED AND DETERMINED BY THE CONTRACTOR AND THE ENGINEER. FENCING, DRAINAGE, GRADING AND OTHER MISCELLANEOUS CONSTRUCTION REQUIRED TO CONSTRUCT TEMPORARY HAUL ROUTES OR ACCESS POINTS ON THE AIRPORT WILL BE THE CONTRACTOR'S TOTAL RESPONSIBILITY AND SHALL BE APPROVED BY THE ENGINEER PRIOR TO THE WORK, ALL ON-SITE ACCESS ROADS TO AIRPORT FACILITIES SHALL REMAIN OPEN AND MAINTAINED AT ALL TIMES
- 21. MOBILIZATION/EQUIPMENT STORAGE AREA WILL BE MADE AVAILABLE FOR CONTRACTOR'S MOBILIZATION AND STORAGE AS SHOWN ON THE PLANS. THIS AREA SHALL BE RESTORED TO THE ORIGINAL CONDITION UPON COMPLETION OF THE PROJECT. THE RESTORATION SHALL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- 22. LOCATION OF KNOWN EXISTING AIRPORT UNDERGROUND CABLES ARE SHOWN ON THE PLANS AND MUST BE VERIFIED BY THE CONTRACTOR. REPAIL ONDER GROUND CABLES AND SHOWN ON THE PLANS AND MUST BE VERIFIED BY THE CONTRACTOR. REPAIL OF DAMAGED CABLE MUST BE STARTED IMMEDIATELY AND CONTINUED UNTIL COMPLETED. ALL SUCH REPAIRS SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS, OR AS DIRECTED BY THE OWNER OF THE CABLE, AND SHALL BE AT THE CONTRACTOR'S EXPENSE. IF FAA CABLES ARE DAMAGED, BEPAIRS SHALL BE DONE FROM POINT TO POINT IN ACCORDANCE WITH FAA BEQUIREMENTS AND IN THE PRESENCE OF A FAA REPRESENTATIVE. THE OWNER MAY ELECT TO HAVE THE REPAIR PERFORMED BY OTHERS IN WHICH CASE THE CONTRACTOR SHALL BE RESPONSIBLE FOR PAYING THE INCURRED COSTS OF REPAIRS.

- 23. COORDINATION MEETINGS THE CONTRACTOR SHALL CONDUCT WEEKLY COORDINATION MEETINGS TO DISCUSS WORK AREAS AND SCHEDULING, ETC. WITH THE ENGINEER, AIRPORT OPERATIONS, FAA, AND OTHER APPROPRIATE OFFICIALS. MINUTES FROM THE WEEKLY MEETINGS SHALL BE PREPARED BY THE CONTRACTOR, FURNISHED TO ALL ATTENDEES PRIOR TO THE SUBSEQUENT MEETING, AND KEPT ON FILE AT THE FIELD OFFICE. THE COORDINATION MEETING COSTS SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT.
- 24. THE CONTRACTOR SHALL PROVIDE THE PHONE NUMBERS OF THREE PERSONNEL, INCLUDING THE PROJECT SUPERINTENDENT, WHO MAY BE CONTACTED IN AN EMERGENCY, PERSONNEL SHALL BE ON CALL 24 HOURS PER DAY FOR MAINTAINING AIRPORT HAZARD LIGHTING AND BARRICADES.
- 25. DRAINAGE MODIFICATIONS SHALL BE SEQUENCED TO PROVIDE POSITIVE DRAINAGE AT ALL TIMES AT NO ADDITIONAL COST TO THE CONTRACT. EXISTING LANSING DRAINAGE FLOWS SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION
- 26. VEHICLES AND EQUIPMENT SHALL NOT BE ALLOWED WITHIN 65.5' FROM ACTIVE TAXIWAYS, 57.5' FROM ACTIVE TAXILANES, 200' FROM ACTIVE RUNWAY 18/36 AND 75' FROM ACTIVE RUNWAY 9/27 UNLESS OTHERWISE APPROVED BY THE AIRPORT MANAGER.
- 27. CONTRACTOR SHALL STORE EQUIPMENT AND MATERIALS IN SUCH A MANNER AS NOT TO VIOLATE FEDERAL AVIATION ADMINISTRATION PART 77 SURFACES OR RUNWAY AND TAXIWAY SAFETY AREAS.
- 28. ALL EXISTING TAXIWAY AND RUNWAY AIRFIELD LIGHTING CIRCUITS, FAA CABLES AND OTHER ELECTRICAL CABLES SHALL REMAIN IN SERVICE AT ALL TIMES. ALL EXISTING LIGHTING AND VALUE COUPMENT SHALL REMAIN IN SERVICE UNTIL PROPOSED IMPROVEMENTS ARE INSTALLED AND OPERATIONAL, UNLESS OTHERWISE APPROVED BY THE ENGINEER. ANY CABLES DAMAGED BY THE CONTRACTOR SHALL BE IMMEDIATELY REPAIRED AT HIS EXPENSE.
- 29. COORDINATION BY THE CONTRACTOR WITH THE EXISTING UTILITIES SHALL BE COMPLETED BEFORE CONSTRUCTION IS STARTED. CONTRACTOR IS REFERRED TO SECTIONS 50-06, 70-06, AND 70-17 OF STANDARD SPECIFICATIONS REQUIREMENTS. THE LOCATION OF UNDERGROUND UTILITIES AS INDICATED ON THE PLANS HAS BEEN OBTAINED FROM EXISTING RECORDS. NEITHER THE OWNER OR THE DESIGN ENGINEER ASSUME ANY RESPONSIBILITY WHATEVER IN ERSPECT TO THE ACCURACY, COMPLETENESS OR SUFFICIENCY OF THE INFORMATION. THER IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED THAT THE LOCATIONS, SIZE AND TYPE MATERIAL OF EXISTING UNDERGROUND UTILITIES AS INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED DURING CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE OF INDEX TO BE ENCOUNTERED DOINT ACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH RECLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES, PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANY OF HIS OPERATIONAL PLANS. THE CONTRACTOR SHALL MAKE ARRANGEMENTS FOR DETAILED INFORMATION AND ASSISTANCE IN LOCATING UTILITIES. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY, THE RESIDENT ENGINEER AND THE AIRPORT MANAGER. ANY SUCH MAINS AND/OR SERVICES DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED IMMEDIATELY AT HIS EXPENSE TO THE SATISFACTION OF THE RESIDENT ENGINEER AND AIRPORT MANAGER.
- 30. ALL AIRFIELD LIGHTING AND LIGHTING GUIDANCE SYSTEMS (NAVAIDS) LOCATED WITHIN AND IMMEDIATELY ADJACENT TO THE CONTRACTORS WORK ZONE SHALL BE CHECKED FOR OPERATIONAL CONDITION PRIOR TO THE DEPARTURE FROM THE AIRPORT WITH THE AIRPORT MANAGER AND/OR AIRPORT MAINTENANCE. ANY DEFECIENCIES IN THESE SYSTEMS DUE TO THE ACTS OF CONTRACTOR OR HIS SUBCONTRACTORS, SUPPLIERS OR CONSULTANTS SHALL BE REPAIRED IMMEDIATELY.

CONTRACTOR CROSSING RUNWAY AND TAXIWAY AIR OPERATIONS AREA (A.O.A.)

ANYTIME THE CONTRACTOR IS REQUIRED TO UTILIZE OR CROSS ACTIVE AIRFIELD PAVEMENTS FOR ACCESS TO AND FROM THE WORK ZONE, A CROSSING GUARD OR ESCORT IN RADIO CONTACT WITH THE AIR FIELD SHALL BE FURNISHED BY THE CONTRACTOR FOR MOVEMENTS OF VEHICLES OR EQUIPMENT TO AND FROM THE WORK ZONE. THE RADIO OPERATOR SHALI BE FAMILIAB WITH AIRPORT GROUND CONTROL PROCEDURES AND DEMONSTRATE KNOWLEDGE OF SAME TO THE AIRPORT THE AIRPORT RESERVES THE RIGHT TO APPROVE THE CROSSING GUARDS. THE CONTRACTOR SHALL PROVIDE THEIR OWN RADIOS. THIS COST SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PAYMENT OF MUNICIPAL FINES (\$500 PER OCCURENCE) DUE TO AIRFIELD INCURSIONS BY HIS EMPLOYEES, SUBCONTRACTORS, SUPPLIERS, CONSULTANTS AND/OR AGENTS.

ANY PAVEMENT DAMAGED BY CONTRACTOR'S OPERATIONS SHALL BE REPAIRED IMMEDIATELY BY HIM TO THE SATISFACTION ANT INVENIENT PARAMAGED DI COMMINICATI DO L'IGNI DA LOTINO SI DEDE DI LI ANTE DI MILLO MILE DI MILLO MILLO DI DA MILLO ANTE DI ANTE DA MILLO ANTE DI MILLO D

WORK WITHIN THE A.O.A. SHALL BE EXPEDITED. ANY DROP OFF SHALL BE ADEQUATELY LIGHTED, SIGNED AND BARRICADED. NO MATERIAL SHALL BE STOCKPILED WITHIN THE A.O.A. SHOULD IT BE NECESSARY FOR THE CONTRACTOR TO TEMPORARILY RELOCATE EQUIPMENT TO ALLOW AIRCRAFT TO PASS, THEY SHALL DO SO AT NO EXTRA COST TO THE PROJECT. THE CONTRACTOR SHALL NOTIFY THE RESIDENT ENGINEER AND AIRPORT MANAGER TWO (2) WORKING DAYS IN ADVANCE OF ANY PLANNED CONSTRUCTION WITHIN THESE LIMITS.

LIMITATIONS ON CONSTRUCTION WITHIN RUNWAY SAFETY AREA (RSA)


AND TAXIWAY/TAXILANE OBJECT FREE AREA (TOFA)

RUNWAYS

THE CONTRACTOR SHALL NOTIFY THE RESIDENT ENGINEER AND AIRPORT MANAGER TEN (10) WORKING DAYS IN ADVANCE OF ANY PLANNED CONSTRUCTION WITHIN THESE LIMITS. WORK SHALL BE EXPEDITED IN THESE AREAS AND AT THE END OF EACH WORKING DAY THESE AREAS SHALL BE SMOOTHLY GRADED TO ALLOW THE RUNWAY TO BE REOPENED. AT LEAST ONE OF THE RUNWAYS SHALL REMAIN IN OPERATION AT ALL TIMES. IF NECCESSARY STEEL PLATES SHALL BE FURNISHED AND INSTALLED BY THE CONTRACTOR TO COVER ANY OPEN TRENCHES OR EXCAVATION WITHIN THE BSA IF DUBING BUNWAY CLOSUBE AN EMERGENCY IS DECLARED. THE CONTRACTOR SHALL IMMEDIATELY CLEAR THE RUNWAY OF ALL VEHICLES, MEN AND EQUIPMENT. REFERENCE TABLE ON PREVIOUS SHEET FOR SAFETY AREA WIDTHS.

TAXIWAYS / TAXILANES:

ANY WORK WITHIN TAXIWAY / TAXILANE OBJECT FREE AREA (TOFA) WILL REQUIRE A TAXIWAY / TAXILANE CLOSURE. WORK WITHIN THE TOFA SHALL BE EXPEDITED. ANY DROP OFF SHALL BE ADEQUATELY LIGHTED, SIGNED AND BABBICADED NO MATERIAL SHALL BE STOCKPILED WITHIN THE TOFA, SHOULD IT BE NECESSABY FOR THE CONTRACTOR TO TEMPORARILY RELOCATE EQUIPMENT TO ALLOW AIRCRAFT TO PASS, THEY SHALL DO SO AT NO EXTRA COST TO THE PROJECT. THE CONTRACTOR SHALL NOTIFY THE RESIDENT ENGINEER AND AIRPORT MANAGER FIVE (5) WORKING DAYS IN ADVANCE OF ANY PLANNED CONSTRUCTION WITHIN THESE LIMITS. OBJECT FREE AREA WIDTHS ARE NOTED ON THIS SHEET. NO DROP-OFFS OR OPEN EXCAVATIONS WILL BE ALLOWED WITHIN THE TAXIWAY / TAXILANE SAFETY AREAS OF OPEN TAXIWAY / TAXILANES.




CONSTRUCTION EQUIPMENT AND TRUCK SIGNAL ORANGE AND WHITE CHECKERED FLAG NOT TO SCALE

CONTRACTOR SHALL PLAN AND PERFORM HIS WORK SO AS NOT TO INTERFERE OR HINDER THE PROGRESS, WORK OR HAUL ROAD ACCESS OF OTHER CONTRACTORS (SEE SECTION 50-05). THE PRIME CONTRACTOR WILL BE RESPONSIBLE TO COORDINATE CONSTRUCTION ACTIVITIES AND ACCESS BETWEEN ALL ON-SITE CONTRACTORS SUBCONTRACTORS

LA042 DESIGN AIRCRAFT APPROACH CATAGORY: B DESIGN AIRPORT GROUP. II RUNWAY 18/36 SAFETY AREA TOTAL WIDTH = 150 RUNWAY 9/27 SAFETY AREA TOTAL WIDTH = 150' TAXIWAY CENTERLINE TO OBJECT SEPARATION = 65.5 TAXILANE CENTERLINE TO OBJECT SEPARATION = 57.5 License No. 184-000613 CONSULTANTS MAXIMUM ANTICIPATED HEIGHT OF CONSTRUCTION EQUIPMENT: 15' POINT "A' POINT "C" NEAREST POINT ON CONSTRUCTION SITE TO ACTIVE LATITUDE: 41° 32' 22.90" **RUNWAY 18/36** LONGITUDE: - 87º 31' 51 21" EXISTING ELEVATION: 613.9 POINT "B POINT "D" NEAREST POINT ON CONSTRUCTION SITE TO ACTIVE RUNWAY 18/36 LATITUDE: 41° 32' 25.61" LONGITUDE: - 87° 31' 39.40" EXISTING ELEVATION:613.6 EXISTING ELEVATION:615.3 FINAL FLASHER BARRICADE NOTES FLASHERS TO BE BATTERY OPERATED. LENS TO BE RED AND BE ABLE TO ROTATE 90 DEGREES 2. SANDBAGS TO BE PLACED ON EACH SUPPORT BRACE AS REQUIRED TO PREVENT DISPLACEMENT BY WIND, JET OR PROP BLAST. 3. CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING BARRICADES AT ALL TIMES TO THE SATISFACTION OF THE AIRPORT. **JANUARY 8, 2021** 4. NO SEPARATE PAYMENT WILL BE MADE FOR THIS ITEM. COSTS SHALL BE CONSIDERED INCIDENTAL TO THE **REHABILITATE PORTIONS OF** PROJECT. TAXIWAY C AND F; REMOVE 5. PLACE AT 10' INTERVALS. TAXIWAY F2 AND ABANDONED 6. ALTERNATE FLASHER LENSES SO THAT EVERY OTHER TAXIWAYS LENS IS ROTATED 90°. OWNER VILLAGE OF LANSING ON PAVEMENT CLOSED RUNWAY MARKER DETAIL Lansing NOT TO SCALE **Municipal Airport** CLOSED RUNWAY MARKER DETAIL NOTES LANSING MUNICIPAL AIRPORT LANSING, ILLINOIS CONTRACTOR SHALL MAINTAIN AND RELOCATE MARKERS AS SHOWN ON THE PLANS OR AS NEEDED TO FACILITATE CONSTRUCTION 4. MARKERS ON PAVEMENT SHALL BE PLACED OVER EXISTING RUNWAY NUMERALS AS SHOWN. MARK DATE DESCRIPTION COST OF FURNISHING, INSTALLING, MAINTAINING AND REMOVING MARKERS SHALL BE CONSIDERED AIP PROJ. NO. 3-17-SBGP-156 DURING VARIOUS PHASES OF WORK, IT WILL BE NECESSARY TO CLOSE RUNWAYS TO AIR TRAFFIC ON A TEMPORARY BASIS AS COORDINATED WITH THE AIRPORT. THE CONTRACTOR SHALL MARK THE IL, PROJ, NO, IGQ-4658 CMT PROJECT NO: 190297-02-00 RUNWAYS TO BE CLOSED BY PLACING A YELLOW CROSS AT THE LOCATION AND DIMENSIONS DETAILED ON THIS SHEET. THE CROSSES ARE SHOWN ON THE RESPECTIVE RUNWAYS ACCORDING TO THE CAD DWG FILE: GC103.DWG ARIOUS PHASES OF WORK AS DELINEATED IN THE SUGGESTED SEQUENCE OF CONSTRUCTION DESIGNED BY: ARM JRO DRAWN BY: AIRFIELD LIGHTS AND SIGNS NOTES CHECKED BY: DKP APPROVED BY: ARM CONTRACTOR SHALL COVER ALL AIRFIELD SIGNS AND TAXIWAY LIGHTS ON CLOSED TAXIWAYS UNTIL THE TAXIWAY IS RE-OPENED FOR AIRCRAFT USE. THE METHOD AND MATERIALS USED TO COPYRIGHT COVER THE SIGNS AND LIGHTS SHALL MEET THE ENGINEER'S AND AIRPORT'S APPROVAL COST INCIDENTAL TO THE CONTRACT. REMOVING LAMPS FROM ENERGIZED FIXTURES AS A MEANS TO SHEET TITLE REMOVE THE LIGHTS OR FIXTURES FROM SERVICE SHALL NOT BE ACCEPTABLE CONSTRUCTION 2. CONTRACTOR SHALL TURN OFF RUNWAY EDGE LIGHTING REGULATOR AND LOCK-OUT/TAG-OUT CIRCUIT BREAKER AND CUT OUT INSIDE THE ELECTRICAL VAULT. DURING ALL RUNWAY CLOSURES. CONTRACTOR SHALL COORDINATE ACCESS TO THE VAULT WITH THE AIRPORT MANAGER/RESIDENT ENGINEER PRIOR TO RE-OPENING THE RUNWAY, THE CONTRACTOR SHALL ACTIVITY PLAN COORDINATE WITH AIRPORT MANAGER/RESIDENT ENGINEER TO RE-ENERGIZE THE RUNWAY NOTES AND DETAILS GC103

NEAREST POINT ON CONSTRUCTION SITE TO ACTIVE **RUNWAY 18/36** LATITUDE: 41° 32' 23.06' LONGITUDE: - 87° 31' 39.41" EXISTING ELEVATION:616.1 NEAREST POINT ON CONSTRUCTION SITE TO ACTIVE RUNWAY 18/36 LATITUDE: 41° 32' 21.69" LONGITUDE: - 87° 32' 01.39"



NOT TO SCALE


SHEET 6

12


OF



- 1. CLOSED RUNWAY MARKERS SHALL BE YELLOW.
- 2. MARKERS SHALL BE MATERIAL APPROVED BY THE ENGINEER
- 5. INCIDENTAL TO THE CONTRACT.



LA042



STORM WATER POLLUTION PREVENTION PLAN

THE FOLLOWING PLAN IS ESTABLISHED AND INCORPORATED IN THE PROJECT TO DIRECT THE CONTRACTOR IN THE PLACEMENT OF TEMPORARY EROSION CONTROL SYSTEMS AND TO PROVIDE A STORM WATER POLLUTION PREVENTION PLAN FOR COMPLIANCE WITH NPDES

THE PURPOSE OF THIS PLAN IS TO MINIMIZE EROSION WITHIN THE CONSTRUCTION SITE AND TO LIMIT SEDIMENTS FROM LEAVING THE SITE BY UTILIZING PROPER TEMPORARY EROSION CONTROL SYSTEMS AND PROVIDING GROUND COVER WITHIN A REASONABLE AMOUNT OF TIME

CERTAIN EROSION CONTROL FACILITIES SHALL BE INSTALLED BY THE CONTRACTOR AT THE BEGINNING OF CONSTRUCTION OTHER ITEMS SHALL BE INSTALLED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER ON A CASE BY CASE SITUATION DEPENDING ON THE CONTRACTOR'S SEQUENCE OF ACTIVITIES, TIME OF YEAR, AND EXPECTED WEATHER CONDI

THE CONTRACTOR SHALL INSTALL PERMANENT FROSION CONTROL SYSTEMS AND SEEDING WITHIN A TIMEFRAME SPECIFIED HEREIN AND AS DIRECTED BY THE ENGINEER, THEREFORE MINIMIZING THE AMOUNT OF AREA SUSCEPTIBLE TO EROSION AND REDUCING THE AMOUNT OF TEMPORARY SEEDING, WHICH WILL BE AT THE CONTRACTOR'S COST. THE ENGINEER WILL DETERMINE IF ANY TEMPOBABY EBOSION CONTBOL SYSTEMS SHOWN IN THE PLAN CAN BE DELETED AND IF ANY ADDITIONAL TEMPOBABY EROSION CONTROL SYSTEMS, WHICH ARE NOT INCLUDED IN THIS PLAN, SHALL BE ADDED. THE CONTRACTOR SHALL PERFORM ALL WORK AS DIRECTED BY THE ENGINEER AND AS SHOWN ON THE PLANS.

SITE DESCRIPTION

THE FOLLOWING IS A DESCRIPTION OF THE CONSTRUCTION ACTIVITY WHICH IS THE SUBJECT OF THIS PLAN:

THIS PROJECT CONSISTS OF THE MILLING AND OVERLAY OF AN EXISTING BITUMINOUS PAVEMENT AT THE LANSING MUNICIPAL AIRPORT. THE PROJECT INCLUDES EXCAVATION, TOPSOILING, GRADING, LANDSCAPING, VARIOUS PAVEMENT ITEMS PAVEMENT MARKING AND OTHER MISCELLANEOUS CONSTRUCTION WORK

DESCRIPTION OF CONSTRUCTION ACTIVITY

THE FOLLOWING IS A DESCRIPTION OF THE INTENDED SEQUENCE OF MAJOR ACTIVITIES WHICH WILL DISTURB SOILS FOR MAJOR PORTIONS OF THE CONSTRUCTION SITE, SUCH AS EXCAVATION AND GRADING:

PLACEMENT, MAINTENANCE, REMOVAL AND PROPER CLEAN-UP OF TEMPORARY EROSION CONTROL.

VARIABLE DEPTH BITUMINOUS PAVEMENT MILLING AND PAVING.

AS NEEDED TURF SHOULDER ADJUSTMENT, SEEDING AND MULCHING.

INSTALLATION OF NEW PAVEMENT MARKING.

REMOVAL AND DISPOSAL OF TEMPORARY SOIL EROSION AND SEDIMENT CONTROL MEASURES.

AREA OF CONSTRUCTION SITE

THE TOTAL AREA OF THE CONSTRUCTION SITE IS ESTIMATED TO BE 1.7 ACRES OF WHICH 1.2 ACRES WILL BE DISTURBED BY GRADING ACTIVITIES.

OTHER REPORTS, STUDIES AND PLANS WHICH AID IN THE DEVELOPMENT OF THE STORM WATER POLLUTION PREVENTION PLAN AS REFERENCED DOCUMENTS:

- 1. INFORMATION OF THE SOILS AND TERRAIN WITHIN THE SITE WAS OBTAINED FROM TOPOGRAPHIC SURVEYS AND SOIL BORINGS THAT WERE UTILIZED FOR THE DEVELOPMENT OF THE PROPOSED TEMPORARY EROSION CONTROL SYSTEMS
- 2. PROJECT PLAN DOCUMENTS, SPECIFICATION AND SPECIAL PROVISIONS, AND PLAN DRAWINGS INDICATING DRAINAGE PATTERNS AND APPROXIMATE SLOPES ANTICIPATED AFTER GRADING ACTIVITIES WERE UTILIZED FOR THE PROPOSED PLACEMENT OF THE TEMPORARY EROSION CONTROL SYSTEMS.

DRAINAGE TRIBUTARIES AND SENSITIVE AREAS RECEIVING RUNOFF FROM THIS CONSTRUCTION SITE:

THE CONSTRUCTION SITE DRAINS INTO THE LANSING DRAINAGE DITCH THROUGH A STORM SEWER SYSTEM

EROSION AND SEDIMENT CONTROL:

DESCRIPTION OF STABILIZATION PRACTICES AT THE BEGINNING OF CONSTRUCTION:

THE DRAWINGS SPECIFICATIONS AND SPECIAL PROVISIONS WILL ENSURE THAT EXISTING VEGETATION IS PRESERVED. THE DRAWINGS SPECIFICATIONS AND SPECIAL PROVISIONS WILL ENSURE THAT EASTING VEGETATION IS PRESERVED WHERE ATTAINABLE AND DISTURBED PORTIONS OF THE SITE WILL BE STABILIZED. STABILIZATION PRACTICES INCLUDE: TEMPORARY SEEDING, PERMANENT SEEDING, MULCHING, SOD, PROTECTION OF TREES, PRESERVATION OF NATURAL VEGETATION, AND ALL OTHER APPROPRIATE MEASURES AS DIRECTED BY THE ENGINEER. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORABILY DE INTITLE AS SOON AS THAT HAT HONOLE IN THIS OF THE STEE WHENE CONSTRUCTION ACTIVITIES HAVE TEMPORATION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED.

AREAS OF EXISTING VEGETATION (WOOD AND GRASSLANDS) OUTSIDE THE PROPOSED CONSTRUCTION LIMITS SHALL BE IDENTIFIED BY THE ENGINEER FOR PRESERVING AND SHALL BE PROTECTED FROM CONSTRUCTION ACTIVITIES.

DEAD, DISEASED, OR UNSUITABLE VEGETATION WITHIN THE SITE SHALL BE REMOVED AS DIRECTED BY THE ENGINEER.

THIS PLAN HAS BEEN PREPARED TO COMPLY WITH THE PROVISIONS OF THE NPDES GENERAL PERMIT NUMBER ILR10, ISSUED BY THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY FOR STORM WATER DISCHARGES FROM CONSTRUCTION SITE ACTIVITIES

DESCRIPTION OF STABILIZATION PRACTICES DURING CONSTRUCTION:

DURING CONSTRUCTION, AREAS OUTSIDE THE CONSTRUCTION LIMITS AS OUTLINED PREVIOUSLY HEREIN SHALL BE PROTECTED. THE CONTRACTOR SHALL NOT USE THIS AREA FOR STAGING (EXCEPT AS DESCRIBED ON THE PLANS AND DIRECTED BY THE ENGINEER), PARKING OF VEHICLES OR CONSTRUCTION EQUIPMENT, STORAGE OF MATERIALS, OR OTHER CONSTRUCTION RELATED ACTIVITIES

WITHIN THE CONSTRUCTION LIMITS, AREAS WHICH MAY BE SUSCEPTIBLE TO EROSION AS DETERMINED BY THE ENGINEER SHALL REMAIN UNDISTURBED UNTIL FULL SCALE CONSTRUCTION IS UNDERWAY TO PREVENT UNNECESSARY SOIL EROSION.

						JULY	AUG.	SEPT.	OCT.	NOV.
			A		•		A			•
N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
		В								►
										•
1IX (SEE IC	OT STD.	. SPEC.	AIRPORT	IS SECT	ION 901-	2.1 FOR	SEEDIN	G MIXTU	JRE)	
			IIX (SEE IDOT STD. SPEC. /			B B C C C C C C C C C C C C C C C C C C			$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	B Image: Constraint of the second s

EARTH STOCKPILES SHALL BE <u>TEMPORARILY SEEDED, AT THE CONTRACTOR'S EXPENSE</u>, IF THEY ARE TO REMAIN UNUSED FOR MORE THAN SEVEN (7) DAYS.

THE DOWN STREAM SIDE OF ALL STOCKPILES SHALL BE ENCOMPASSED WITH EROSION CONTROL BARRIER

AS CONSTRUCTION PROCEEDS, THE CONTRACTOR SHALL INSTITUTE THE FOLLOWING AS DIRECTED BY THE ENGINEER

A. PLACE TEMPORARY EROSION CONTROL FACILITIES AT LOCATIONS SHOWN ON THE PLANS.

CONSTRUCTION EQUIPMENT SHALL BE STORED AND FUELED ONLY AT DESIGNATED LOCATIONS WITHIN THE STAGING AREA. ALL NECESSARY MEASURES SHALL BE TAKEN TO CONTAIN ANY FUEL OR POLLUTANT IN ACCORDANCE WITH EPA WATER QUALITY REGULATIONS. LEAKING EQUIPMENT OR SUPPLIES SHALL BE IMMEDIATELY REPAIRED OR REMOVED FROM THE SITE.

THE RESIDENT ENGINEER SHALL INSPECT THE PROJECT PERIODICALLY DURING CONSTRUCTION ACTIVITIES. INSPECTION SHALL ALSO BE DONE WEEKLY AND AFTER RAINS OF 1/2" OR GREATER OR EQUIVALENT SNOWFALL AND DURING WINTER SHUTDOWN PERIOD. THE PROJECT SHALL ADDITIONALLY BE INSPECTED BY THE BESIDENT ENGINEER ON A BI-WEEKLY BASIS TO DETERMINE THAT THE EBOSION AND SEDIMENT CONTROL EFFORTS ARE IN PLACE AND EFFECTIVE AND IF OTHER EROSION CONTROL WORK IS NECESSARY.

SEDIMENT COLLECTED DURING CONSTRUCTION OF THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED OFF SITE ON A REGULAR BASIS. THE COST OF THIS MAINTENANCE SHALL BE INCIDENTAL TO THE CONTRACT.

THE TEMPORARY EROSION CONTROL SYSTEMS SHALL BE REMOVED AS DIRECTED BY THE ENGINEER AFTER USE IS NO LONGER NEEDED OR NO LONGER FUNCTIONING. THE COST OF THIS REMOVAL SHALL BE INCIDENTAL TO THE CONTRACT

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PREVENTING SOIL CONTAMINATION FROM BUILDING MATERIALS, FERTILIZERS, CHEMICALS, PAVEMENT MARKING, WASTE PILES, FUEL CONTAINMENT, AND ANY OTHER POTENTIAL HAZARDOUS MATERIALS THAT MAY EXIST ONSITE.

NO DEDICATED CONCRETE OR ASPHALT BATCH PLANTS SHALL BE LOCATED ON THIS SITE.

DESCRIPTION OF STRUCTURAL PRACTICES AFTER FINAL GRADING:

TEMPORARY EROSION CONTROL SYSTEMS SHALL BE LEFT IN PLACE WITH PROPER MAINTENANCE UNTIL PERMANENT EROSION CONTROL IS IN PLACE AND WORKING PROPERLY AND ALL PROPOSED TURF AREAS ARE SEEDED AND ESTABLISHED.

COST OF MAINTAINING THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE INCIDENTAL TO THE CONTRACT.

ONCE PERMANENT EROSION CONTROL SYSTEMS AS PROPOSED IN THE PLANS ARE FUNCTIONAL AND ESTABLISHED, TEMPORARY ITEMS SHALL BE REMOVED, CLEANED UP, AND DISTURBED TURF RE-SEEDED AND/OR SODDED.

MAINTENANCE AFTER CONSTRUCTION:

CONSTRUCTION IS COMPLETE AFTER FINAL ACCEPTANCE BY THE ILLINOIS DIVISION OF AERONAUTICS. MAINTENANCE OF TEMPORARY AND PERMANENT EROSION CONTROL SYSTEMS UP TO THIS DATE WILL BE REQUIRED BY THE CONTRACTOR.

DOCUMENTATION:

DEC.

N/A

┢

A MINIMUM OF 30 DAYS SHALL BE SUBMITTED.

THROUGHOUT CONSTRUCTION. THE CONTRACTOR SHALL MAINTAIN AND UPDATE AN "AS-BUILT" SET OF STORM WATER POLLUTION PREVENTION PLANS IN THE PROJECT FILES. THE SWPPP SHALL BE UPDATED WITHIN 7-DAYS OF ANY MODIFICATIONS TO THE PLANS. THE SWPPP AND ALL REVISIONS SHALL BE RETAINED FOR THREE YEARS AFTER FINAL STABILIZATION OF THE SITE, WHICH SHALL BE DEFINED AS VEGETATION COVER OF AT LEAST 70% OF HISTORIC CONDITIONS.

A STORM WATER POLLUTION PREVENTION PLAN EROSION CONTROL INSPECTION REPORT (FORM AER 2259) SHALL BE BE COMPLETED WITH INSPECTION EREQUENCIES AS OUTLINED HEREIN, SWPPP REPORTS SHALL BE RETAINED FOR THREE YEARS AFTER THE DATE OF FINAL STABILIZATION AS DEFINED HEREIN.

IF ANY VIOLATION OF THE PROVISIONS OF THE PLAN IS IDENTIFIED DURING THE CONDUCT OF THE CONSTRUCTION COVERED IN THIS PLAN, THE ENGINEER AND/OR CONTRACTOR SHALL COMPLETE FOR THE PROJECT FILE AN "INCIDENT OF NONCOMPLIANCE (ION)" REPORT FOR THE IDENTIFIED VIOLATION. THE FORMS SHALL BE FILLED OUT AND SHALL INCLUDE SPECIFIC INFORMATION ON THE INCIDENT THAT CAUSED NONCOMPLIANCE, ACTIONS THAT WERE TAKEN TO CORRECT THE NONCOMPLIANCE AND TO PREVENT ITS REOCCURRENCE, AND A STATEMENT DETAILING ANY ENVIRONMENTAL IMPACT WHICH MAY HAVE RESULTED FROM THE NONCOMPLIANCE. ALL REPORTS OF NONCOMPLIANCE SHALL BE SIGNED BY A RESPONSIBLE AUTHORITY IN ACCORDANCE WITH PART VI. G. OF THE GENERAL PERMIT.

NPDES PERMIT #

DATE ISSUED DATE EXPIRED

GENERAL NOTES FOR SOIL EROSION AND SEDIMENT CONTROL:

- ALL TREE PROTECTION, SEDIMENT CONTROL MEASURES, AND PERMANENT AND TEMPORARY STORM WATER PRACTICES SHALL BE IN PLACE PRIOR TO STARTING CONSTRUCTION.
- NO WORK SHALL BE PERFORMED IN FLOWING WATER, WORK IN AND NEAR FLOWING WATER SHALL BE ISOLATED FROM CONCENTRATED FLOWS OR STREAM FLOWS AT ALL TIMES. THE USE OF EARTHEN MATERIAL FOR ISOLATION WILL NOT BE ACCEPTABLE.
- STREAM FLOW
- PROLONG GRADING OR SHAPING SO THAT THE ENTIRE PROJECT CAN BE PERMANENTLY SEEDED AT ONE TIMI
- ADJACENT STREETS SHALL BE KEPT FREE OF SOIL AND DEBRIS
- SHOULD IT BE NECESSARY TO REMOVE ANY EROSION CONTROL DEVICES FOR CONSTRUCTION REASONS, THE CONTRACTOR SHALL FIRST OBTAIN PERMISSION AND SHALL REPLACE AND/OR REPAIR THE REMOVED DEVICES THE SAME DAY. THE COST OF REMOVING AND REPLACING THE DEVICE SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- 8. ALL OTHER SOIL EROSION AND SEDIMENT CONTROL DEVICES AND MEASURES DEEMED NECESSARY BY THE RESIDENT ENGINEER, COOK COUNTY, LANSING MUNICIPAL AIRPORT/VILLAGE OF LANSING, IDOT DIVISION OF AERONAUTICS, AND THE IEPA SHALL BE IMPLEMENTED IMMEDIATELY UPON NOTIFICATION OF THE CONTRACTOR.
- 9 THE CONTRACTOR SHALL PROVIDE LOCATIONS FOR CONCRETE TRUCK WASHOUT AS APPROVED BY THE ENGINEER PRIOR TO ANY CONCRETE POURS. THESE LOCATIONS SHALL NOT BE NEAR ANY STREAM OR BODY OF WATER. LOCATIONS SHALL BE APPROVED BY THE ENGINEER PRIOR TO ANY CONCRETE POURS. ADDITIONALLY THE CONTRACTOR SHALL PROVIDE ADEQUATE FACILITIES TO WASH OUT PAVING EQUIPMENT AND FINISHING TOOLS, ALL WASTE WATER AND EXCESS CONCRETE MATERIALS SHALL BE CONTAINED BY AN APPROVED CONCRETE WASHOUT FACILITY.
- CONSISTENT BETWEEN ALL PROJECT PHASES AND ALL SUB-CONTRACTORS.
- 11. THE CONTRACTOR SHALL TAKE ALL PRECAUTIONS TO PROTECT WETLANDS TO REMAIN FROM DAMAGE BY SEDIMENT, CONSTRUCTION EQUIPMENT, OR BY HIS PERSONNEL, THE CONTRACTOR SHALL ASSURE THAT DEBRIS OR ANY CONSTRUCTION MATERIAL IS NOT DISPOSED OF IN THE WETLANDS.
- 12. WATER PUMPED OR OTHERWISE DISCHARGED FROM THE SITE DURING CONSTRUCTION DEWATERING SHALL BE FILTERED BY AN APPROVED MEANS.
- 13. SEDIMENT COLLECTED DURING CONSTRUCTION BY THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED OF ON A BEGULAR BASIS SEDIMENT SHALL BE REMOVED FROM FROSION CONTROL SYSTEMS WHEN THE HEIGHT OF THE SEDIMENT EXCEEDS ONE-HALF OF THE HEIGHT OF THE DEVICE OR AS RECOMMENDED BY THE MANUFACTURER, WHICHEVER IS LESS
- 14. ALL EROSION CONTROL MEASURES SHALL BE KEPT OPERATIONAL AND MAINTAINED CONTINUOUSLY THROUGHOUT THE RIOD OF LAND DISTURBANCE UNTIL PERMANENT SOIL EROSION AND SEDIMENT CONTROL MEASURES ARE OP
- 15. THE CONDITION OF THE CONSTRUCTION SITE FOR WINTER SHUTDOWN SHALL BE ADDRESSED EARLY IN THE FALL GROWING SEASON SO THAT SLOPES AND OTHER BARE EARTH AREAS MAY BE STABILIZED WITH TEMPORARY AND/OR PERMANENT VEGETATIVE COVER. ALL OPEN AREAS THAT ARE TO REMAIN IDLE THROUGHOUT THE WINTER SHALL RECEIVE TEMPORARY FROSION CONTROL MEASURES INCLUDING TEMPORARY SEEDING, MULCHING AND/OR FROSION CONTROL BLANKET PRIOR TO THE END OF THE FALL GROWING SEASON. THE AREAS TO BE WORKED BEVOND THE END OF THE GROWING SEASON MUST INCORPORATE SOIL STABILIZATION MEASURES THAT DO NOT RELY ON VEGETATIVE COVER SUCH AS EROSION CONTROL BLANKET AND HEAVY MULCHING.

16. PERMANENT STABILIZATION SHALL BE COMPLETED WITHIN 7 DAYS FOR AREAS WHERE WORK IS COMPLETED.

CONTRACTOR CERTIFICATION STATEMENT
THIS CERTIFICATION STATEMENT IS A PART OF THE STORM WATER PO BELOW IN ACCORDANCE WITH NPDES PERMIT NO. ILR10 ISSUED BY THI

PROJECT INFORMATION:		REH.
ROUTE: LANSING MUNICIPAL AIRPORT	MARKED:	REM
SECTION: 8	PROJECT N	UMBE
COUNTY: COOK	CONTRACT	NUME

I CERTIFY UNDER PENALTY OF LAW THAT I UNDERSTAND THE TERMS AND CONDITIONS OF THE GENERAL NATIONAL POLI UTION DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT (ILR10) THAT AUTHORIZES THE STORM WATER DISCHARGES ASSOCIATED WITH INDUSTRIAL ACTIVITY FROM THE CONSTRUCTION SITE IDENTIFIED AS PART OF THIS CERTIFICATION.

SIGNATURE:	DATE:
PRINTED NAME:	TITLE:
NAME OF FIRM:	_
STREET ADDRESS:	-
CITY, STATE, ZIP:	
PHONE NUMBER:	
THE INFORMATION WITHIN THIS BOX SHALL BE COMP	PLETED BY THE CO

THE INFORMATION WITHIN THIS BOX SHALL BE COMPLETED BY THE C
COMPLETION OF THIS IS A CONTRACT REQUIREMENT.

DIRECTLY ON THE SWPPP SITE MAP

	DECIMINIC DATE
MAJOR GRADING ACTIVITIES:	BEGINNING DATE:
LOCATION:	COMPLETION DATE:
MAJOR GRADING ACTIVITIES:	BEGINNING DATE:
LOCATION:	COMPLETION DATE:
SITE STABILIZATION:	BEGINNING DATE:
LOCATION:	COMPLETION DATE:
SITE STABILIZATION:	BEGINNING DATE:
LOCATION:	COMPLETION DATE:
CONSTRUCTION CEASED: EXPLANATION:	BEGINNING DATE:

LA042

CONSTRUCTION MATERIALS AND/OR OTHER STOCKPILES SHALL NOT BE LOCATED ON STREAM BANKS NOR IN THE PATH OF

4. TEMPORARY EROSION CONTROL DEVICES SHALL BE CONSTRUCTED AS SHOWN ON THE PLANS OR AS DIRECTED BY THE

5 PERMANENT SEEDING SHALL BE LISED WHENEVER POSSIBLE LINDER NO CIRCUMSTANCES SHALL THE CONTRACTOR

6. THE CONTRACTOR SHALL INSPECT ADJACENT STREETS DAILY AND CLEAN ADJACENT STREETS WHEN NECESSARY.

10. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES TO ENSURE THAT EROSION CONTROL MEASURES ARE

LUTION PREVENTION PLAN FOR THE PROJECT DESCRIBED ILLINOIS ENVIRONMENTAL PROTECTION AGENCY.

ABILITATE PORTIONS OF TAXIWAY C AND F OVE TAXIWAY F2 AND ABANDONED TAXIWAY

B· IGQ-4658

BER: 3-17-SBGP- 156

INTRACTOR AFTER THE AWARD OF THE CONTRACT



License No. 184-000613 CONSULTANTS

FINAL

JANUARY 8, 2021

REHABILITATE PORTIONS OF TAXIWAY C AND F; REMOVE TAXIWAY F2 AND ABANDONED TAXIWAYS



VILLAGE OF LANSING



LANSING MUNICIPAL AIRPORT LANSING, ILLINOIS

MARK DATE DESCRIPTION AIP PROJ. NO. 3-17-SBGP-156 IL. PROJ. NO. IGQ-4658 CMT PROJECT NO: 190297-02-00 CAD DWG FILE: L102.DWG

DESIGNED BY:	ARM
DRAWN BY:	JRO
CHECKED BY:	DKP
APPROVED BY:	ARM
COPYRIGHT	

SHEET TITLE


9

SHEET

STORMWATER POLLUTION PREVENTION PLAN NOTES AND DETAILS

> L102 OF

12



Taxiv E-28.1 Path: Date:

